

MECHANICAL SYMBOLS LIST

AC-1	TXF-1	CONTROLS AND SENSORS	
			THERMOSTAT
			HUMIDISTAT
			DUCT SMOKE DETECTOR
AIR DEVICES		DUCTWORK	
		*****	AIR DUCT W/ 1.5" ACOUSTICAL LINING
			FLEXIBLE DUCT
DUCT ACCESSORIES			FLEXIBLE CONNECTION
			RECTANGULAR DUCT (WIDTH X DEPTH)
			ROUND DUCT (DIAMETER)
			ROUND DUCT CROSS SECTION
			SUPPLY AIR RECTANGULAR DUCT CROSS SECTION
			RETURN AIR RECTANGULAR DUCT CROSS SECTION
HVAC PIPING		MECHANICAL ABBREVIATIONS	
		RTU	ROOF TOP UNIT
		AFF	ABOVE FINISHED FLOOR
		AL	ACOUSTIC LINING
		CFM	CUBIC FEET OF AIR PER MINUTE
		COP	COEFFICIENT OF PERFORMANCE
		DN	DOWN
		EER	ENERGY EFFICIENCY RATIO
		EF	EXHAUST FAN
		EX	EXHAUST
		FA	FRESH AIR
		FC	FLEXIBLE CONNECTION
		HSPF	HEATING SEASONAL PERFORMANCE FACTOR
		IEER	INTEGRATED ENERGY EFFICIENCY RATIO
		MD	MOTORIZED DAMPER
		REF	REFRIGERANT PIPING
		SEER	SEASONAL ENERGY EFFICIENCY RATIO
		SAE	SAME AS EXISTING
		(N)	NEW
		(E)	EXISTING
		BD	BACKDRAFT DAMPER
		SA	SUPPLY AIR
		RA	RETURN AIR
		OA	OUTSIDE AIR
		WMS	WIRE MESH SCREEN
		GD	GRAVITY/ BACKDRAFT DAMPER
		WT	WEIGHT

FIELD VERIFY ALL CONDITIONS

- DESIGN DRAWINGS ARE SCHEMATIC. THIS CONTRACTOR SHALL VISIT THE SITE PRIOR TO BIDDING OR AWARD OF CONTRACT TO INSPECT EXISTING FIELD CONDITIONS. THIS CONTRACT SHALL INCLUDE ALL LABOR AND MATERIALS NECESSARY FOR FIELD MODIFICATIONS DUE TO EXISTING CONDITIONS.
- THE CONTRACTOR SHALL CONTACT THE ARCHITECT, ENGINEER OR OWNER PRIOR TO BIDDING FOR INTERPRETATIONS AND CLARIFICATIONS OF THE DESIGN AND INCLUDE IN HIS BID ALL COSTS TO MEET THE DESIGN INTENT. CLARIFICATIONS MADE BY THE ARCHITECT, ENGINEER OR OWNER AFTER BIDDING WILL BE FINAL AND SHALL BE IMPLEMENTED AT CONTRACTORS COST.
- BIDDING CONTRACTORS SHALL HAVE A WORKING KNOWLEDGE OF LOCAL CODES AND ORDINANCES AND SHALL INCLUDE IN THEIR BIDS THE COSTS FOR ALL WORK INSTALLED IN STRICT ACCORDANCE WITH GOVERNING CODES. THE PLANS AND SPECIFICATIONS NOT WITHSTANDING, THE CONTRACTOR SHALL ALERT ARCHITECT, ENGINEER OR OWNER OF ANY APPARENT DISCREPANCIES BETWEEN GOVERNING CODES AND DESIGN INTENT.

CODE COMPLIANCE

- 2021 INTERNATIONAL BUILDING CODE
- 2021 INTERNATIONAL MECHANICAL CODE.
- 2021 INTERNATIONAL PLUMBING & FUEL GAS CODE
- 2023 NFPA 70 NATIONAL ELECTRICAL CODE
- 2021 INTERNATIONAL ENERGY CONSERVATION CODE

MECHANICAL DRAWING LIST

M-0.1	GENERAL NOTES, SYMBOLS AND ABBREVIATION
M-0.2	MECHANICAL SPECIFICATIONS
M-1.1	MECHANICAL FLOOR PLAN AND SCHEDULES
M-2.1	MECHANICAL DETAILS

WOODLAWN, MD BUILDING
DEPARTMENT NOTES

ALL WORK SHALL COMPLY WITH APPLICABLE SECTIONS OF 2021-IBC WITH THE WOODLAWN, MD LOCAL AMENDMENTS AND RULES AND REGULATIONS OF THE DEPARTMENT OF BUILDINGS TO DATE.

- THE CONTRACTOR SHALL ENGAGE THE SERVICES OF A PROFESSIONAL ENGINEER, ARCHITECT OR OTHER PERSON HAVING INCORPORATED INTO AND MADE A PART OF THESE SPECIFICATIONS, AND THEIR PROVISIONS SHALL BE CARRIED OUT BY THE CONTRACTOR WHO SHALL BE RESPONSIBLE PRIOR TO SUBMITTING A PROPOSAL OF ANY WORK OR MATERIALS WHICH VIOLATE ANY OF THE ABOVE LAWS AND REGULATIONS. ANY WORK DONE BY THE CONTRACTOR CAUSING SUCH VIOLATION SHALL BE CORRECTED BY THE CONTRACTOR.
- BEFORE PROCEEDING WITH ANY WORK IN OCCUPIED OR USED AREAS, THE CONTRACTOR SHALL APPLY TO OWNER FOR PERMISSION TO ENTER SUCH AREAS. THE CONTRACTOR IS OBLIGED TO PERFORM HIS WORK ONLY AT THE TIMES DESIGNATED BY OWNER. THERE WILL BE NO ADDITIONAL COMPENSATION FOR THE WORK PERFORMED AFTER HOURS OR ON OFF-DAYS WITHOUT PRIOR WRITTEN APPROVAL.
- THE WORK IN THE BUILDING SHALL BE DONE WHEN AND AS DIRECTED, AND IN A MANNER SATISFACTORY TO THE OWNER. THE WORK SHALL BE PERFORMED SO AS TO CAUSE THE LEAST POSSIBLE INCONVENIENCE AND DISTURBANCE TO THE PRESENT OCCUPANTS.
- THE CONTRACTOR'S PROPOSAL FOR ALL WORK SHALL BE PREDICATED ON THE PERFORMANCE OF THE WORK DURING REGULAR WORKING HOURS. WHEN SO DIRECTED, HOWEVER, THE CONTRACTOR SHALL INSTALL WORK IN OVERTIME AND THE ADDITIONAL COST TO BE CHARGED THEREFORE SHALL BE ONLY THE "PREMIUM" PORTION OF THE WAGES PAID.
- CONTRACTOR SHALL ASCERTAIN THE APPROPRIATE METHOD FOR BRINGING THE UNITS INTO AND THROUGH THE BUILDING TO POSITION UNIT IN LOCATION SHOWN ON THE PLANS. WHERE NECESSARY, EQUIPMENT SHALL BE SHIPPED FROM MANUFACTURER IN SECTIONS OF SIZE SUITABLE FOR MOVING THROUGH RESTRICTIVE SPACES. COORDINATE WITH BUILDING OWNER APPROPRIATE TIMES OF DAY SUCH EQUIPMENT MAY BE MOVED THROUGH ALL AREAS.
- REMOVAL AND RELOCATION OF CERTAIN EXISTING WORK WILL BE NECESSARY FOR THE PERFORMANCE OF THE GENERAL WORK. ALL EXISTING CONDITIONS CANNOT BE COMPLETELY DETAILED ON THE DRAWINGS. THE CONTRACTOR SHALL SURVEY THE SITE AND INCLUDE ALL CHANGES IN MAKING UP THE WORK PROPOSAL.
- DISCONNECT, REMOVE AND/OR RELOCATE EXISTING MATERIAL, EQUIPMENT AND OTHER WORK AS NOTED OR REQUIRED FOR PROPER INSTALLATION OF NEW SYSTEM.
- CONNECT NEW WORK TO EXISTING WORK

SECTION 0101 — QUALITY OF WORK

- 1.1 WORKMANSHIP
- A. ALL WORK SHALL BE FREE FROM DEFECTS IN MATERIALS AND WORKMANSHIP FOR A PERIOD OF ONE YEAR FROM DATE OF FINAL ACCEPTANCE.
- B. ALL DEFECTS WHICH DEVELOP OR ARE DISCOVERED WITHIN THIS PERIOD SHALL BE REPAIRED BY THE CONTRACTOR TO THE SATISFACTION OF THE ARCHITECT OR BUILDING MANAGER AT NO ADDITIONAL COST TO THE OWNER.
- C. UPON COMPLETION OF THE WORK THE CONTRACTOR SHALL REMOVE FROM THE SITE, ALL TOOLS, DEMOLISHED APPLIANCES AND ANY SURPLUS MATERIAL.
- 1.2 CODE COMPLIANCE
- A. ALL WORK SHALL MEET ALL STATE AND LOCAL CODES HAVING JURISDICTION.
- END OF SECTION 0101

SECTION 078413—PENETRATION FIRE—STOPPING

- 1.1 QUALITY ASSURANCE
- A. INSTALLER QUALIFICATIONS: AN FM GLOBAL—APPROVED FIRE—STOP CONTRACTOR OR A UL—QUALIFIED FIRE—STOP CONTRACTOR.
- B. FIRE—TEST—RESPONSE CHARACTERISTICS: UL, INTERTEK ETL SEMKO OR FM GLOBAL
- 1.2 PENETRATION FIRESTOPPING
- A. PENETRATIONS IN FIRE—RESISTANCE—RATED WALLS: F—RATINGS PER ASTM E 814 OR UL 1479.
- B. PENETRATIONS IN HORIZONTAL ASSEMBLIES: F— AND T—RATINGS PER ASTM E 814 OR UL 1479.
- C. PENETRATIONS IN SMOKE BARRIERS: L—RATINGS PER UL 1479.
- D. W—RATINGS: PER UL 1479.
- 1.3 INSTALLATION
- A. IDENTIFICATION: PREPRINTED METAL OR PLASTIC LABELS.
- 1.4 FIELD QUALITY CONTROL
- A. INSPECTION OF INSTALLED FIRE—STOPPING: BY OWNER—ENGAGED AGENCY ACCORDING TO ASTM E 2174.
- 1.5 THROUGH—PENETRATION FIRESTOP SYSTEM SCHEDULE

WHERE UL—CLASSIFIED SYSTEMS ARE INDICATED, THEY REFER TO SYSTEM NUMBERS IN UL'S "FIRE RESISTANCE DIRECTORY" UNDER PRODUCT CATEGORY XHEZ.

FOR THE FOLLOWING SYSTEMS:

- METALLIC AND NON—METALLIC PIPES, CONDUIT, OR TUBING, ELECTRICAL CABLES, CABLE TRAYS WITH ELECTRIC CABLES, MISCELLANEOUS ELECTRICAL PENETRANTS, INSULATED PIPES, GROUPINGS OF PENETRANTS, USE ON OR MORE THE FOLLOWING MATERIALS:
- a. LATEX SEALANT
- b. SILICONE SEALANT
- c. INTUMESCENT PUTTY
- d. MORTAR
- e. SILICONE FOAM
- f. PILLOWS/BAGS
- g. INTUMESCENT WRAP STRIPS
- h. INTUMESCENT COMPOSITE SHEET

SECTION 230529 — HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

- 1.1 PERFORMANCE REQUIREMENTS
- A. DELEGATED DESIGN: DESIGN TRAPEZE PIPE HANGERS AND EQUIPMENT SUPPORTS, INCLUDING COMPREHENSIVE ENGINEERING ANALYSIS BY A QUALIFIED PROFESSIONAL ENGINEER, USING PERFORMANCE REQUIREMENTS AND DESIGN CRITERIA INDICATED.
- B. STRUCTURAL PERFORMANCE: HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT SHALL WITHSTAND THE EFFECTS OF GRAVITY LOADS AND STRESSES WITHIN LIMITS AND UNDER CONDITIONS INDICATED ACCORDING TO ASCE/SEI 7.
1. DESIGN SUPPORTS FOR MULTIPLE PIPES CAPABLE OF SUPPORTING COMBINED WEIGHT OF SUPPORTED SYSTEMS, SYSTEM CONTENTS, AND TEST WATER.
2. DESIGN EQUIPMENT SUPPORTS CAPABLE OF SUPPORTING COMBINED OPERATING WEIGHT OF SUPPORTED EQUIPMENT AND CONNECTED SYSTEMS AND

SECTION 230517 — SLEEVES AND SLEEVE SEALS FOR HVAC PIPING

- 1.1 SLEEVE—SEAL SYSTEMS
- A. FIELD—ASSEMBLED, MODULAR SEALING—ELEMENT UNIT FOR FILLING ANNULAR SPACE BETWEEN PIPING AND SLEEVE.
1. SEALING ELEMENTS: EPDM RUBBER OR NBR.
2. PRESSURE PLATES: CARBON STEEL, PLASTIC, STAINLESS STEEL.
3. CONNECTING BOLTS AND NUTS: CARBON STEEL WITH CORROSION—RESISTANT COATING, STAINLESS STEEL.
- B. MANUFACTURERS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, AVAILABLE MANUFACTURERS OFFERING PRODUCTS THAT MAY BE INCORPORATED INTO THE WORK INCLUDE, BUT ARE NOT LIMITED TO, THE FOLLOWING:
1. ADVANCE PRODUCTS & SYSTEMS, INC.
2. CALPICO, INC.
3. METRAFLEX COMPANY (THE).
4. PIPELINE SEAL AND INSULATOR, INC.
5. PROCO PRODUCTS, INC.
- 1.2 SLEEVE—SEAL FITTINGS
- A. MANUFACTURED PLASTIC, SLEEVE—TYPE, PLASTIC OR RUBBER WATER—STOP ASSEMBLY MADE FOR IMBEDDING IN CONCRETE SLAB OR WALL.
- 1.3 GROUT
- A. NON—SHRINK, FACTORY PACKAGED.
- 1.4 SLEEVE AND SLEEVE—SEAL SCHEDULE
- A. USE SLEEVES AND SLEEVE SEALS FOR THE FOLLOWING PIPING—PENETRATION APPLICATIONS:
1. INTERIOR PARTITIONS:
- a. PIPING SMALLER THAN NPS 6 (DN 150): GALVANIZED—STEEL—PIPE SLEEVES, PVC—PIPE SLEEVES.
- b. PIPING NPS 6 (DN 150) AND LARGER: GALVANIZED—STEEL—SHEET SLEEVES.
- END OF SECTION 230517

SECTION 230518 — ESCUTCHEONS FOR HVAC PIPING

- PART 2 — PRODUCTS
- 2.1 ESCUTCHEONS
- A. ONE—PIECE, CAST—BRASS TYPE: WITH POLISHED, CHROME—PLATED AND ROUGH—BRASS FINISH AND SETSCREW FASTENER.
- B. ONE—PIECE, DEEP—PATTERN TYPE: DEEP—DRAWN, BOX—SHAPED BRASS WITH CHROME—PLATED FINISH AND SPRING—CLIP FASTENERS.

- C. ONE—PIECE, STAMPED—STEEL TYPE: WITH CHROME—PLATED FINISH AND SPRING—CLIP FASTENERS.
- 2.2 FLOOR PLATES
- A. ONE—PIECE FLOOR PLATES: CAST—IRON FLANGE WITH HOLES FOR FASTENERS.
- PART 3 — EXECUTION
- 3.1 INSTALLATION
- A. INSTALL ESCUTCHEONS FOR PIPING PENETRATIONS OF WALLS, CEILINGS, AND FINISHED FLOORS.
- B. INSTALL ESCUTCHEONS WITH ID TO CLOSELY FIT AROUND PIPE, TUBE, AND INSULATION OF PIPING AND WITH OD THAT COMPLETELY COVERS OPENING.
1. ESCUTCHEONS FOR NEW PIPING:
- a. PIPING WITH FITTING OR SLEEVE PROTRUDING FROM WALL: ONE—PIECE, DEEP—PATTERN TYPE.
- b. INSULATED PIPING: ONE—PIECE, STAMPED—STEEL TYPE.
- c. BARE PIPING AT WALL AND FLOOR PENETRATIONS IN FINISHED SPACES: ONE—PIECE, CAST—BRASS TYPE WITH POLISHED, CHROME—PLATED FINISH OR STAMPED—STEEL TYPE.
- d. BARE PIPING AT CEILING PENETRATIONS IN FINISHED SPACES: ONE—PIECE, CAST—BRASS TYPE WITH POLISHED, CHROME—PLATED FINISH OR STAMPED—STEEL TYPE.
- 3.2 FIELD QUALITY CONTROL
- A. REPLACE BROKEN AND DAMAGED ESCUTCHEONS AND FLOOR PLATES USING NEW MATERIALS.
- END OF SECTION 230518

SECTION 230529 — HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

- 1.1 PERFORMANCE REQUIREMENTS
- A. DELEGATED DESIGN: DESIGN TRAPEZE PIPE HANGERS AND EQUIPMENT SUPPORTS, INCLUDING COMPREHENSIVE ENGINEERING ANALYSIS BY A QUALIFIED PROFESSIONAL ENGINEER, USING PERFORMANCE REQUIREMENTS AND DESIGN CRITERIA INDICATED.
- B. STRUCTURAL PERFORMANCE: HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT SHALL WITHSTAND THE EFFECTS OF GRAVITY LOADS AND STRESSES WITHIN LIMITS AND UNDER CONDITIONS INDICATED ACCORDING TO ASCE/SEI 7.
- 1.2 SUBMITTALS
- A. SHOP DRAWINGS: SIGNED AND SEALED BY A PROFESSIONAL ENGINEER
- 1.3 QUALITY ASSURANCE
- A. AWS D1.1/D11.M, "STRUCTURAL WELDING CODE — STEEL."
- 1.4 COMPONENTS
- A. METAL PIPE HANGERS AND SUPPORTS: CARBON OR STAINLESS STEEL
- B. TRAPEZE PIPE HANGERS: CARBON OR STAINLESS STEEL
- C. FIBERGLASS PIPE HANGERS: —CLEVIS, CENTURY COMPOSITES, COOPER B—LINE
- D. METAL FRAMING SYSTEMS: MFMA MANUFACTURER
- E. FIBERGLASS STRUT SYSTEMS: COOPER B—LINE
- F. THERMAL—HANGER SHIELD INSERTS:
- G. FASTENER SYSTEMS: POWDER—ACTUATED FASTENERS OR MECHANICAL—EXPANSION ANCHORS
- H. PIPE STANDS: COMP

MECHANICAL GENERAL NOTES:

- A. PENETRATIONS OF THE AIR BARRIER SHALL BE CAULKED, GASKETED OR OTHERWISE SEALED IN A MANNER COMPATIBLE WITH THE CONSTRUCTION MATERIALS AND LOCATION. SEALING SHALL ALLOW FOR EXPANSION, CONTRACTION AND MECHANICAL VIBRATION. JOINTS AND SEAMS ASSOCIATED WITH PENETRATIONS SHALL BE SEALED IN THE SAME MANNER OR TAPED SEALING MATERIALS SHALL BE SECURELY INSTALLED AROUND THE PENETRATION SO AS NOT TO DISLODGE, LOOSEN OR OTHERWISE IMPAIR THE PENETRATIONS' ABILITY TO RESIST POSITIVE AND NEGATIVE PRESSURE FROM WIND, STACK EFFECT AND MECHANICAL VENTILATION.
- B. ALL EQUIPMENT AND MATERIALS WILL BE INSTALLED ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS AND ACCORDING TO THE BEST PRACTICE.
- C. ALL DUCTWORK SHALL BE COORDINATED WITH OTHER TRADES.
- D. CONTRACTOR SHALL BALANCE EACH DEVICE WITH THE CFM SHOWN ON PLAN.
- E. PROVIDE PROGRAMMABLE THERMOSTATS WITH SUB-BASE AND REMOTE TEMPERATURE SENSOR.
- F. DUCTWORK LOCATED IN EXPOSED CEILING SHALL BE INTERNALLY INSULATED.
- G. PROVIDE FIRE OR FIRE+SMOKE DAMPER WHEREVER DUCTS ARE CROSSING FIRE/SMOKE RATED WALLS/BARRIERS. COORDINATE WITH ARCHITECTURAL DRAWINGS FOR FIRE RATINGS OF THE WALLS.
- H. CONTRACTOR TO FIELD VERIFY EXISTING DUCTWORK, ASSOCIATED ACCESSORIES AND EXISTING HVAC EQUIPMENT.
- I. COORDINATE LOCATIONS AND SIZES OF ROOF OPENINGS WITH OWNER AND STRUCTURAL ENGINEERS.
- J. EQUIPMENT SIZES, DIMENSIONS AND REQUIRED CONNECTIONS SHALL BE VERIFIED WITH THE ACTUAL EQUIPMENT SELECTED. VENDOR DRAWINGS BEFORE FABRICATION OF DUCTWORK, PIPING ETC.
- K. ALL DUCT SIZES SHOWN ON MECHANICAL FLOOR PLANS ARE CLEAR INSIDE DIMENSIONS. INTERNAL INSULATION THICKNESS OF DUCTS SHALL BE CONSIDERED SEPARATELY.
- L. PROVIDE ACOUSTICAL LINING FOR THE FIRST 10 FT OF SUPPLY AND RETURN DUCTWORK.
- M. PROVIDE WEATHERPROOF COATING FOR ALL EXPOSED DUCT INSULATION ON ROOF.
- N. CONTRACTOR TO VERIFY IN FIELD THAT ANY EXHAUST FROM ADJACENT TENANT IS TERMINATED 10 FEET AWAY FROM MECHANICAL OUTSIDE AIR INTAKE.

MECHANICAL PLAN KEY NOTES:

1. #6" EXHAUST DUCT UP THROUGH ROOF. PROVIDE OFFSET AND TRANSITION AS NEEDED. CONTRACTOR TO VERIFY AND TERMINATE TOILET EXHAUST 10 FEET AWAY FROM ADJACENT TENANT ROOFTOP UNIT.
2. RESTROOM EXHAUST FAN. INTERLOCK FAN OPERATION WITH EXISTING ROOFTOP UNIT.
3. REUSE & RELOCATE EXISTING THERMOSTAT AND TEMPERATURE SENSOR FOR EXISTING RTU AS SHOWN ON PLAN. COORDINATE FINAL LOCATION WITH ARCHITECT/OWNER.
4. TERMINATE EXHAUST 10 FEET FROM PROPERTY/ LOT LINE, 40 INCH ABOVE ROOF, 3 FEET AWAY FROM ANY OPERABLE OPENING INTO THE BUILDING AND 10 FEET AWAY FROM ANY OUTSIDE AIR INTAKES. TERMINATE WITH GOOSENECK AND BIRDSCREEN.
5. CONNECT NEW SUPPLY BRANCH DUCT TO EXISTING MAIN TRUNK OF SUPPLY AIR DUCT.
6. CONNECT NEW RETURN BRANCH DUCT TO EXISTING MAIN TRUNK OF RETURN AIR DUCT.
7. EXISTING HVAC UNIT ON THE ROOF SERVING THE SPACE TO REMAIN WITH ALL ITS SUPPORTS AND ACCESSORIES AND TO BE REUSED. CONTRACTOR TO VERIFY ON SITE, THE EXISTING HVAC UNIT CAPACITY IS SUFFICIENT TO CATER THE COOLING AND HEATING LOAD OF 48 MBH. CONTACT BACK TO ENGINEER OF RECORD IN CASE OF ANY DISCREPANCY AND THE CAPACITY OF THE EXISTING UNIT IS INSUFFICIENT.
8. EXISTING SUPPLY AND RETURN MAIN BRANCH TRUNKS OF EXISTING RTU(E) TO REMAIN WITH ALL ITS SUPPORTS AND ACCESSORIES. REMOVE ALL EXISTING BRANCH DUCTS AND PATCH THE DUCTWORK AS REQUIRED.

FAN SCHEDULE

UNIT ID	MANUFACTURER	MODEL	CFM	TYPE	DRIVE	FAN RPM	WEIGHT (LBS)	E.S.P.		MOTOR			DIMENSIONS				SERVICE	INTERLOCKED WITH	NOTES
								(IN. W.G.)	HP	VOLTS	PHASE		L	W	H				
EF-1(N)	GREENHECK	SP-A90	70	CEILING	DIRECT	900	15	0.25	0.01(BHP)	115	1		13	10	9		REST ROOM	RTU(E)	1-4
EF-2(N)	GREENHECK	SP-A90	70	CEILING	DIRECT	900	15	0.25	0.01(BHP)	115	1		13	10	9		MOP SINK	LIGHT SWITCH	1-4

NOTES / ACCESSORIES:

- THERMAL OVERLOAD PROTECTION & DISCONNECT SWITCH.
- PROVIDE VIBRATION ISOLATOR, HANGERS AND REQUIRED ACCESSORIES FOR FAN INSTALLATION.
- GRAVITY BACKDRAFT DAMPER.
- AMCA SEAL & UL CERTIFIED.

DIFFUSER AND REGISTER SCHEDULE

UNIT ID	MANUFACTURER	MODEL	SIZE	DESCRIPTION	REMARKS
A	METALAIRE	570006-AL (01) WHITE	24x24	ALUMINUM, 2-CONE SQUARE FACE DIFFUSER WITH ROUND NECK, ALUMINUM, WITH ADJUSTABLE DISCHARGE AND RADIAL OPPOSED BLADE DAMPER, MODEL D3.	1,2,3,4,5
		570006-AL (03) BLACK		ALUMINUM, 2-CONE SQUARE FACE DIFFUSER WITH ROUND NECK, ALUMINUM, WITH ADJUSTABLE DISCHARGE AND RADIAL OPPOSED BLADE DAMPER, MODEL D3.	
B	METALAIRE	570006-AL (01) WHITE	12x12	ALUMINUM, 2-CONE SQUARE FACE DIFFUSER WITH ROUND NECK, ALUMINUM, WITH ADJUSTABLE DISCHARGE AND RADIAL OPPOSED BLADE DAMPER, MODEL D3.	1,2,3,4,5
		570006-AL (03) BLACK		ALUMINUM, 2-CONE SQUARE FACE DIFFUSER WITH ROUND NECK, ALUMINUM, WITH ADJUSTABLE DISCHARGE AND RADIAL OPPOSED BLADE DAMPER, MODEL D3.	
C	METALAIRE	RH-6 (01) WHITE	24X24	ALUMINUM RETURN GRILLE -0.667" SPACING SET AT 45 DEGREE ANGLE, VOLUME CONTROL OPPOSED BLADE DAMPERS, MODEL OBDA.	1,2,4
		RH-6 (03) BLACK		ALUMINUM RETURN GRILLE -0.667" SPACING SET AT 45 DEGREE ANGLE, VOLUME CONTROL OPPOSED BLADE DAMPERS, MODEL OBDA.	

NOTES:

- MAXIMUM NOISE CRITERION RATING < 35 DBA.
- BAKED ENAMEL FINISH, COLOR TO BE SELECTED BY ARCHITECT.
- DIFFUSERS SHALL BE 4-WAY BLOW UNLESS OTHERWISE INDICATED ON PLANS.
- MOUNTING FRAME TYPE SHALL BE COORD. WITH CEILING / WALL CONSTRUCTION TYPE.
- NECK SIZE SHALL BE AS SCHEDULED.

NECK SIZES:

Up To 100 Cfm	- 6" DIA
101 To 225 Cfm	- 8" DIA
176 To 275 Cfm	- 10" DIA
276 To 395 Cfm	- 12" DIA
396 To 535 Cfm	- 14" DIA
536 To 615 Cfm	- 15" DIA


AIR BALANCE

UNIT	SUPPLY AIR (CFM)	OUTSIDE AIR (CFM)	RETURN AIR (CFM)	EXHAUST AIR (CFM)	PRESSURE
RTU(E)	1600	220	1380	0	+220
EF-1(N)	0	0	0	70	-70
EF-2(N)	0	0	0	70	-70
TOTAL:	1600	220	1380	140	80


BUILDING PRESSURE: POSITIVE

NOTES:


- CONTRACTOR TO ADJUST VOLUME DAMPER ON FRESH AIR TAP OF EXISTING RTU TO PROVIDE OUTSIDE AIR AS MENTIONED IN ABOVE TABLE.




1 LOW PRESSURE BALANCING DAMPER
M-2.1 N.T.S




2 TYPICAL GOOSNECK DETAIL
M-2.1 N.T.S




3 ACOUSTICAL TREATMENT DUCT LINING
M-2.1 N.T.S




4 METHOD OF HANGING DUCTWORK
M-2.1 N.T.S



5 SUPPLY AIR DUCTWORK SUB-MAIN/BRANCH DUCT CONNECTION
M-2.1 N.T.S



6 TYPICAL DIFFUSER CONNECTION DETAIL
M-2.1 N.T.S



7 CEILING FAN HANGING SUPPORT DETAIL
M-2.1 N.T.S

These drawings are the property of the Architect, Signal Workline Heeser Architects P.C. Unauthorized reproduction for any purpose is an infringement upon copyright laws. Violators will be subject to prosecution to fullest extent of the law.
Written dimensions on these drawings shall have precedence over scale dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job and this office must be notified of any variation from the dimensions and conditions shown by these drawings.

NY ENGINEERS
NEARBY ENGINEERS
382 NE 191ST STREET, SUITE 4674, MIAMI, FL 33179
PH - 914.257.3455 | WWW.NY-ENGINEERS.COM

Revision Schedule		
#	Date	Revision
1	07/02/25	PERMIT ISSUE

PERMIT ISSUE

07/02/25

**MECHANICAL
DETAILS**

Professional Certification
I certify that these documents were prepared or approved by me, and that I am a duly licensed professional engineer under the laws of the State of Maryland.
License No. **46018** Expiration Date **10-08-26**

Drawn by: **NYE** Date: **07/01/2025**

Project No: **14057.11**

M-2.1

ELECTRICAL SYMBOL LIST				GENERAL NOTES (APPLY TO ALL "E" DRAWINGS)			
LIGHTING							
	LED LIGHTING FIXTURE AND OUTLET BOX. HALF SHADED FIXTURE OR "EM" INDICATES FIXTURES WITH INTEGRAL BATTERY PACK FOR EMERGENCY SERVICE, U.O.N.		JUNCTION BOX WITH BLANK COVER PLATE,	A	AMPERES	EA	EACH
			DUPLEX CONVENIENCE RECEPTACLE.	A/C, AC	ABOVE COUNTER	EC	EMPTY CONDUIT/ ELECTRICAL CONTRACTOR
	LUMINAIRE TYPE : INDICATE BY UPPERCASE LETTER SEE LIGHTING FIXTURE SCHEDULE.		GFI DUPLEX CONVENIENCE RECEPTACLE.	AF	AMPERE FRAME/AMP FUSE	EF	EXHAUST FAN
	CIRCUIT NUMBER : INDICATED BY NUMBER		USB DUPLEX CONVENIENCE RECEPTACLE.	AFF	ABOVE FINISHED FLOOR	EM	EMERGENCY
	SWITCHING INDICATED BY LOWER CASE LETTERS.		QUAD RECEPTACLE – 20A–1P, 125V, NEMA 5–20R.	AS	AMP SWITCH	EMT	ELECTRICAL METALLIC TUBING
	DENOTES LUMINAIRE ON EMERGENCY CIRCUIT.		230 VOLT RECEPTACLE	AIC	AMPS INTERRUPTING CAPACITY	EQUIP	EQUIPMENT
	DENOTES FIXTURES DESIGNATED AS NIGHTLIGHT, WIRED TO 24 HOURS UNSWITCHED CIRCUIT.		DATA OUTLET – (1) PORT UNO, +18" AFF, UNO TEL / DATA OUTLET TO BE PROVIDED WITH 1" CONDUIT U.O.N. TO H.C. AND TERMINATED WITH 90 DEGREE ELBOW AND BUSHING. TEL / DATA OUTLET PLATE SHALL BE PROVIDED WITH 1 1/4" DIAMETER GROMMETED OPENING.	AT	AMP TRIP	ER	EXISTING TO BE RELOCATED
	CEILING/WALL MOUNTED SELF POWERED EXIT LIGHT FIXTURE WITH DIRECTIONAL ARROWS AS INDICATED. SHADED AREA DENOTES FACE(S). ISOLITE ELITE SERIES LED EXIT SIGN	MOTORS AND CONTROLS		ATS	AUTOMATIC TRANSFER SWITCH	ETR	EXISTING TO REMAIN
SWITCHES AND CONTROLS				AUTO	AUTOMATIC	EWf	ELECTRIFIED WORKSTATION FURNITURE
	20A WALL SWITCH		30A/240V NON FUSED DISCONNECT SWITCH	AWG	AMERICAN WIRE GAUGE	EWH	ELECTRIC WATER HEATER
	20A 3–WAY WALL SWITCH U.N.O.	ANNOTATION		C	CONDUIT	FA	FIRE ALARM
	WALL MOUNTED OCCUPANCY SWITCH			C/B,CB	CIRCUIT BREAKER	FBO	FURNISHED BY OTHERS, INSTALLED & WIRED BY EC
	CEILING MOUNTED OCCUPANCY SENSOR.			CKT	CIRCUIT	FDR	FEEDER
	WALL MOUNTED PHOTOCCELL MOUNTED IN NEMA 3R ENCLOSURE.			CLG	CEILING	FIBO	FURNISHED & INSTALLED BY OTHERS, WIRED BY EC
WIRING SYSTEMS				COMM	COMMUNICATION	FIXT	FIXTURE
	POWER OR LIGHTING CIRCUITRY HOMERUN WITH PANELBOARD DESIGNATION, NUMBER WHERE USED INDICATES CIRCUIT NUMBER. IT SHALL CONSISTS OF 1#12 Ø, 1#12 N. & 1#12 G. IN 3/4" C, UNLESS OTHERWISE NOTED.		INDICATES MOUNTING HEIGHT, CENTER LINE TO FINISHED FLOOR.	CT	CURRENT TRANSFORMER	FL	FLOOR
	POWER OR LIGHTING CIRCUITRY HOMERUN WITH PANELBOARD DESIGNATION, NUMBER WHERE USED INDICATES CIRCUIT NUMBER. IT SHALL CONSISTS OF 2#12 Ø, 2#12 N. & 2#12 G. IN 3/4" C, UNLESS OTHERWISE NOTED.		KEYED NOTE REFERENCE	CU	COPPER	FLUOR	FLUORESCENT
	POWER OR LIGHTING CIRCUITRY HOMERUN WITH PANELBOARD DESIGNATION, NUMBER WHERE USED INDICATES CIRCUIT NUMBER. IT SHALL CONSISTS OF 3#12 Ø, 3#12 N. & 3#12 G. IN 3/4" C, UNLESS OTHERWISE NOTED.	POWER DISTRIBUTION		*C	DEGREE CELSIUS	G	GROUND
ELECTRICAL DRAWING LIST				*F	DEGREE FAHRENHEIT	GFI	GROUND FAULT INTERRUPTER
	DISTRIBUTION PANELBOARD, 208Y/120V–SURFACE OR FLUSH MOUNTED.			DIA	DIAMETER	GP	GENERAL PURPOSE
E–0.1	ELECTRICAL SYMBOL LIST, ABBREVIATIONS			DISC	DISCONNECT	HC	HUNG CEILING
E–0.2	ELECTRICAL SPECIFICATIONS SHEET 01 OF 02			DN	DOWN	HP	HORSEPOWER
E–0.3	ELECTRICAL SPECIFICATIONS SHEET 02 OF 02			DP	DISTRIBUTION PANEL	HWH	HOW WATER HEATER
E–1.1	ELECTRICAL LIGHTING PLAN			DWH			

ELECTRICAL SPECIFICATIONS

1. GENERAL:
- A. THE "GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION," AIA DOCUMENT A201, LATEST EDITION, AND THESE SPECIFICATIONS AS APPLICABLE ARE PART OF THIS CONTRACT.
- B. DRAWING ARE DIAGRAMMATIC AND INDICATE GENERAL ARRANGEMENT OF SYSTEMS AND WORK. CONDUIT ROUTING IS SHOWN DIAGRAMMATICALLY AND DOES NOT SHOW ALL OFFSETS, DROPS AND RISES OF RUNS. THE CONTRACTOR SHALL ALLOW IN HIS PRICE FOR ROUTING OF CONDUIT TO AVOID OBSTRUCTIONS. COORDINATION WITH EXISTING SERVICES, INCLUDING THOSE OF OTHER TRADES, IS REQUIRED. MAINTAIN HEADROOM AND SPACE CONDITIONS.
- C. BIDDERS, BEFORE SUBMITTING PROPOSALS, SHALL VISIT AND CAREFULLY EXAMINE THE AREA AFFECTED BY THIS WORK TO FAMILIARIZE THEMSELVES WITH THE EXISTING CONDITIONS AND THE DIFFICULTIES THAT WILL ATTEND THE EXECUTION OF THIS WORK. SUBMISSION OF A PROPOSAL WILL BE CONSTRUED AS EVIDENCE THAT SUCH AN EXAMINATION HAS BEEN MADE, AND LATER CLAIMS WILL NOT BE RECOGNIZED FOR EXTRA LABOR, EQUIPMENT, OR MATERIALS, REQUIRED BECAUSE OF DIFFICULTIES ENCOUNTERED WHICH COULD HAVE BEEN FORESEEN HAD SUCH AN EXAMINATION BEEN MADE.
- D. INSTALL WORK SO AS TO BE READILY ACCESSIBLE FOR OPERATION, MAINTENANCE AND REPAIR. MINOR ELEVATION FROM DRAWING MAY BE MADE TO ACCOMPLISH THIS, BUT CHANGES WHICH INVOLVE EXTRA COST SHALL NOT BE MADE WITHOUT APPROVAL.
- E. REMOVAL AND RELOCATION OF CERTAIN EXISTING WORK MAY BE NECESSARY FOR THE PERFORMANCE OF THE GENERAL WORK. ALL EXISTING CONDITIONS CANNOT BE COMPLETELY DETAILED ON THE DRAWINGS. THE CONTRACTOR SHALL SURVEY THE SITE AND INCLUDE ALL CHANGES AND CHARGES IN MAKING UP THE WORK PROPOSAL.
- F. CONNECTIONS TO EXISTING WORK: INSTALL NEW WORK AND CONNECT TO EXISTING WORK WITH MINIMUM INTERFERENCE TO EXISTING FACILITIES. TEMPORARY SHUTDOWNS OF EXISTING SERVICES SHALL BE PERFORMED AT NO ADDITIONAL CHARGES. AT TIMES NOT TO INTERFERE WITH NORMAL OPERATION OF EXISTING FACILITIES AND ONLY WITH WRITTEN CONSENT OF OWNER. ALARM AND EMERGENCY SYSTEMS SHALL NOT BE INTERRUPTED. MAINTAIN CONTINUOUS OPERATION OF EXISTING FACILITIES AS REQUIRED WITH NECESSARY TEMPORARY CONNECTIONS BETWEEN NEW AND EXISTING WORK. CONNECT NEW WORK TO EXISTING WORK IN NEAT AND ACCEPTABLE MANNER. RESTORE EXISTING DISTURBED WORK TO ORIGINAL CONDITION, INCLUDING MAINTENANCE OF WIRING CONTINUITY AS REQUIRED.
- G. DISCONNECT, REMOVE AND/OR RELOCATE EXISTING MATERIAL, EQUIPMENT AND OTHER WORK AS NOTED OR REQUIRED FOR PROPER INSTALLATION OF NEW WORK.
- H. THE CONTRACTOR SHALL KEEP ALL EQUIPMENT AND MATERIALS, AND ALL PARTS OF THE BUILDING, EXTERIOR SPACES AND ADJACENT STREETS, SIDEWALKS AND PAVEMENTS, FREE FROM MATERIAL AND DEBRIS RESULTING FROM THE EXECUTION OF THIS WORK. EXCESS MATERIALS WILL NOT BE PERMITTED TO ACCUMULATE EITHER ON THE INTERIOR OR THE EXTERIOR.
- I. SEAL OPENINGS THROUGH PARTITIONS, WALLS AND FLOORS WITH MINERAL WOOL OR OTHER NONCOMBUSTIBLE MATERIAL, UNLESS OTHERWISE NOTED.
- J. PROVIDE ALL NECESSARY FLASHING AND COUNTER FLASHING TO MAINTAIN THE WATERPROOFING INTEGRITY OF THE BUILDING AS REQUIRED BY THE INSTALLATION OR REMOVAL OF CONDUIT AND EQUIPMENT. PROVIDE EQUIPMENT CURBS AS REQUIRED.
- K. ALL EXISTING MATERIAL, EQUIPMENT AND CONSTRUCTION DEBRIS TO BE REMOVED UNDER THIS CONTRACT SHALL BECOME THE PROPERTY OF THE CONTRACTOR WITH THE EXCEPTION OF SPECIFIC EQUIPMENT AND APPARATUS REQUESTED BY THE BUILDING DEPARTMENT, ARCHITECT OR AS NOTED TO BE RELOCATED ON THE DRAWINGS. REMOVED EQUIPMENT SHALL BE PROPERLY DISPOSED OF BY THIS CONTRACTOR.
- L. THE CONTRACTOR'S PROPOSAL FOR ALL WORK SHALL BE PRECEDIATED ON THE PERFORMANCE OF THE WORK DURING REGULAR WORKING HOURS, WHEN SO DIRECTED, HOWEVER, THE CONTRACTOR SHALL INSTALL WORK DURING OVERTIME HOURS AND THE ADDITIONAL COST TO BE CHARGED THEREFORE SHALL BE ONLY THE "PREMIUM" PORTION OF THE WAGES PAID.
- M. UNLESS OTHERWISE SPECIFICALLY NOTED OR SPECIFIED, INCLUDE ALL CUTTING AND PATCHING OF EXISTING FLOORS, WALLS, PARTITIONS AND OTHER MATERIALS IN THE EXISTING BUILDING. THE CONTRACTOR SHALL RESTORE THESE AREAS TO ORIGINAL CONDITION.
- N. ALL MATERIAL AND EQUIPMENT SHALL BE NEW UNLESS OTHERWISE NOTED AND SHALL BE IN ACCORDANCE WITH BUILDING STANDARDS.
- O. INSURANCE: PROVIDE IN ACCORDANCE WITH OWNER/BUILDING REQUIREMENTS AND SHALL INCLUDE A HOLD HARMLESS CLAUSE FOR OWNER AND ENGINEER.
- P. THE FINAL ACCEPTANCE SHALL BE MADE AFTER THE CONTRACTOR HAS ADJUSTED HIS EQUIPMENT, TESTED THE VARIOUS SYSTEMS, AND DEMONSTRATED THAT IT FULFILLS THE REQUIREMENTS OF THE DRAWINGS AND SPECIFICATIONS AND HAS FURNISHED ALL THE REQUIRED CERTIFICATE OF INSPECTION AND APPROVAL.
2. GENERAL PROVISIONS FOR ELECTRICAL WORK:
- A. DEFINITIONS:
- 1) "PROVIDE": TO FURNISH, INSTALL AND CONNECT UP COMPLETE AND READY FOR SAFE AND REGULAR OPERATION THE PARTICULAR WORK REFERRED TO UNLESS SPECIFICALLY OTHERWISE NOTED.
- 2) "INSTALL": TO ERECT, MOUNT AND CONNECT COMPLETE WITH RELATED ACCESSORIES.
- 3) "FURNISH" OR "SUPPLY": TO PURCHASE, PROCURE, ACQUIRE, AND DELIVER COMPLETE WITH RELATED ACCESSORIES.
- 4) "WORK": LABOR, MATERIALS, EQUIPMENT, APPARATUS, CONTROLS, ACCESSORIES AND OTHER ITEMS REQUIRED FOR PROPER AND COMPLETE INSTALLATION.
- 5) "WIRING": RACEWAY, FITTINGS, WIRE, BOXES, AND RELATED ITEMS.
- 6) "CONCEALED": EMBEDDED IN MASONRY OR OTHER CONSTRUCTION, INSTALLED IN FURRED SPACES, WITHIN DOUBLE PARTITIONS OR HUNG CEILINGS, IN TRENCHES, IN CRAWL SPACES, OR IN ENCLOSURES.
- 7) "EXPOSED": NOT INSTALLED UNDERGROUND OR "CONCEALED" AS DEFINED ABOVE.
- 8) "SIMILAR" OR "EQUAL": EQUAL IN MATERIALS, WEIGHT, SIZE, DESIGN AND EFFICIENCY OF SPECIFIED PRODUCT.
- B. TEMPORARY LIGHT AND POWER: PROVIDE TEMPORARY LIGHT AND POWER SYSTEMS AT EARLIEST POSSIBLE DATE WITHIN THE CONSTRUCTION AREAS FOR THE REQUIREMENTS OF ALL TRADES AS HEREIN DESCRIBED. EXTEND SYSTEMS TO NEW CONSTRUCTION AS SOON AS PHYSICALLY POSSIBLE. MAINTAIN SYSTEM DURING WORKING HOURS. PROVIDE ALL REQUIRED MAINTENANCE, INCLUDING LAMPS AND SOCKETS.
- C. QUALITY ASSURANCE
- 1) QUALITY OF MATERIALS: ALL EQUIPMENT SHALL BE NEW SPECIFICATION GRADE, FREE FROM DEFECTS AND SYSTEMS BY APPROVED TESTING AGENCY AND BEARING THEIR LABEL. MATERIALS AND EQUIPMENT OF SIMILAR APPLICATION SHALL BE OF SAME MANUFACTURER, EXCEPT AS NOTED.
- 2) GUARANTEE: ALL MATERIALS AND WORKMANSHIP SHALL BE GUARANTEED AS DEFINED IN PARAGRAPH 2.C.
- 3) CURRENT CHARACTERISTICS:
- a. SERVICE: 120/208 VOLT, 3 PHASE, 4 WIRE, 60 HERTZ WITH GROUNDED NEUTRAL.
- b. DISTRIBUTION: 120/208 VOLT, 3 PHASE, 4 WIRE, 60 HERTZ WITH GROUNDED NEUTRAL.
- 4) HEIGHTS OF OUTLETS:
- a. FROM FINISHED FLOOR TO CENTERLINE OF OUTLETS FOR:
- RECEPTACLES AND TELEPHONES: 1 FT-6 IN.
- WALL SWITCHES: 4 FT-0 IN.
- WALL FIXTURES: 7 FT-0 IN.
- MOTOR CONTROLLERS: 5 FT-0 IN.
- CLOCKS: 7 FT 6 IN
- b. EXCEPTIONS: AT JUNCTION OF DIFFERENT WALL FINISH MATERIALS, ON MOLDING OR BREAK IN WALL SURFACE, IN VIOLATION OF CODE, OR AS NOTED OR DIRECTED.
- D. PRODUCT DELIVERY, STORAGE AND HANDLING
- 1) MOVING OF EQUIPMENT: WHERE NECESSARY, SHIP IN CARTED SECTIONS OF SIZE TO PERMIT PASSING THROUGH AVAILABLE SPACES.
- 2) ACCESSIBILITY: FOR OPERATION, MAINTENANCE AND REPAIR, MINOR DEVIATIONS SHALL BE PERMITTED. CHANGES OF MAGNITUDE OR INVOLVING EXTRA COST ARE NOT PERMISSIBLE WITHOUT REVIEW. GROUP CONCEALED ELECTRICAL EQUIPMENT REQUIRING ACCESS WITH EQUIPMENT FREELY ACCESSIBLE THROUGH ACCESS DOORS.
- E. MATERIALS
- 1) NAMEPLATES: PROVIDE BLACK LAMCROID SHEET WITH 3/4 IN. WHITE LETTERING, FASTENED WITH EPOXY CEMENT FOR EACH DISCONNECT SWITCH, CIRCUIT BREAKER, PANEL, CABINET, TRANSFORMER, ENCLOSURE, MOTOR CONTROLLER AND THE LIKE. NAMEPLATES SHALL DESCRIBE THE NAME AND NUMBER OF EACH COMPONENT.
- 2) CABLE TAGS: TAG EACH CONDUCTOR PASSING THROUGH SPLICE OR PULLBOX WITH A WHITE LINEN TAG, INDICATING POINT OF ORIGIN AND TERMINATION OF THE CIRCUIT.
- 3) INSERTS AND SUPPORTS:
- a. INSERTS: STEEL, SLOTTED TYPE, FACTORY PAINTED.
- SINGLE ROD: SIMILAR TO GRINNELL FIG. 281.
- MULTI-ROD: SIMILAR TO FEE AND MASON SERIES 9000 WITH END CAPS AND CLOSURE STRIPS.
- CLIP FORM NAILS FL


ELECTRICAL SPECIFICATIONS (CONT.)

- G. PROVIDE FLAMEPROOF LINEN OR FIBER TAGS IN ACCESSIBLE LOCATIONS FOR FEEDERS INDICATE FEEDER NUMBER, SIZE, PHASE AND POINTS OF ORIGIN AND TERMINATIONS. FOR CONTROL AND ALARM WIRING INDICATE TYPE (CONTROL OR ALARM), SIZE OF WIRE, AND POINTS OF ORIGIN AND TERMINATIONS.
- H. TERMINATIONS, SPLICES AND TAPS UNDER 600 VOLTS: COPPER CONDUCTORS NO. 10 AND SMALLER SHALL UTILIZE COMPRESSION-TYPE OF TWIST-ON SPRING-LOADED CONNECTORS AND CLEAR NYLON-INSULATED COVERING. COPPER CONDUCTORS NO. 8 AND LARGER SHALL UTILIZE MECHANICAL BOLTED PRESSURE OR HYDRAULIC COMPRESSION TYPE USING MANUFACTURER'S RECOMMENDED TOOLING. CABLE LUGS AND CONNECTORS SHALL UTILIZE COMPRESSION TYPE OF SAME METAL AS CONDUCTOR. PROVIDE TO MATCH CABLE WITH MARKING INDICATING SIZE AND TYPE. COPPER LUG CONNECTIONS TO BUS BARS: USE ANTISEIZE COMPOUND ON TANG.
- I. NOT MORE THAN 3 LIGHTING OR CONVENIENCE OUTLET CIRCUITS SHALL BE INSTALLED IN ONE CONDUIT UNLESS OTHERWISE INDICATED. FILL NO THERMOPLASTIC WIRES AT TEMPERATURES LOWER THAN 32 DEG F. PROVIDE SEPARATE RACEWAYS FOR CONDUCTORS OF 120/208 AND 208/480 VOLT SYSTEMS, EXCEPT 480 VOLT MOTOR BRANCH CIRCUIT WIRING AND RELATED 120 VOLT CONTROL WIRING. THERMOPLASTIC WIRES SHALL NOT BE INSTALLED IN COMPUTER AREA RAISED FLOORS.
- J. LEAVE WIRES WITH SUFFICIENT SLACK TO PERMIT MAKING FINAL CONNECTIONS.
- K. PERFORM CONTINUITY AND INSULATION TESTS. MEGGER TEST 100 PERCENT OF FEEDERS, 10 PERCENT OF BRANCH CIRCUITS AND ALL MOTOR BRANCH CIRCUITS OVER 25 HP.
- PERFORM TESTS PRIOR TO CONNECTING EQUIPMENT AND IN PRESENCE OF AUTHORIZED REPRESENTATIVES. SUBMIT WRITTEN REPORT OF RESULTS. CORRECT OR REPLACE CABLE TESTING BELOW MANUFACTURER'S STANDARDS.
11. WIRING DEVICES:
- A. WIRING DEVICES SHALL BE SPECIFICATION GRADE UNLESS OTHERWISE SPECIFIED. ALL DEVICES SHALL BE FLUSH MOUNTED, UNLESS OTHERWISE NOTED. PROVIDE COMPLETE MATERIAL AND ACCESSORIES AS NOTED.
- B. LOCAL WALL SWITCHES SHALL BE ROCKER TYPE, QUIET OPERATING, RATED 20 AMP, 120/277 VOLT, AC, SIMILAR TO LEVITON DECORA SERIES A5621 (SINGLE POLE), A5623 (3-WAY) AND A5624 (4-WAY).
- C. STRAIGHT BLADE RECEPTACLES SHALL BE COMMERCIAL SPECIFICATION GRADE DUPLEX CONVENIENCE 125 VOLTS, 2 POLE, 3 WIRE, U GROUND SLOT, DECORA SERIES BY LEVITON. GROUNDED, EXCEPT AS NOTED.
- 1) SINGLE GANG, RECESSED, DUPLEX RECEPTACLE: TAMPER RESISTANT, 2-POLE, 3-WAY, 3-WIRE, GROUNDING, 15A, 125V, NEMA 5-20R, LEVITON 689 SERIES (COLOR AS SPECIFIED BY ARCHITECT).
- 2) USB CHARGER, DUPLEX TAMPER-RESISTANT RECEPTACLE: TAMPER RESISTANT,
- D. INSERTION RECEPTACLES SHALL BE HOSPITAL GRADE DUPLEX CONVENIENCE 125 VOLTS, 2 POLE, 3 WIRE, U GROUND SLOT, GROUNDED, EXCEPT AS NOTED.
- 1) HEALTH CARE FACILITIES:
- a) DUPLEX, 20 AMP, 125 VOLTS, 2 POLE, 3 WIRE, U GROUND SLOT: SIMILAR TO HUBBELL NO. 8300 HOSPITAL GRADE.
- b) SINGLE, 20 AMP, 125 VOLT, 2 POLE, 3 WIRE, U GROUND SLOT: SIMILAR TO HUBBELL NO. 8310 HOSPITAL GRADE.
- 2) GROUND FAULT INTERRUPTER RECEPTACLES:
- a. 20 AMP DUPLEX FEED-THROUGH TYPE, SIMILAR TO NO. GF8300.
- E. DEVICE PLATES: SEE ARCHITECT FOR TYPE. FOR RECEPTACLES WITH OTHER THAN 120 VOLT, INSCRIBED VOLTAGE AVAILABLE.
- F. COLORS: COORDINATE COLORS WITH ARCHITECT.
- G. MOUNTING ORIENTATION OF RECEPTACLES (HORIZONTAL OR VERTICAL): COORDINATE WITH ARCHITECT.
12. LIGHTING FIXTURES:
- A. FIXTURES TO BE AS SPECIFIED BY ARCHITECT AND SHALL BE COMPLETELY FACTORY ASSEMBLED, WIRED AND EQUIPPED WITH ALL NECESSARY SOCKETS, BALLASTS, SUPPORTING HARDWARE AND ACCESSORIES. REFER TO DRAWINGS FOR INDIVIDUAL FIXTURE DESCRIPTIONS.
- B. FIXTURE CATALOG NUMBERS USED TO ILLUSTRATE EQUIPMENT TYPE DO NOT NECESSARILY DENOTE REQUIRED MOUNTING EQUIPMENT OR ACCESSORIES. PROVIDE ACCESSORIES TO SUIT.
- C. BALLAST: CLASS P, HIGH POWER FACTOR, LOWEST AVAILABLE NEMA RATED NOISE LEVEL, ET1 AND CBM APPROVED. ENERGY SAVING TYPE. TRIGGER START FOR 24-INCH LAMPS AND RAPID START FOR 48-INCH. TWO LAMP BALLASTS: NO. THREE LAMP BALLASTS. BALLASTS SHALL BE ADVANCE MAGNETEK, UNIVERSAL OR EQUAL.
- D. LED DRIVERS SHALL BE ELECTRONIC TYPE, LABELED AS COMPLIANT WITH RADIO FREQUENCY INTERFERENCE (RFI) REQUIREMENTS OF FCC TITLE 47, PART 15 AND COMPLY WITH NEMA SSL 1 "ELECTRONIC DRIVERS FOR LED DEVICES, ARRAYS OR SYSTEMS". LED DRIVERS SHALL HAVE A SOUND RATING OF 7%, HAVE A MINIMUM EFFICIENCY OF 85% AND BE RATED FOR A THD OF LESS THAN 20% AT ALL INPUT VOLTAGES.
- E. DIMMABLE LED DRIVERS SHALL BE CAPABLE OF DIMMING WITHOUT LED STROBING OR FLICKER ACROSS THEIR FULL DIMMING RANGE. PROVIDE TYPE OF LED DRIVER AS PER LIGHTING FIXTURE SCHEDULE. DIMMABLE LED DRIVERS SHALL BE 0-10V WHERE NOT INDICATED.
- F. CONTINUOUS ROW, TWO LAMP STRIP FIXTURES SHALL BE STAGGERED TYPE.
- G. FLUORESCENT LIGHTING FIXTURES, INCLUDING GENERAL CONSTRUCTION, LAMPS AND BALLASTS SHALL CONFORM TO THE ENERGY EFFICIENCY REQUIREMENTS OF CONSOLIDATED EDISON CO. AND QUALITY FOR A UTILITY REBATE TO OWNER UNDER CON EDISON'S ENLIGHTENED ENERGY LIGHTING REBATE PROGRAM. CONTRACTOR SHALL COORDINATE REBATE PROGRAM WITH CON EDISON AND ARRANGE FOR CON EDISON TO PERFORM A SURVEY TO INVENTORY ALL EXISTING FIXTURES PRIOR TO DEMOLITION.
- H. EXIT SIGNS SHALL BE PRECISION DIE-CAST ALUMINUM HOUSING WITH LASER-FORMED ACRYLIC LEGEND. EXIT SIGNS SHALL COMPLY WITH UL 924 AND BE MEA APPROVED FOR USE IN NEW YORK CITY. AC POWERED WITH PREMIUM LONG-LIFE NICKEL CADMIUM BATTERY WITH STANDARD UL LISTED 3-HOUR RUN TIME. PROVIDE WITH INTEGRAL AUTOMATIC CHARGER IN A SELF-CONTAINED POWER PACK. LED INDICATOR WITH PUSH TO TEST SWITCH.
13. TELEPHONE CONDUIT SYSTEM:
- A. PROVIDE COMPLETE SYSTEM OF, RACEWAYS AND ACCESSORIES, OUTLET BOXES, SLEEVES AND FISHWIRES.
- B. EQUIPMENT SHALL CONFORM TO REQUIREMENTS OF TELEPHONE COMPANY.
- C. OUTLETS SHALL BE:
- 1) WALL: 4 IN. SQUARE WITH BUSHED COVER PLATE.
- D. PROVIDE FISHWIRES, IN RACEWAYS OVER 10 FT LONG.
- E. CONDUIT SHALL BE 3/4 IN. MINIMUM. FURNISH EMPTY CONDUIT FROM OUTLET BOX TO BUSHED END THRU WALL 6" BELOW THE PLASTER CEILING.
- F. FACE RACEWAYS IN ROOMS SHALL HUBBELL HBL500, HBL750 OR HBL2000 SERIES OR AS ACCEPTABLE.
14. PANELBOARDS:
- A. PANELBOARDS SHALL BE OF THE DEAD FRONT TYPE MANUFACTURED IN CODE GAUGE AND SIZE BOXES FOR MOUNTING AS INDICATED ON PLANS COMPLETE WITH TRIM, DOORS AND LOCKS. ALL LOCKS SHALL BE KEYED ALIKE.
- B. CIRCUIT BREAKERS SHALL BE OF THE BOLT-ON THERMAL MAGNETIC MOLDED CASE TYPE, AND SHALL HAVE THE TRIP RATINGS AND NUMBER OF POLES SHOWN IN SCHEDULES ON THE CONTRACT DRAWINGS. FOR BLANK (SPACE) COMPARTMENTS, PROVIDE FULL RATED BUS. MINIMUM GUTTER SPACES SHALL BE 5-3/4". SIDES, TOP AND BOTTOM, INCREASE FOR THROUGH FEEDERS. PROVIDE 25% COPPER GROUND BUS AND 100% COPPER NEUTRAL BUS AND INCREASE NEUTRAL BUS INDICATED.
- C. LOCKING TABS SHALL BE PROVIDED ON ALL CIRCUIT BREAKERS SERVING EMERGENCY LIGHTING, FIRE ALARM SYSTEM, SECURITY SYSTEMS AND OTHER EMERGENCY OR CRITICAL EQUIPMENT AND AS NOTED ON THE CONTRACT DRAWINGS. A TOTAL OF 5 SPARE LOCKING TABS SHALL BE FURNISHED TO THE OWNER.
- D. BUSES SHALL BE HARD DRAWN COPPER OF 98 PERCENT CONDUCTIVITY AND SHALL HAVE CROSS SECTIONAL AREAS LARGE ENOUGH TO LIMIT THE TEMPERATURE RISE, WHEN CARRYING FULL LOAD, TO 35 DEGREES C. ABOVE AN AMBIENT INSIDE THE ENCLOSURE OF 35 DEGREES C. AS DEFINED IN IEEE STANDARD RULES. MAIN BUS CAPACITY SHALL BE AS SHOWN ON THE CONTRACT DRAWINGS.
- E. ENCLOSURES SHALL BE SURFACE OR FLUSH AS INDICATED. TRIMS SHALL BE SECURED TO PANEL WITH MACHINE SCREWS. COVERS SHALL BE HINGED DOOR-IN-DOOR CONSTRUCTION WITH CYLINDER LOCKS AND CATCHES. LOCKS MUST BE COMPATIBLE WITH BUILDING STANDARD KEY SYSTEM AND WHEN NONE EXISTS, THEY SHALL BE SIMILAR TO A YALE NO. 911 KEY.
- F. DISTRIBUTION AND SUB-DISTRIBUTION PANELBOARD SHALL BE A MINIMUM OF 30" WIDE AND 10" DEEP.
- G. ALL STANDARD PANELBOARDS SHALL BE A MINIMUM OF 20" WIDE AND 5 3/4" DEEP.
- H. FURNISH ALL PANELBOARDS WITH FEED-THRU LUGS UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
- I. ALL NEW PANELBOARDS SHALL BE PROVIDED WITH AN ENGRAVED WHITE CORE LAMACOID NAMEPLATE, WITH 3/4 IN. WHITE LETTERING ON A BLACK BACKGROUND, WITH DESIGNATION LISTED (PANELBOARD NAME), FASTENED WITH EPOXY CEMENT OR OVAL HEAD CHROME PLATED MACHINE SCREWS.
- J. THE CIRCUIT DIRECTORY SHALL BE TYPEWRITTEN AND PROVIDED INSIDE EACH PANEL DOOR TO INDICATE EQUIPMENT AND/OR AREA SERVED. DIRECTORY HOLDER SHALL BE METAL FRAME WITH CLEAR PLASTIC, TRANSPARENT COVER. THE TYPE

LIGHT FIXTURE SCHEDULE NOTES—	
A.	COORDINATE FINAL FIXTURE MAKE AND MODEL WITH ARCHITECT.
B.	ELECTRICAL CONTRACTOR TO COORDINATE WITH OWNER AND ENSURE THAT THE LIGHTS FIXTURES ARE IN COMPLIANCE WITH THE CURRENT CODES.
C.	CONTRACTOR ADVISED TO UPDATE THE EMERGENCY LIGHT FIXTURES LOCATIONS/QUANTITY PER SITE REQUIREMENT UP ON FINAL INSPECTION OR PER LOCAL AHJ REQUIREMENT. ONE FOOT CANDLE OF EMERGENCY ILLUMINATION SHALL BE PROVIDED ALONG ALL EGRESS PATHWAYS AND EMERGENCY SIGN SHALL BE INSTALLED AT ALL INTERSECTIONS, EXIT CORRIDORS, PATHWAYS AND EXIT EGRESS OPENINGS IN ACCORDANCE WITH THE IBC 1008.3.1 MEANS OF EGRESS ILLUMINATION.THE EMERGENCY POWER SYSTEM SHALL PROVIDE POWER FOR A DURATION OF +90MINUTES AND SHALL CONSIST OF STORAGE BATTERIES.

ELECTRICAL LIGHTING KEYED NOTES:	
1	E.C. SHALL COORDINATE THE EXACT LOCATION AND POWER REQUIREMENT OF THE NEW ILLUMINATED BUILDING SIGN BEFORE COMMENCING ANY WORK. E.C. SHALL ALSO PROVIDE AND LOCATE THE DISCONNECT SWITCH FOR THE NEW ILLUMINATED BUILDING SIGN PER NEC 600.6(A). BASE BID ACCORDINGLY.
2	SIGN/EXTERIOR SIGNAGE SHALL BE CONTROLLED WITH EXTERIOR MOUNTED PHOTOCELL/TIME CLOCK. E.C TO VERIFY LOCATION IN FIELD PRIOR TO ROUGH-IN.
3	CONNECT ALL EMERGENCY EGRESS AND NIGHT LIGHTING FIXTURES TO THE NEAREST LIGHTING BRANCH CIRCUIT AHEAD OF ALL SWITCHING AND CONTROLS PER LOCAL CODES.
4	PROVIDE CEILING MOUNTED/WALL MOUNTED SHOW WINDOW RECEPTACLE WITHIN 18 INCHES OF TOP OF THE SHOW WINDOW AS PER NEC 210.62. VERIFY EXACT LOCATION WITH ARCHITECT/OWNER.
5	E.C SHALL COORDINATE WITH THE ARCHITECT/OWNER FOR THE EXACT SWITCH LOCATION FOR THE LIGHT FIXTURES. REPORT ENGINEER ON RECORD FOR ANY DISCREPANCY. BASE BID ACCORDINGLY.
6	E.C SHALL INTERCONNECT EF-1(N) TO THE RTU-1(E). COORDINATE WITH MECHANICAL DRAWINGS FOR MORE DETAILS.
7	E.C SHALL INTERCONNECT EF-2(N) WITH THE LIGHTS IN THE SAME ROOM. COORDINATE WITH MECHANICAL DRAWINGS FOR MORE DETAILS.

LIGHT FIXTURE SCHEDULE				
TYPE	DESCRIPTION	MANUFACTURER	CATALOG NUMBER	WATTAGE
A	2x4 RECESSED LAY-IN FIXTURE	KEYSTONE LIGHTING	MHKT-BPLED50PS-24-8CSA-VDIM	40 WATTS
B	6" RECESSED CAN LIGHT FIXTURE	TBD	TBD	20 WATTS
EX	EXIT SIGNS	TBD	TBD	2 WATTS
EM	WALL-MOUNTED EMERGENCY LIGHTS	TBD	TBD	2 WATTS
(E)	EXISTING LIGHT FIXTURE TO REMAIN	-	-	-



1 ELECTRICAL LIGHTING PLAN
1/4" = 1'-0"

These drawings are the property of the Architect, Signal Workline Hesser Architects P.C. Unauthorized reproduction for any purpose is an infringement upon copyright laws. Violators will be subject to prosecution to fullest extent of the law.
Written dimensions on these drawings shall have precedence over scale dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and this office must be notified of any variation from the dimensions and conditions shown by these drawings.

NY ENGINEERS
NEARBY ENGINEERS
382 NE 191ST STREET, SUITE 49674, MIAMI, FL 33179
PH - 914.257.3455 | WWW.NY-ENGINEERS.COM

Revision Schedule		
#	Date	Revision
1	07/02/25	PERMIT ISSUE

PERMIT ISSUE

07/02/25

ELECTRICAL LIGHTING PLAN

Professional Certification
I certify that these documents were prepared or approved by me, and that I am a duly licensed professional engineer under the laws of the State of Maryland.
License No. **48018** Expiration Date: **10-08-26**

Drawn by:
NYE
Date:
07/01/2025
Project No:
14057.11


E-1.1

ELECTRICAL POWER PLAN GENERAL WORK NOTES:


- A. E.C. SHALL COORDINATE WITH OTHER TRADE CONTRACTORS FOR EXACT LOCATION AND POWER REQUIREMENT OF THE EQUIPMENT FROM OTHER TRADES. PROVIDE WIRING AND CONTROLS AS REQUIRED (IF NOT PROVIDED BY THEM), PRIOR TO BID. BASE BID ACCORDINGLY.
- B. ALL THE RECEPTACLES SHALL BE RATED PER CIRCUIT. E.C. SHALL VERIFY AND MAKE FINAL CONNECTIONS ACCORDINGLY.
- C. ELECTRICAL CONTRACTOR SHALL PROVIDE TYPED PANEL DIRECTORY FOR ALL THE ELECTRICAL PANELS AS PER NEC 408.4(A).
- D. THE ENTIRE ELECTRICAL INSTALLATION SHALL COMPLY WITH THE NEC AND ALL STATE AND LOCAL CODES.
- E. ALL 125-VOLT RECEPTACLES SUPPLIED BY SINGLE-PHASE BRANCH CIRCUITS RATED 150 VOLTS OR LESS TO GROUND, 50 AMPERES OR LESS, AND ALL RECEPTACLES SUPPLIED BY THREE-PHASE BRANCH CIRCUITS RATED AT 150 VOLTS OR LESS TO GROUND, 100 AMPERES OR LESS, INSTALLED IN THE LOCATIONS SPECIFIED IN 210.8(B) SHALL HAVE GFI PROTECTION. IF GFI RECEPTACLE IS NOT READILY ACCESSIBLE THEN PROVIDE THE GFI BREAKER IN PANELS.

ELECTRICAL POWER PLAN KEYED WORK NOTES:

- 1 ELECTRICAL CONTRACTOR SHALL COORDINATE WITH PLUMBING CONTRACTOR FOR THE EXACT POWER REQUIREMENTS AND LOCATION OF RCP AND WH. PRIOR TO ROUGH-IN. BASE BID ACCORDINGLY.
- 2 PROVIDE DUPLEX RECEPTACLE AND CAT6 DATA CABLE AND ALL OTHER REQUIRED CONNECTION IN FIELD AND COORDINATE FOR FINAL LOCATION AND MOUNTING HEIGHT WITH OWNER.
- 3 EXISTING 200A(M.C.B), 120/208V, 3-PHASE, 4-WIRE ELECTRICAL PANEL "A" (NAME TO BE VERIFY ON FIELD) TO REMAIN AND RELOCATED TO THE LOCATION AS SHOWN IN THE DRAWING. E.C. TO COORDINATE EXACT LOCATION WITH ARCHITECT/OWNER IN FIELD AND ALSO FIELD. VERIFY THE EXACT SIZE & OPERABLE CONDITION OF THE PANEL, REPLACE IF FOUND INOPERABLE. BASE BID ACCORDINGLY.
- 4 E.C. SHALL VERIFY/PERFORM THE INSTALLATION OF ELECTRICAL PANELS IN COMPLIANCE WITH NEC ARTICLE 110.26(A) AND (B). E.C. SHALL FIELD VERIFY THAT THE PANELS ARE UNOBSTRUCTED AND THE AREA WHERE THE PANELS ARE PLACED SHALL NOT BE USED AS A STORAGE SPACE.
- 5 E.C. SHALL INSTALL A 24-PORT CAT 6 PATCH PANEL (TRENDNET TC-P24C6) ON THE BACKBOARD AT A HEIGHT NOT EXCEEDING 5 FEET (AFF). COORDINATE FOR FINAL LOCATION WITH OWNER.
- 6 PROVIDE 4'x6'x3/4" FIRE RATED PLYWOOD MOUNTED IN IT CLOSET NEAR ELECTRICAL PANEL. COORDINATE FOR FINAL LOCATION WITH OWNER.
- 7 PROVIDE 6' CAT6 CABLE COILED ABOVE TILE. MARK TILE WITH BLUE PAINTERS TAPE. TERMINATE WITH MALE RJ45 PLUG IN CEILING AND ON PATCH PANEL COORDINATE FOR FINAL LOCATION WITH OWNER. BASE BID ACCORDINGLY.
- 8 E.C. SHALL PROVIDE THE SPLIT CONTROLLED RECEPTACLES WITH THE TOP RECEPTACLE CONTROLLED AS PER THE C405.11.1. BASE BID ACCORDINGLY.
- 9 PROVIDE 6' CAT6 CABLE COILED ABOVE TILE. MARK TILE WITH BLUE PAINTERS TAPE. TERMINATE WITH MALE RJ45 PLUG IN CEILING AND ON PATCH PANEL FOR THE SECURITY CAMERA COORDINATE FOR FINAL LOCATION WITH OWNER. BASE BID ACCORDINGLY.



2 WIRING DIAGRAM
N.T.S



1 ELECTRICAL POWER PLAN
1/4" = 1'-0"

These drawings are the property of the Architect, Signal Workline Heeser Architects P.C. Unauthorized reproduction for any purpose is an infringement upon copyright laws. Violators will be subject to prosecution to the fullest extent of the law.

Written dimensions on these drawings shall have precedence over scale dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and this office must be notified of any variation from the dimensions and conditions shown by these drawings.

NY ENGINEERS

NEARBY ENGINEERS
382 NE 191ST STREET, SUITE 49674, MIAMI, FL 33179
PH - 914.257.3455 | WWW.NY-ENGINEERS.COM

Revision Schedule

#	Date	Revision
1	07/02/25	PERMIT ISSUE

PERMIT ISSUE

07/02/25

ELECTRICAL
POWER PLAN

Professional Certification
I certify that these documents were prepared or approved by me, and that I am a duly licensed professional engineer under the laws of the State of Maryland.
License No. **48018** Expiration Date **10-08-26**


Drawn by:
NYE

Date:
07/01/2025

Project No:
14057.11

E-1.2

NOTE:
THIS INFORMATION MAY NOT CONTAIN ALL DETAILS REQUIRED FOR CONSTRUCTION. APPROPRIATE MODIFICATION MAY BE REQUIRED TO ENSURE SUITABILITY OF THESE DRAWINGS FOR THE SPECIFIC APPLICATION. IT IS THE USER'S RESPONSIBILITY TO ENSURE INSTALLATION OF THE EQUIPMENT/SYSTEM IS IN ACCORDANCE WITH BUILDING/PROJECT SPECIFICATIONS, APPLICABLE CODES AND STANDARDS.



- NOTES:
1. ALL CONDUIT MAY BE COMBINED ON SAME SUPPORT CHANNEL WHERE PRACTICAL.
 2. SUPPORT CHANNEL LENGTH SHALL NOT BE DETERMINED UNTIL ALL PIPING, CONDUIT, ETC. TO BE SUPPORTED IS COORDINATED.
 3. SUPPORT CHANNEL SPACING SHALL BE NO MORE THAN 10'-0".
 4. UNISTRUT AND CONDUIT INSTALLATION MAY BE REVERSED.



1 CONDUIT SUPPORT DETAIL
E-2.1 N.T.S

- MANUAL MODE OPERATION:
1. PUSHBUTTON PRESS IS REQUIRED TO TURN LOAD ON.
 2. LOAD TURNS OFF WHEN SENSOR TIMES OUT OR BY PRESSING PUSH BUTTON.
 3. IF DAYLIGHT SENSOR IS ENABLED AND LIGHT LEVEL IS ABOVE SETPOINT, LOAD WILL NOT TURN ON.

- AUTOMATIC MODE OPERATION:
1. WHEN SENSOR ACTIVATES LOAD TURNS ON.
 2. PUSHBUTTON CAN BE USED TO TURN LOAD ON OR OFF. IF PUSHBUTTON IS USED TO TURN LOAD OFF, SENSOR MUST TIME OUT FIRST, BEFORE LOAD CAN TURN BACK ON AUTOMATICALLY.
 3. IF DAYLIGHT SENSOR IS ENABLED AND LIGHT LEVEL IS ABOVE SETPOINT, LOAD WILL NOT TURN ON.

SENSOR TYPES INCLUDE:
ONW-D-1001-MV-N

- 1 PROVIDE SENSING CONDUCTOR TAPPED AHEAD OF ANY SWITCHES WHERE SWITCH SERVES EMERGENCY FIXTURES.



4 CONNECTION) OCCUPANCY/VACANCY-SINGLE LEVEL
WIRING DIAGRAM-LOW VOLTAGE WALL SWITCH SENSOR(NEUTRAL)
E-2.1 N.T.S

- AUTOMATIC MODE OPERATION:
1. WHEN SENSOR ACTIVATES, LOAD TURNS ON.
 2. LOAD TURNS OFF, WHEN SENSOR TIMES OUT.
 3. SWITCHES CAN BE USED TO TURN LOAD OFF.

RECOMMENDED WIRE:


18-3 AWG STRANDED WIRE SHIELDED OR NON-SHIELDED

SENSOR TYPES INCLUDE:

OAC-DT-0501, OAC-DT-1000, OAC-DT-2000
OAC-U-0501, OAC-U-1000, OAC-U-2000
OAC-P-0500, OAC-P-1500


SWITCHPACK TYPE INCLUDES:

SP20-MV



5 WIRING DIAGRAM-LOW VOLTAGE CEILING SENSOR OCCUPANCY
-AUTO ON/OFF WITH LINE VOLTAGE OVERRIDE TO OFF
THREE-WAY SWITCHING.
E-2.1 N.T.S


- NOTES:
1. ALL CONDUCTORS IN VERTICAL RACEWAYS SHALL BE SUPPORTED IN ACCORDANCE WITH ARTICLE 300.19 OF NEC. CABLE SUPPORTS SHALL BE LOCATED AT THE INTERVALS REQUIRED BY THE NEC.
 2. CABLE SUPPORT SYSTEM SHALL BE AS MANUFACTURED BY O-2 GEDNEY WITH POZI-GRIP "S"-STYLE WEDGING PLUG OR APPROVED EQUAL.
 3. FOR THREADLESS CONDUIT (RIGID, IMC OR EMT), ATTACH CONDUIT BODY TO MALE THREADS OF A SET SCREW OR COMPRESSION CONNECT, AS PERMITTED BY SPECIFICATIONS.
 4. PROVIDE PULL BOX AT EACH LOCATION OF CABLE SUPPORTS. PULL BOX SHALL BE SIZED AS PER CODE TO ACCOMMODATE ALL CONDUITS.



2 VERTICAL CABLE SUPPORT DETAIL
E-2.1 N.T.S

NOTES:

- 1 TYPICAL FOR WOOD AND METAL STUD ROUGH-IN
- 2 PLASTER RINGS NOT SHOWN
- 3 LOCATE ALL OUTLET BOXES IN ACCORDANCE WITH ARCHITECTURAL AND MECHANICAL DRAWINGS, AND WITH ALL APPLICABLE SHOP DRAWINGS.
- 4 IN ACCORDANCE WITH UBC 4304 OUTLETS ON OPPOSITE SIDES OF WALLS OR PARTITIONS IN THE SAME STUD SPACE MUST BE SEPARATED BY A MIN. OF 24" HORIZONTAL DISTANCE.



3 DETAIL TYPICAL ROUGH-IN REQUIREMENTS
E-2.1 N.T.S

These drawings are the property of the Architect. Signal Wireless Heuser Architects P.C. Unauthorized reproduction for any purpose is an infringement upon copyright laws. Violators will be subject to prosecution by federal extent of the law.

NY ENGINEERS
NEARBY ENGINEERS
382 NE 191ST STREET, SUITE 49674, MIAMI, FL 33179
PH - 914.257.3455 | WWW.NY-ENGINEERS.COM

Revision Schedule

#	Date	Revision
07/02/25	PERMIT ISSUE	

PERMIT ISSUE

07/02/25

**ELECTRICAL
DETAILS**

Professional Certification
I certify that these documents were prepared or approved by me, and that I am a duly licensed professional engineer under the laws of the State of Maryland.
License No. 46018 Expiration Date 10-08-26

Drawn by: NYE Date: 07/01/2025


Project No: 14057.11

E-2.1

ELECTRICAL RISER KEYED WORK NOTES:	
①	EXISTING 200A, 120/208V, 3-PHASE, 4-WIRE ELECTRICAL INCOMING SERVICE TO THE PROJECT SPACE. E.C. SHALL GET INFORMATION ABOUT THE EXISTING POWER DISTRIBUTION PRIOR TO COMMENCING ANY WORK AND INFORM ENGINEER ON RECORD FOR ANY DISCREPANCIES.
②	EXISTING 200A, 120/208V, 3-PHASE, 4-WIRE ELECTRICAL METER FOR THE PROJECT SPACE SHALL REMAIN. E.C. SHALL VERIFY THE OPERABLE CONDITION OF EXISTING ELECTRICAL METER & REPLACE IF FOUND INOPERABLE. BASE BID ACCORDINGLY.
③	EXISTING 200A(M.C.B), 120/208V, 3-PHASE, 4-WIRE ELECTRICAL PANEL "A" (NAME TO BE VERIFY ON FIELD) TO REMAIN AND RELOCATED TO THE LOCATION AS SHOWN IN THE DRAWING. E.C TO COORDINATE EXACT LOCATION WITH ARCHITECT/OWNER IN FIELD AND ALSO FIELD VERIFY THE EXACT SIZE & OPERABLE CONDITION OF THE PANEL, REPLACE IF FOUND INOPERABLE. BASE BID ACCORDINGLY.
④	EXISTING INCOMING FEEDERS TO REMAIN. E.C. TO VERIFY OPERABLE CONDITION OF FEEDER'S IN FIELD AND PROVIDE NEW IF FOUND INOPERABLE. BASE BID ACCORDINGLY.

ELECTRICAL RISER GENERAL NOTES:	
A.	ABOVE RISER DIAGRAM IS FOR REFERENCE PURPOSES ONLY. E.C. SHALL VERIFY EXACT POWER DISTRIBUTION IN FIELD AND INFORM ENGINEER ON RECORD FOR ANY DISCREPANCY.
B.	E.C. SHALL VERIFY INCOMING SERVICE AMPERAGE, WIRE SIZING AND DISTRIBUTION.
C.	ELECTRICAL CONTRACTOR TO COORDINATE FAULT CURRENT (Isc) RATING WITH UTILITY COMPANY AND AHJ PRIOR TO COMMENCING ANY WORK.
D.	E.C. TO VERIFY OPERABLE CONDITIONS OF EXISTING DEVICES IN FIELD. REPLACE/RECTIFY IF FOUND IN OPERABLE. BASE BID ACCORDINGLY.

ELECTRICAL RISER SYMBOLS:	
	NEW
	EXISTING ITEM/FEEDER TO REMAIN
	EXISTING ITEM/FEEDER TO BE DISCONNECTED & REMOVED



① ELECTRICAL RISER DIAGRAM
1/4" = 1'-0"

PANEL SCHEDULE GENERAL NOTES--	
A.	E.C. SHALL ENSURE THAT ALL BREAKERS IN THE PANEL ARE CLEARLY AND ACCURATELY LABELED.
B.	" * " = PROVIDE NEW BREAKER IN THE EXISTING PANEL.

PANEL: A (EXISTING)										MOUNTING: SURFACE				
208Y/120		VOLTS,	3	PHASE,	4	WIRE	PANEL LOCATION: IT CLOSET							
MAIN CB: 200A		MLO: NA		BUS: 225A		MIN,	FED FROM: EXISTING ELECTRICAL METER							
NOTE: L: LIGHTING, R: RECEPTACLES, K: KITCHEN/EQUIPMENTS, C: REFRIGERATION, H: HVAC, M: MOTOR, O: OTHER/MISCELLANEOUS														
CKT NO.	TRIP AMPS	DESCRIPTION OF LOAD	LOAD TYPE	LOAD (KVA)	MINIMUM BRANCH CIRCUIT	PER PHASE (KVA)			MINIMUM BRANCH CIRCUIT	LOAD (KVA)	LOAD TYPE	DESCRIPTION OF LOAD	TRIP AMPS	CKT NO.
						A	B	C						
1	20	RESTROOM RECEPTACLE	R	0.18	2#12, #12G, #3/4"C	1.01			2#12, #12G, #3/4"C	0.83	L	LIGHTING-OPEN OFFICE LIGHTS	20	2
3	20	REFRIGERATOR	E	0.65	2#12, #12G, #3/4"C		1.11		2#12, #12G, #3/4"C	0.46	L	LIGHTING-OFFICES	20	4
5			H	3.00				3.67	2#12, #12G, #3/4"C	0.67	L	LIGHTING	20	6
7	40/3P	EXISTING MECHANICAL EQUIPMENT	H	3.00	EXISTING	3.28			2#12, #12G, #3/4"C	0.28	L	LIGHTING	20	8
9			H	3.00			5.76		2#10, #10G, #3/4"C	2.76	L	EXTERIOR SIGNAGE	30	10
11	20	WATER FOUNTAIN	O	0.90	2#12, #12G, #3/4"C			1.65	2#12, #12G, #3/4"C	0.75	E	MICROWAVE	20	12
13						0.36			2#12, #12G, #3/4"C	0.36	R	OFFICE 101	20	14
15	40/3P	SPARE					0.36		2#12, #12G, #3/4"C	0.36	R	OFFICE 102	20	16
17								0.23	2#12, #12G, #3/4"C	0.36	R	OFFICE 103	20	18
19	20	IT CLOSEY QUAD RECEPTACLE	R	1.84	2#12, #12G, #3/4"C	2.07			2#12, #12G, #3/4"C	0.23	O	TIME CLOCK	20	20
21	20	IT CLOSEY QUAD RECEPTACLE	R	1.84	2#12, #12G, #3/4"C		1.84					SPARE	20	22
23	20	RECEPTION RECEPTACLE	R	0.36	2#12, #12G, #3/4"C			1.82		1.46	O		</	

PLUMBING LEGEND		
DESCRIPTION	ABBREV.	SYMBOL
SANITARY WASTE PIPING	SAN	— — — SAN — — —
VENT PIPING	V	— — — — —
COLD WATER PIPING	CW	— — — — — CW — — — — —
HOT WATER PIPING	HW	— — — — — HW — — — — —
HOT WATER RETURN PIPING	HWR	— — — — — HWR — — — — —
FLOOR DRAIN	FD	— — — — — FD — — — — —
GATE VALVE	GV	— — — — — GV — — — — —
TEE UP		— — — — — TEE UP — — — — —
TEE DOWN		— — — — — TEE DOWN — — — — —
90° UP		— — — — — 90° UP — — — — —
90° DOWN		— — — — — 90° DOWN — — — — —
SHUT OFF VALVE	SOV	— — — — — SOV — — — — —
BELOW FINISHED FLOOR	BFF	— — — — — BFF — — — — —
POINT OF NEW CONNECTION		— — — — — POINT OF NEW CONNECTION — — — — —
WATER HEATER	WH	— — — — — WH — — — — —
FLOOR CLEANOUT	FCO	— — — — — FCO — — — — —

CODE COMPLIANCE	
a.	2021 INTERNATIONAL BUILDING CODE
b.	2021 INTERNATIONAL MECHANICAL CODE
c.	2021 INTERNATIONAL PLUMBING & FUEL GAS CODE
d.	2023 NFPA 70 NATIONAL ELECTRICAL CODE
e.	2021 INTERNATIONAL ENERGY CONSERVATION CODE

PLUMBING DRAWING LIST	
P-0.1	PLUMBING NOTES, SYMBOLS, SPECS & ABBREVIATIONS
P-1.1	PLUMBING FLOOR PLANS
P-2.1	PLUMBING DETAILS
P-3.1	PLUMBING RISER DIAGRAMS

BUILDING DEPARTMENT PLUMBING NOTES	
------------------------------------	--

- ALL PLUMBING SYSTEMS (SANITARY, WASTE, VENT & WATER DISTRIBUTION PIPING SYSTEMS) AND ASSOCIATED EQUIPMENT SHALL BE INSTALLED, OPERATED AND MAINTAINED IN ACCORDANCE WITH THE REQUIREMENTS OF MARYLAND STATE PLUMBING CODE (2021 INTERNATIONAL PLUMBING CODE).
- INSTALLATION OF UNDERGROUND SANITARY DRAINAGE AND VENT PIPING SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION IN PC 702.2
- PROTECTION OF PIPING AND PLUMBING SYSTEM COMPONENTS AS PER SECTION IN PC 305.
- TRENCHING, EXCAVATION AND BACKFILL AS PER SECTION IN PC 306.
- RODENT PROOFING AS PER IN PC 304.
- MATERIALS USED IN PLUMBING SYSTEMS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION IN PC 303, PC 402, PC 605, PC 702, PC 802, PC 902 & PC 1004.
- EQUIPMENT CONNECTIONS AND JOINING OF PIPING SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF CHAPTERS 4, 5, 6, 7 AND 9.
- DEEP SEAL TRAPS FOR FLOOR DRAINS SHALL BE PROVIDED AS PER PC 1002, AND CLEAN-OUTS SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION PC 708
- BUILDING HOUSE TRAPS SHALL BE PROVIDED AS PER SECTION PC 1002.
- VERTICAL AND HORIZONTAL PIPING SHALL BE SUPPORTED IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION PC 308
- WATER SUPPLY SYSTEMS SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE REQUIREMENTS OF CHAPTER 6 SECTION PC 601-603, 604, 606, 607, 608, 610
- THE SANITARY DRAINAGE SYSTEM SHALL BE SIZED AND INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF PC CHAPTER 7 SECTIONS PC 701 THROUGH PC 712.
- VENT PIPING FOR THE SANITARY DRAINAGE SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF CHAPTER 9 SECTIONS PC 901 THROUGH PC 912 THROUGH PC 917.

- PLUMBING SPECIFICATIONS
1. BASIC PLUMBING REQUIREMENTS, MATERIALS AND METHODS
- 1.01 SCOPE
- A. PROVIDE ALL MATERIAL, TOOLS, SUPERVISION AND LABOR INCLUDING ALL MISCELLANEOUS AND INCIDENTAL ITEMS REQUIRED FOR COMPLETE AND OPERABLE PLUMBING INSTALLATIONS AS SHOWN OR DESCRIBED ON THE DRAWINGS AND IN THESE SPECIFICATIONS.
- B. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING AND NEW CONDITIONS AND MATERIALS WITHIN THE CONSTRUCTION AREA. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE OWNER'S SATISFACTION.
- C. OBTAIN ALL PERMITS, PAY ALL PERMIT FEES AND SCHEDULE ALL REQUIRED INSPECTIONS. COPIES OF ALL PERMITS AND INSPECTION CERTIFICATES SHALL BE FORWARDED TO THE OWNER FOR RECORD.
- D. THE GENERAL CONDITIONS OF THE CONTRACT AND ALL DIVISION 1 REQUIREMENTS APPLY TO THE WORK OF THIS SECTION.
- E. THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO SUBMITTING BID TO DETERMINE CONDITIONS AND THE EXTENT OF THE WORK. BY COMMENCING WORK, THE CONTRACTOR ACKNOWLEDGES HIS CONFIRMATION OF ALL CONDITIONS AS ACCEPTABLE WITH REFERENCE TO HIS CONTRACT, SCOPE OF WORK AND BID PRICE SUCH THAT NO ADDITIONAL COMPENSATION SHALL BE FORTHCOMING FOR UNFORESEEN EXISTING CONDITIONS.
- F. IN ALL AREAS SUBJECT TO FREEZING CONDITIONS, THE CONTRACTOR SHALL PROVIDE FREEZE PROTECTION FOR ALL DOMESTIC WATER PIPING INSTALLED UNDER HIS CONTRACT.
- G. ALL ELECTRICAL REQUIREMENTS SHALL BE COORDINATED WITH THE CONTRACTOR FOR ELECTRICAL WORK. THIS CONTRACTOR IS RESPONSIBLE FOR ALL LOW VOLTAGE WIRING FOR EQUIPMENT INSTALLED UNDER HIS CONTRACT. THE CONTRACTOR FOR ELECTRICAL WORK IS RESPONSIBLE FOR LINE VOLTAGE POWER WIRING ONLY.
- H. COLOR AND FINISH SELECTIONS FOR ALL MATERIALS, INCLUDING PAINTING OF PIPING, SHALL BE AS DIRECTED AND/OR APPROVED BY THE ARCHITECT.
- I. MINOR DETAILS NOT SHOWN OR SPECIFIED, BUT NECESSARY FOR THE PROPER AND ACCEPTABLE CONSTRUCTION, INSTALLATION OR OPERATION OF ANY PART OF THE WORK AS DETERMINED BY THE ENGINEER SHALL BE INCLUDED AS IF SPECIFIED OR INDICATED ON THE DRAWINGS.
- J. THIS CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIREMENTS FOR THE INSTALLATION, CONNECTION, EXTENSION OR MODIFICATION TO ALL UTILITY SERVICES WITH RESPECTIVE PROVIDERS INCLUDING PAYMENT OF ALL ASSOCIATED FEES.
- K. THE CONTRACTOR IS RESPONSIBLE FOR ALL PAINTING ASSOCIATED WITH CUTTING AND PATCHING. ALL PAINTING IN AREAS WITH COMPLETE FINISH RENOVATIONS SHALL BE PROVIDED BY THE GENERAL CONTRACTOR.
- 1.02 SUBMITTALS
- A. SUBMITTAL REQUIREMENTS SHALL BE COORDINATED WITH THE ARCHITECT AND AUTHORITIES HAVING JURISDICTION. UNLESS OTHERWISE DIRECTED, CONTRACTOR SHALL PROVIDE SUBMITTALS AS LISTED BELOW.
- PIPE AND FITTINGS
 - VALVES
 - HANGERS AND SUPPORTS
 - PLUMBING PIPING LAYOUT
 - TESTS
 - PLUMBING FIXTURES
 - WATER HEATERS & ACCESSORIES
 - FLOOR DRAINS
 - MIXING VALVES
 - ALL SCHEDULED PLUMBING EQUIPMENT
- B. SUBMITTALS FROM SUPPLIERS OR MANUFACTURERS WHICH DO NOT BEAR THE STAMP OF THE SUBMITTING CONTRACTOR INDICATING THAT THE CONTRACTOR HAS REVIEWED THE SUBMITTAL FOR CONFORMANCE WITH THE PROJECT REQUIREMENTS WILL BE RETURNED REJECTED.
- C. THE ENGINEER'S REVIEW OF SUBMITTALS IS A COURTESY WHICH DOES NOT RELIEVE THE CONTRACTOR FROM CONFORMING WITH THE CONSTRUCTION DOCUMENTS, REGARDLESS OF THE ACTION INDICATED BY THE SHOP DRAWINGS STAMP.
- D. SUBMIT PROOF OF APPROVAL AND/OR CONFIRMATION OF SATISFACTORY TEST RESULTS TO THE OWNER AND THE ARCHITECT.
- E. SUBMIT TO THE OWNER'S MAINTENANCE PERSONNEL OPERATION AND MAINTENANCE DATA FOR ALL SYSTEM COMPONENTS, SERVICING REQUIREMENTS, INSPECTION DATA, REPLACEMENT PART NUMBERS AND AVAILABILITY AND CONTACT INFORMATION FOR SERVICE/SUPPLY COMPANY.
- F. FOR ALL BELOW GRADE PIPING WHERE ACTUAL INSTALLATION DEVIATES FROM CONSTRUCTION DRAWINGS, THE CONTRACTOR SHALL PROVIDE AS-BUILT DRAWINGS INDICATING BELOW GRADE PIPE LOCATIONS DIMENSIONED TO NEAREST COLUMN LINES.
- G. RECORD AS-BUILT DRAWINGS SHALL BE SUPPLIED TO THE OWNER/TENANT AFTER COMPLETION OF THE WORK SHOWING ANY ALTERATIONS, ADDITIONS AND/OR DELETIONS TO THE SYSTEM(S) INSTALLED.
- 1.03

PLUMBING FIXTURE SCHEDULE								
LEGEND	PLUMBING FIXTURE	MANUFACTURE AND MODEL NUMBER	CONNECTION SIZE -- INCHES					REMARKS
			TRAP	SOIL/WASTE	VENT	COLD WATER	HOT WATER	
WC-1	FLOOR MOUNTED WATER CLOSET	MANUFACTURE: AMERICAN STANDARD MODEL: CADET 2467.016	-	4"	2"	¾"	-	FLOOR MOUNTED TANK/HEAVY DUTY PLUS COMMERCIAL TOILET SEAT
L-1	LAVATORY	MANUFACTURE: AMERICAN STANDARD MODEL: LUCERNE 0355.02	1½"	2"	1½"	½"	½"	PROVIDE WITH P-TRAP.PROVIDE WITH TMV-1.LIMIT TEMP. TO 110° F. FAUCET: MOEN MODEL #8886 FINISH: CHROME (0.5 GPM)
FD-1	FLOOR DRAIN	MANUFACTURE: ZURN MODEL: ZN415	3"	3"	2"	-	-	PROVIDE WITH TRAP PRIMER
DF-1	DRINKING FOUNTAIN	MANUFACTURE: ELKAY MODEL: LZSTLDDLC	1½"	2"	1½"	½"	-	PROVIDE WITH P-TRAP FILTERED FOUNTAIN OR EQUIVALENT
MS-1	MOP SINK	MANUFACTURE: MUSTEE MODEL: 63M	3"	3"	2"	¾"	¾"	PROVIDE WITH P-TRAP FAUCET: MUSTEE #63.600A
PS-1	PANTRY SINK	MANUFACTURE: ELKAY MODEL: LWSB151562K	2"	2"	2"	¾"	¾"	PROVIDE WITH P-TRAP

NOTE: CONTRACTOR TO COORDINATE WITH ARCHITECTURAL DRAWINGS FOR ALL PLUMBING FIXTURES SPECIFICATIONS AND MOUNTING HEIGHT INSTALLATION.

PLUMBING KEYED NOTES:

1

EXTEND AND CONNECT NEW 4" SANITARY LINE TO EXISTING UNDERGROUND SANITARY WASTE. CONTRACTOR TO FIELD COORDINATE, VERIFY LOCATION, DIRECTION, AND ELEVATION OF EXISTING SANITARY PIPING.

2

CONNECT TO NEW 3" VENT PIPE TO EXISTING VENT LINE. CONTRACTOR TO FIELD VERIFY SIZE, ROUTING & LOCATION ON SITE.

3

EXTEND AND CONNECT NEW 1" CW PIPING TO EXISTING CW LINE. CONTRACTOR TO CONFIRM WATER SUBMETER, BACKFLOW PREVENTER REQUIREMENTS WITH LANDLORD. CONTRACTOR TO FIELD VERIFY EXACT SIZE, ROUTING AND LOCATION PRIOR TO BID.

4

PROVIDE HOT WATER MIXING VALVE (TMV-1) AND SET MAXIMUM OUTLET TEMPERATURE AT 110°F.

5

ROUTE DRAIN LINE FROM T&P RELIEF ON WATER HEATER TO MOP SINK. PROVIDE AIR GAP PER LOCAL CODE.

6

CONTRACTOR TO INSTALL NEW WATER HEATER(WH-1) WALL MOUNTED ABOVE MOP SINK. PROVIDE WATER HEATER WITH EXPANSION TANK(ET-1), RECIRCULATION PUMP(RCP-1), THERMO STATIC MIXING VALVE(TM-2) AND WALL MOUNTED SUPPORT. REFER SHEET P-3.0 FOR INSTALLATION DETAILS AND P-4.0 FOR EQUIPMENT SCHEDULE.

7

PROVIDE FLOOR DRAIN WITH TRAP PRIMER. REFER SHEET P-3.0 FOR INSTALLATION DETAILS.

CONTRACTOR NOTE:

A.

IT IS RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE ARCHITECT, LANDLORD OR TENANT OF ANY DISCREPANCIES ENCOUNTERED ON THE PLANS OR IN EXISTING SITE CONDITIONS PRIOR TO SUBMISSION OF BID.

B.

BIDDERS ARE TO VISIT THE SITE AND FAMILIARIZE THEMSELVES WITH EXISTING CONDITIONS AND SATISFY THEMSELVES AS TO THE NATURE AND SCOPE OF THE WORK.

C.

THE BASE BID SHALL REFLECT MODIFICATIONS TO SYSTEMS AND DEVICES AS REQUIRED BY STATE, LOCAL AND FEDERAL CODES WHETHER INDICATED OR NOT ON CONTRACT DOCUMENTS.


D.

THE SUBMISSIONS OF A BID WILL BE EVIDENCE THAT SUCH AS EXAMINATION AND COMPLIANCE WITH THE GOVERNING CODES/REQUIREMENTS HAS BEEN MADE.


E.

LATER CLAIMS FOR LABOR, EQUIPMENT OR MATERIALS REQUIRED OR FOR DIFFICULTIES ENCOUNTERED WHICH COULD HAVE BEEN FORSEEN HAD AND EXAMINATION AND CODE/REQUIREMENTS REVIEW BEEN MADE, WILL NOT BE ALLOWED.

PLUMBING LEGEND		
DESCRIPTION	ABBREV.	SYMBOL
SANITARY WASTE PIPING	SAN	--- SAN ---
VENT PIPING	V	--- V ---
COLD WATER PIPING	CW	--- CW ---
HOT WATER PIPING	HW	--- HW ---
HOT WATER RETURN PIPING	HWR	---HWR---
FLOOR DRAIN	FD	FD
GATE VALVE	GV	GV
TEE UP		TEE UP
TEE DOWN		TEE DOWN
90° UP		90° UP
90° DOWN		90° DOWN
SHUT OFF VALVE	SOV	SOV
BELOW FINISHED FLOOR	BFF	BFF
WATER HEATER	WH	WH
FLOOR CLEANOUT	FDO	FDO



1 FLOOR PLAN-SANITARY
1/4" = 1'-0"



2 FLOOR PLAN-WATER
1/4" = 1'-0"

These drawings are the property of the Architect. Signal Workline Heeser Architects P.C. Unauthorized reproduction for any purpose is an infringement upon copyright laws. Violators will be subject to prosecution by fullest extent of the law.
Written dimensions on these drawings shall have precedence over scale dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job and this office must be notified of any variation from the dimensions and conditions shown by these drawings.












NY ENGINEERS
NEARBY ENGINEERS
382 NE 191ST STREET, SUITE 49674, MIAMI, FL 33179
PH - 914.257.3455 | WWW.NY-ENGINEERS.COM

Revision Schedule		
#	Date	Revision
1	07/02/25	PERMIT ISSUE

PERMIT ISSUE

07/02/25

Professional Certification
I certify that these documents were prepared or approved




These drawings are the property of the Architect, Signal Warfare Hesser Architects P.C. Unauthorized reproduction for any purpose is an infringement upon copyright laws. Violators will be subject to prosecution by federal extent of the law.


Written dimensions on these drawings shall have precedence over scale dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and this office must be notified of any variation from the dimensions and conditions shown by these drawings.

NY ENGINEERS

NEARBY ENGINEERS
382 NE 191ST STREET, SUITE 4674, MI



1 FLOOR PLAN-SANITARY
SCALE: N.T.S.



2 RISER DIAGRAM-WATER
SCALE: N.T.S.

PLUMBING FIXTURE SCHEDULE								
LEGEND	PLUMBING FIXTURE	MANUFACTURE AND MODEL NUMBER	CONNECTION SIZE - INCHES					REMARKS
			TRAP	SOIL/WASTE	VENT	COLD WATER	HOT WATER	
WC-1	FLOOR MOUNTED WATER CLOSET	MANUFACTURE: AMERICAN STANDARD MODEL: CADET 2467.016	-	4"	2"	3/4"	-	FLOOR MOUNTED TANK/HEAVY DUTY PLUS COMMERCIAL TOILET SEAT
L-1	LAVATORY	MANUFACTURE: AMERICAN STANDARD MODEL: LUCERNE 0355.02	1 1/2"	2"	1 1/2"	1/2"	1/2"	PROVIDE WITH P-TRAP. PROVIDE WITH TMV-1. LIMIT TEMP. TO 110° F. FAUCET: MOEN MODEL #8886 FINISH: CHROME (0.5 GPM)
FD-1	FLOOR DRAIN	MANUFACTURE: ZURN MODEL: ZN415	3"	3"	2"	-	-	PROVIDE WITH TRAP PRIMER
DF-1	DRINKING FOUNTAIN	MANUFACTURE: ELKAY MODEL: LZSTLDDLC	1 1/2"	2"	1 1/2"	1/2"	-	PROVIDE WITH P-TRAP FILTERED FOUNTAIN OR EQUIVALENT
MS-1	MOP SINK	MANUFACTURE: MUSTEE MODEL: 63M	3"	3"	2"	3/4"	3/4"	PROVIDE WITH P-TRAP FAUCET: MUSTEE #63.600A
PS-1	PANTRY SINK	MANUFACTURE: ELKAY MODEL: LWSB151562K	2"	2"	2"	3/4"	3/4"	PROVIDE WITH P-TRAP

NOTE: CONTRACTOR TO COORDINATE WITH ARCHITECTURAL DRAWINGS FOR ALL PLUMBING FIXTURES SPECIFICATIONS AND MOUNTING HEIGHT INSTALLATION.

HOT WATER HEATER WITH STORAGE									
TAG No.	QUANTITY	NO. ELEMENTS	LOCATION	MAX. INPUT (KW/MBH)	STOR. CAP (GAL)	RECOVERY CAP. (GPH) @100° RISE	TYPE	ELECT. CHARACTERISTICS CONTROLS	REMARKS
WH-1	1	1	ABOVE MOP SINK	5 KW	20	18	ELECTRIC STORAGE TYPE WATER HEATER	208V/14/60Hz	- DIMENSIONS 21-3/4"D X 22-1/4"H - PROVIDE EXPANSION TANK (ET-1) & RCP-1 AS PER SCHEDULE - WALL MOUNTED HEATER - PROVIDE HOLDRITE 30-SWHP-WM PLATFORM FOR WALL MOUNTED WATER HEATER - PROVIDE WITH TMV-2. LIMIT TEMPRATURE TO 120° F ON HOT WATER OUTLET.

EXPANSION TANK SCHEDULE							
ITEM	QUANTITY	LOCATION	SERVICE	GALLONS	MANUFACTURER & MODEL NO.	WEIGHT(LBS)	DIMENSION
EXPANSION TANK (ET-1)	1	REFER PLANS	HOT WATER	2	THERM-X-TROL ST-5	5	DIMENSIONS - 13"(H)x8"(DIA.)

THERMOSTATIC MIXING VALVE SCHEDULE							
TAG	LOCATION	SERVICE	CAPACITY RANGE (GPM)		OUTLET TEMP. RANGE (°F)		REMARKS
			MIN.	MAX.	MIN.	MAX.	
TMV-1	LAVATORY	HOT WATER	0.06	3.10	95	115	WATTS MODEL ZW3870XLT-4P -LEAD FREE -ASSE 1070 LISTED -CSA APPROVED
TMV-2	EXISTING WATER HEATER	HOT WATER	0.1	30	100	160	CONTROLS MV17-3 -LEAD FREE SOLID DZR BRASS BODY -ASSE 1017 LISTED -CSA APPROVED

RECIRCULATING PUMP SCHEDULE					
ITEM	QUANTITY	GPM	TOTAL HEAD (FT)	MOTOR HP	MANUFACTURER & MODEL NO.
RCP-1	1	2	10	0.115	GRUNDFOS UP 15-18 BS

These drawings are the property of the Architect, Sigurd Winslow Hesser Architects P.C. Unauthorized reproduction for any purpose is an infringement upon copyright laws. Violators will be subject to prosecution by fullest extent of the law.
Written dimensions on these drawings shall have precedence over scale dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job, and this office must be notified of any variation from the dimensions and conditions shown by these drawings.

NY ENGINEERS
NEARBY ENGINEERS
382 NE 191ST STREET, SUITE 46674, MIAMI, FL 33179
PH - 914.257.3455 | WWW.NY-ENGINEERS.COM

Revision Schedule		
#	Date	Revision
07/02/25	PERMIT ISSUE	

PERMIT ISSUE

07/02/25

Professional Certification