

MECHANICAL SYMBOLS LIST

AC-1	TXF-1	EQUIPMENT SYMBOL
AIR DEVICES		
CEILING DIFFUSER SUPPLY		
		CEILING DIFFUSER RETURN
		RETURN AIR GRILLE WALL MOUNTED
DUCT ACCESSORIES		
		BACKDRAFT DAMPER
		VOLUME DAMPER W/ ACCESS DOOR
CONTROLS AND SENSORS		
		THERMOSTAT
		HOOD TEMPERATURE SENSOR
		DUCT SMOKE DETECTOR
		MANUAL ON/OFF SWITCH FOR HOOD
		TEMPERATURE SENSOR
DUCTWORK		
		AIR DUCT W/ 1.5" ACOUSTICAL LINING
		FLEXIBLE DUCT
		FLEXIBLE CONNECTION
		RECTANGULAR DUCT (WIDTH X DEPTH)
		SUPPLY AIR RECTANGULAR DUCT CROSS SECTION
		RETURN AIR RECTANGULAR DUCT CROSS SECTION
		ROUND DUCT (DIAMETER)
		ROUND DUCT CROSS SECTION
ABBREVIATIONS		
AL		ACOUSTIC LINING
BD		BACKDRAFT DAMPER
CDS		CEILING DIFFUSER SUPPLY
CDR		CEILING DIFFUSER RETURN
CFM		CUBIC FEET OF AIR PER MINUTE
LDS		LINEAR SLOT DIFFUSER
FC		FLEXIBLE CONNECTION
IEER		INTEGRATED ENERGY EFFICIENCY RATIO
ACCU		AIR COOLED CONDENSING UNIT
RTU		ROOF TOP UNIT
TEF		TOILET EXHAUST FAN
KEF		KITCHEN EXHAUST FAN
VD		VOLUME DAMPER
RG		RETURN GRILLE
MAU		MAKE UP AIR UNIT
MECHANICAL DRAWING LIST		
M0.1		MECHANICAL ABBREVIATIONS, SYMBOLS LIST & GENERAL NOTES
M0.2		MECHANICAL SPECIFICATIONS
M1.0		MECHANICAL FLOOR PLAN
M1.1		MECHANICAL ROOF PLAN & SECTIONS
M5.1		MECHANICAL DETAILS (1 OF 3)
M5.2		MECHANICAL DETAILS (2 OF 3)
M5.3		MECHANICAL DETAILS (3 OF 3)
M6.1		MECHANICAL SCHEDULES
H1.0	(1 OF 4)	KITCHEN HOOD DRAWINGS (1 OF 4)
H1.1	(2 OF 4)	KITCHEN HOOD DRAWINGS (2 OF 4)
H1.2	(3 OF 4)	KITCHEN HOOD DRAWINGS (3 OF 4)
H1.3	(4 OF 4)	KITCHEN HOOD DRAWINGS (4 OF 4)
APPLICABLE CODES		
IBC		2018 INTERNATIONAL BUILDING CODE
IFC		2018 INTERNATIONAL FIRE CODE
IMC		2018 INTERNATIONAL MECHANICAL CODE
IPC		2018 INTERNATIONAL PLUMBING CODE
IECC		2018 INTERNATIONAL ENERGY CONSERVATION CODE
NEC		2014 NATIONAL ELECTRICAL CODE W/LOCAL AMENDMENTS
IFGC		2018 INTERNATIONAL FUEL GAS CODE

CITY OF PITTSBURGH BUILDING DEPARTMENT NOTES

ALL WORK SHALL COMPLY WITH APPLICABLE SECTIONS OF 2018-CITY OF PITTSBURGH BUILDING CODE AND RULES AND REGULATIONS OF THE DEPARTMENT OF BUILDINGS TO DATE.

- THE CONTRACTOR SHALL ENGAGE THE SERVICES OF A PROFESSIONAL ENGINEER TO PROVIDE THE REQUIRED SPECIAL INSPECTIONS AND TESTS.
- TESTS WILL BE CONDUCTED UNDER DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, ARCHITECT OR OTHER PERSON HAVING NOT LESS THAN FIVE (5) YEARS EXPERIENCE SUPERVISING THE INSTALLATION OF SUCH MECHANICAL SYSTEMS. THE TESTS WILL SHOW COMPLIANCE WITH 2018 INTERNATIONAL BUILDING CODE REQUIREMENTS AS OUTLINES IN SECTION [BC 1704].
- THE LICENSED PROFESSIONAL ENGINEER, ARCHITECT OR OTHER PERSON HAVING NOT LESS THAN FIVE (5) YEARS EXPERIENCE SUPERVISING THE INSTALLATION OF SUCH MECHANICAL SYSTEMS AND CONDUCTING SUCH TESTS WILL FILE DOCUMENTATION AND REPORTS OF TESTS THAT THE SYSTEM COMPLIES WITH THE CONSTRUCTION DOCUMENTS AND APPLICABLE LAWS.
- SMOKE DETECTOR SHALL MEET UL268A.
- THE FOLLOWING WORK ITEMS, COMPONENTS, MATERIALS, CAPACITIES, ETC. SHALL COMPLY WITH THE REFERENCED CODE OR STANDARD:
 - A. STANDARDS OF HEATING – 2018 IMC SECTION 309
 - B. DUCT CONSTRUCTION AND INSTALLATION – 2018 IMC SECTION 603
 - C. AIR INTAKES, EXHAUSTS AND RELIEF – 2018 IMC SECTION 403.
 - D. AIR FILTERS – 2018 IMC SECTION 605
 - E. GAS FIRED EQUIPMENT – 2018 IMC SECTION 901
- MINIMUM TEMPERATURE TO BE MAINTAINED IN OCCUPIED SPACES DURING HEATING SEASON: 68 DEG. FAHRENHEIT.
- VENTILATION FOR ALL AREA SHALL COMPLY WITH 2018 IMC SECTION 401.
- A STATEMENT SHALL BE FILED BY THE OWNER OR TENANT IN POSSESSION THAT THE VENTILATION SYSTEM WILL BE KEPT IN CONTINUOUS OPERATION AT ALL TIMES DURING THE NORMAL OCCUPANCY OF THE STRUCTURE AS REQUIRED BY 2018 IMC SECTION 403.
- REFER TO ARCHITECTURAL DRAWINGS FOR REQUIRED FIRE-RATED WALL AND SMOKE WALL CONSTRUCTION AND LOCATION.
- THESE PLANS ARE APPROVED ONLY FOR THE WORK INDICATED ON THE APPLICATION SPECIFICATION SHEET. ALL OTHER MATTERS SHOWN ARE NOT TO BE RELIED UPON OR TO BE CONSIDERED AS EITHER BEING APPROVED OR IN ACCORDANCE WITH APPLICABLE CODES.
- ALL HEATING AND COOLING LOADS CALCULATED PER ASHRAE/ACCA 183.

THERMOSTATIC CONTROLS:

C403.4.1 THERMOSTATIC CONTROLS

THE SUPPLY OF HEATING AND COOLING ENERGY TO EACH ZONE SHALL BE CONTROLLED BY INDIVIDUAL THERMOSTATIC CONTROLS CAPABLE OF RESPONDING TO TEMPERATURE WITHIN THE ZONE. WHERE HUMIDIFICATION OR DEHUMIDIFICATION OR BOTH IS PROVIDED, AT LEAST ONE HUMIDITY CONTROL DEVICE SHALL BE PROVIDED FOR EACH HUMIDITY CONTROL SYSTEM.

EXCEPTION: INDEPENDENT PERIMETER SYSTEMS THAT ARE DESIGNED TO OFFSET ONLY BUILDING ENVELOPE HEAT LOSSES, GAINS OR BOTH SERVING ONE OR MORE PERIMETER ZONES ALSO SERVED BY AN INTERIOR SYSTEM PROVIDED:

- THE PERIMETER SYSTEM INCLUDES AT LEAST ONE THERMOSTATIC CONTROL ZONE FOR EACH BUILDING EXPOSURE HAVING EXTERIOR WALLS FACING ONLY ONE ORIENTATION (WITHIN +/-45 DEGREES) (0.8 RAD) FOR MORE THAN 50 CONTIGUOUS FEET (15 240 MM); AND
- THE PERIMETER SYSTEM HEATING AND COOLING SUPPLY IS CONTROLLED BY THERMOSTATS LOCATED WITHIN THE ZONES SERVED BY THE SYSTEM.

C403.4.1.1 HEAT PUMP SUPPLEMENTARY HEAT

HEAT PUMPS HAVING SUPPLEMENTARY ELECTRIC RESISTANCE HEAT SHALL HAVE CONTROLS THAT, EXCEPT DURING DEFROST, PREVENT SUPPLEMENTARY HEAT OPERATION WHERE THE HEAT PUMP CAN PROVIDE THE HEATING LOAD.

C403.4.1.2 DEADBAND

WHERE USED TO CONTROL BOTH HEATING AND COOLING, ZONE THERMOSTATIC CONTROLS SHALL BE CAPABLE OF PROVIDING A TEMPERATURE RANGE OR DEADBAND OF AT LEAST 5°F (2.8°C) WITHIN WHICH THE SUPPLY OF HEATING AND COOLING ENERGY TO THE ZONE IS CAPABLE OF BEING SHUT OFF OR REDUCED TO A MINIMUM.

EXCEPTIONS:

1. THERMOSTATS REQUIRING MANUAL CHANGEOVER BETWEEN HEATING AND COOLING MODES.
2. OCCUPANCIES OR APPLICATIONS REQUIRING PRECISION IN INDOOR TEMPERATURE CONTROL AS APPROVED BY THE CODE OFFICIAL.

C403.4.1.3 SETPOINT OVERLAP RESTRICTION

WHERE A ZONE HAS A SEPARATE HEATING AND A SEPARATE COOLING THERMOSTATIC CONTROL LOCATED WITHIN THE ZONE, A LIMIT SWITCH, MECHANICAL STOP OR DIRECT DIGITAL CONTROL SYSTEM WITH SOFTWARE PROGRAMMING SHALL BE PROVIDED WITH THE CAPABILITY TO PREVENT THE HEATING SET POINT FROM EXCEEDING THE COOLING SET POINT AND TO MAINTAIN A DEADBAND IN ACCORDANCE WITH SECTION C403.2.4.1.2.

C403.4.2 OFF-HOUR CONTROLS

EACH ZONE SHALL BE PROVIDED WITH THERMOSTATIC SETBACK CONTROLS THAT ARE CONTROLLED BY EITHER AN AUTOMATIC TIME CLOCK OR PROGRAMMABLE CONTROL SYSTEM.

EXCEPTIONS:

1. ZONES THAT WILL BE OPERATED CONTINUOUSLY.
2. ZONES WITH A FULL HVAC LOAD DEMAND NOT EXCEEDING 6,800 BTU/H (2 KW) AND HAVING A READILY ACCESSIBLE MANUAL SHUTOFF SWITCH.

C403.4.2.1 THERMOSTATIC SETBACK CAPABILITIES

THERMOSTATIC SETBACK CONTROLS SHALL HAVE THE CAPABILITY TO SET BACK OR TEMPORARILY OPERATE THE SYSTEM TO MAINTAIN ZONE TEMPERATURES DOWN TO 55°F (13°C) OR UP TO 85°F (29°C).

C403.4.2.2 AUTOMATIC SETBACK AND SHUTDOWN CAPABILITIES

AUTOMATIC TIME CLOCK OR PROGRAMMABLE CONTROLS SHALL BE CAPABLE OF STARTING AND STOPPING THE SYSTEM FOR SEVEN DIFFERENT DAILY SCHEDULES PER WEEK AND RETAINING THEIR PROGRAMMING AND TIME SETTING DURING A LOSS OF POWER FOR AT LEAST 10 HOURS. ADDITIONALLY, THE CONTROLS SHALL HAVE A MANUAL OVERRIDE THAT ALLOWS TEMPORARY OPERATION OF THE SYSTEM FOR UP TO 2 HOURS; A MANUALLY OPERATED TIMER CAPABLE OF BEING ADJUSTED TO OPERATE THE SYSTEM FOR UP TO 2 HOURS; OR AN OCCUPANCY SENSOR.

C403.4.2.3 AUTOMATIC START CAPABILITIES

AUTOMATIC START CONTROLS SHALL BE PROVIDED FOR EACH HVAC SYSTEM. THE CONTROLS SHALL BE CAPABLE OF AUTOMATICALLY ADJUSTING THE DAILY START TIME OF THE HVAC SYSTEM IN ORDER TO BRING EACH SPACE TO THE DESIRED OCCUPIED TEMPERATURE IMMEDIATELY PRIOR TO SCHEDULED OCCUPANCY.

APPLICABLE CODES

GENERAL NOTES

- CONTRACTOR SHALL SURVEY THE AREA OF THIS WORK BEFORE SUBMITTING A BID AND SHALL BE RESPONSIBLE FOR NOTIFYING THE ARCHITECT OF ANY CONDITIONS WHICH WOULD PREVENT THE INSTALLATION OF THE WORK AS SHOWN ON DRAWINGS.
- ALL APPLICABLE CODES, LAWS AND REGULATIONS GOVERNING OR RELATING TO ANY PORTION OF THIS WORK ARE HEREBY INCORPORATED INTO AND MADE A PART OF THESE SPECIFICATIONS, AND THEIR PROVISIONS SHALL BE CARRIED OUT BY THE CONTRACTOR WHO SHALL INFORM THE OWNER, PRIOR TO SUBMITTING A PROPOSAL, OF ANY WORK OR MATERIALS WHICH VIOLATE ANY OF THE ABOVE LAWS AND REGULATIONS. ANY WORK DONE BY THE CONTRACTOR CAUSING SUCH VIOLATION SHALL BE CORRECTED BY THE CONTRACTOR.
- BEFORE PROCEEDING WITH ANY WORK IN OCCUPIED OR USED AREAS, THE CONTRACTOR SHALL APPLY TO OWNER FOR PERMISSION TO ENTER SUCH AREAS. THE CONTRACTOR IS OBLIGED TO PERFORM HIS WORK ONLY AT THE TIMES DESIGNATED BY OWNER. THERE WILL BE NO ADDITIONAL COMPENSATION FOR THE WORK PERFORMED AFTER HOURS OR ON OFF-DAYS WITHOUT PRIOR WRITTEN APPROVAL.
- THE WORK IN THE BUILDING SHALL BE DONE WHEN AND AS DIRECTED, AND IN A MANNER SATISFACTORY TO THE OWNER. THE WORK SHALL BE PERFORMED SO AS TO CAUSE THE LEAST POSSIBLE INCONVENIENCE AND DISTURBANCE TO THE PRESENT OCCUPANTS.
- THE CONTRACTOR'S PROPOSAL FOR ALL WORK SHALL BE PREDICATED ON THE PERFORMANCE OF THE WORK DURING REGULAR WORKING HOURS. WHEN SO DIRECTED, HOWEVER, THE CONTRACTOR SHALL INSTALL WORK IN OVERTIME AND THE ADDITIONAL COST TO BE CHARGED THEREFOR SHALL BE ONLY THE "PREMIUM" PORTION OF THE WAGES PAID.
- CONTRACTOR SHALL ASCERTAIN THE APPROPRIATE METHOD FOR BRINGING THE UNITS INTO AND THROUGH THE BUILDING TO POSITION UNIT IN LOCATION SHOWN ON THE PLANS. WHERE NECESSARY, EQUIPMENT SHALL BE SHIPPED FROM MANUFACTURER IN SECTIONS OF SIZE SUITABLE FOR MOVING THROUGH RESTRICTIVE SPACES. COORDINATE WITH BUILDING OWNER APPROPRIATE TIMES OF DAY SUCH EQUIPMENT MAY BE MOVED THROUGH ALL AREAS.
- DISCONNECT, REMOVE AND/OR RELOCATE EXISTING MATERIAL, EQUIPMENT AND OTHER WORK AS NOTED OR REQUIRED FOR PROPER INSTALLATION OF NEW SYSTEM.
- SUPPORT ALL DUCTWORK AND PIPING FROM BUILDING STRUCTURE AND/OR FRAMING IN AN APPROVED MANNER, WHERE OVERHEAD CONSTRUCTION DOES NOT PERMIT FASTENING OR SUPPORTS FOR EQUIPMENT, FURNISH ADDITIONAL FRAMING, INSERTS SHALL BE STEEL SLOTTED TYPE AND FACTORY PAINTED. SINGLE ROD SHALL BE SIMILAR TO GRINNELL FIG. 281, MULTI-ROD SHALL BE SIMILAR TO FEE & MASON SERIES 9000 WITH END CAPS AND CLOSURE STRIPS. MAXIMUM LOADING INCLUDING PIPES, DUCTWORK CONTENTS AND COVERING SHALL NOT EXCEED 75% OF RATED INSERT CAPABILITY, WHEN SUPPORTING FROM BUILDING USE BEAM CLAMPS IN APPROVED MANNER.
- PROVIDE ALL NECESSARY FLASHING AND COUNTER FLASHING TO MAINTAIN THE WATERPROOFING INTEGRITY OF THIS BUILDING AS REQUIRED BY THE INSTALLATION OR REMOVAL OF PIPES, DUCTS, LOUVERS, CONDUIT, AND EQUIPMENT. PROVIDE EQUIPMENT CURBS AND DUNNAGE STEEL AS REQUIRED.
- SEAL OPENINGS AROUND DUCTS AND PIPING THROUGH PARTITIONS, WALLS AND FLOORS (NOT IN SHAFTS) WITH MINERAL WOOL OR OTHER NONCOMBUSTIBLE MATERIAL (FIBERGLASS INSULATION IS NOT ACCEPTABLE).
- WHERE PENETRATIONS THROUGH FIRE RATED WALLS ARE NOT FIRE PROOFED THIS CONTRACTOR SHALL BE RESPONSIBLE TO SEAL SAME TO MAINTAIN THE RATED INTEGRITY.
- INSTALL WORK SO AS TO BE READILY ACCESSIBLE FOR OPERATION, MAINTENANCE AND REPAIR. MINOR DEVIATIONS FROM DRAWINGS MAY BE MADE TO ACCOMPLISH THIS, BUT CHANGES WHICH INVOLVE EXTRA COST SHALL NOT BE MADE WITHOUT APPROVAL.
- REMOVABLE ACCESS TILE AND/OR ACCESS DOOR ARE REQUIRED IN HUNG CEILINGS, SHAFTS AND WALLS FOR ALL VOLUME AND FIRE DAMPERS, AUTOMATIC DAMPERS AND ALL OTHER MECHANICAL EQUIPMENT AND DEVICES. HVAC CONTRACTOR TO FURNISH ACCESS LOCATION REQUIREMENTS TO GENERAL CONTRACTOR. ACCESS TILE IDENTIFICATION: PROVIDE BUTTONS, TABS, AND MARKERS TO IDENTIFY LOCATION OF CONCEALED VALVES, DAMPERS AND EQUIPMENT.
- THE CONTRACTOR SHALL KEEP ALL EQUIPMENT AND MATERIALS, AND ALL PARTS OF THE BUILDING, EXTERIOR SPACES AND ADJACENT STREETS, SIDEWALKS AND PAVEMENTS, FREE FROM MATERIAL AND DEBRIS RESULTING FROM THE EXECUTION OF THIS WORK. EXCESS MATERIALS WILL NOT BE PERMITTED TO ACCUMULATE EITHER ON THE INTERIOR OR THE EXTERIOR.
- UNLESS OTHERWISE SPECIFICALLY SPECIFIED, INCLUDE ALL CUTTING AND PATCHING OF EXISTING FLOORS, WALLS, PARTITIONS AND OTHER MATERIALS IN THE EXISTING BUILDING. THE CONTRACTOR SHALL RESTORE THESE AREAS TO ORIGINAL CONDITION.
- MATERIALS AND WORKMANSHIP, UNLESS OTHERWISE NOTED, SHALL BE IN ACCORDANCE WITH BUILDING STANDARDS.
- ALL EQUIPMENT SHALL BE PROVIDED WITH ONE YEAR WARRANTY PARTS AND LABOR AND FIVE YEARS ON COMPRESSORS. WARRANTY PERIOD BEGINS UPON PROJECT ACCEPTANCE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR HIS WORK WITH ITS COMPLETION AND FINAL ACCEPTANCE AND SHALL REPLACE ANY OF THE SAME WHICH MAY BE DAMAGED, LOST, OR STOLEN WITHOUT ADDITIONAL COST TO THE OWNER.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE FAILURE OF ANY DUCTWORK SYSTEM OR EQUIPMENT TO FUNCTION PROPERLY UPON COMPLETION OF HIS WORK UPON SAID SYSTEM OR EQUIPMENT.
- SUBMIT SHOP DRAWING OF ALL WORK WHICH MUST BE APPROVED BY THE ARCHITECT AND ENGINEER BEFORE WORK COMMENCES.

GENERAL HVAC NOTES

GENERAL:

- PROVIDE ALL MATERIAL AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE MECHANICAL SYSTEMS AS INDICATED ON THE DRAWINGS, AS SPECIFIED AND AS REQUIRED BY CODE.
- CONTRACT DOCUMENT DRAWINGS FOR MECHANICAL WORK (HVAC, PLUMBING, AND FIRE PROTECTION) ARE DIAGRAMMATIC AND ARE INTENDED TO CONVEY SCOPE AND GENERAL ARRANGEMENT ONLY.
- THE LOCATIONS OF ALL ITEMS SHOWN ON THE DRAWINGS OR CALLED FOR IN THE SPECIFICATIONS THAT ARE NOT FIXED BY DIMENSIONS ARE APPROXIMATE ONLY. THE EXACT LOCATIONS NECESSARY TO SECURE THE BEST CONDITIONS AND RESULTS MUST BE DETERMINED BY THE PROJECT SITE CONDITIONS AND SHALL HAVE THE APPROVAL OF THE ENGINEER BEFORE BEING INSTALLED. DO NOT SCALE DRAWINGS.
- WHEN MECHANICAL WORK (HVAC, PLUMBING, SHEET METAL, FIRE PROTECTION, ETC.) IS SUBCONTRACTED, IT SHALL BE THE MECHANICAL CONTRACTOR'S RESPONSIBILITY TO COORDINATE SUBCONTRACTORS AND THE ASSOCIATED CONTRACTS. WHEN DISCREPANCIES ARISE PERTAINING TO WHICH CONTRACTOR PROVIDES A PARTICULAR ITEM OF THE MECHANICAL CONTRACT OR WHICH CONTRACTOR PROVIDES FINAL CONNECTIONS FOR A PARTICULAR ITEM OF THE MECHANICAL CONTRACT, IT SHALL BE BROUGHT TO THE ATTENTION OF THE MECHANICAL CONTRACTOR, WHOSE DECISION SHALL BE FINAL.
- COORDINATE CONSTRUCTION OF ALL MECHANICAL WORK WITH ARCHITECTURAL, STRUCTURAL, CIVIL, ELECTRICAL WORK, ETC., SHOWN ON OTHER CONTRACT DOCUMENT DRAWINGS.
- INSTALL ALL MECHANICAL EQUIPMENT AND APPURTENANCES IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, CONTRACT DOCUMENTS, AND APPLICABLE CODES AND REGULATIONS.
- WHERE TWO OR MORE ITEMS OF THE SAME TYPE OF EQUIPMENT ARE REQUIRED, THE PRODUCT OF ONE MANUFACTURER SHALL BE USED.
- COORDINATE ALL EQUIPMENT CONNECTIONS WITH MANUFACTURERS' CERTIFIED DRAWINGS. COORDINATE AND PROVIDE ALL DUCT AND PIPING TRANSITIONS REQUIRED FOR FINAL EQUIPMENT CONNECTIONS TO FURNISHED EQUIPMENT. FIELD VERIFY AND COORDINATE ALL DUCT AND PIPING DIMENSIONS BEFORE FABRICATION.
- ALL CONTROL WIRE AND CONDUIT SHALL COMPLY WITH THE NATIONAL ELECTRIC CODE AND ELECTRICAL DIVISION OF THE SPECIFICATION.
- PROVIDE VIBRATION ISOLATION FOR ALL MECHANICAL EQUIPMENT TO PREVENT TRANSMISSION OF VIBRATION TO BUILDING STRUCTURE.
- LOCATE ALL TEMPERATURE, AND FLOW MEASURING DEVICES IN ACCESSIBLE LOCATIONS WITH THE STRAIGHT SECTION OF PIPE OR DUCT UP- AND DOWNSTREAM AS RECOMMENDED BY THE MANUFACTURER FOR GOOD ACCURACY.
- WHERE BEAMS ARE INDICATED TO BE PENETRATED WITH DUCTWORK OR PIPING, COORDINATE DUCTWORK AND PIPING LAYOUT WITH BEAM OPENING SIZE AND OPENING LOCATIONS. COORDINATION SHALL BE DONE PRIOR TO THE FABRICATION OF DUCTWORK, CUTTING OF PIPING, OR FABRICATION OF BEAMS.
- ALL MISCELLANEOUS STEEL REQUIRED TO ENSURE PROPER INSTALLATION AND AS SHOWN IN THE DETAILS FOR DUCTWORK, AND EQUIPMENT (UNLESS OTHERWISE NOTED) SHALL BE FURNISHED AND INSTALLED BY THE MECHANICAL CONTRACTOR.
- PROVIDE ACCESS PANELS FOR INSTALLATION IN WALLS AND CEILINGS, WHERE REQUIRED, TO SERVICE DAMPERS, VALVES, SMOKE DETECTORS, AND OTHER CONCEALED MECHANICAL EQUIPMENT. ACCESS PANELS SHALL BE TURNED OVER TO THE GENERAL CONTRACTOR FOR INSTALLATION. ACCESS PANEL

SPECIFICATIONS

SECTION 0001 – NOTICE TO BIDDERS

1.1 BIDDERS REPRESENTATIONS

- A. THE BIDDER BY MAKING A BID REPRESENTS THAT:
THE BIDDER HAS READ AND UNDERSTANDS THE BIDDING DOCUMENTS, TO THE EXTENT THAT SUCH DOCUMENTATION RELATES TO THE WORK FOR WHICH THE BID IS SUBMITTED, AND FOR OTHER PORTIONS OF THE PROJECT, IF ANY, BEING BID CONCURRENTLY OR PRESENTLY UNDER CONSTRUCTION.
- B. THE BID IS MADE IN COMPLIANCE WITH THE BIDDING DOCUMENTS.
- C. THE SPECIFICATIONS AND DRAWINGS ARE INTENDED TO SERVE JOINTLY AS A BASIS FOR THE BIDDER TO SUBMIT A CONTRACT PRICE FOR THE MATERIAL AND LABOR.
- D. SHOULD CONFLICTS OR DISCREPANCIES OCCUR WITHIN THE BIDDING DOCUMENTS, THE ITEM OR ITEMS IN DISPUTE THAT REPRESENT THE GREATER COST SHALL PREVAIL IN THE FINAL BID.
- E. THE BID IS BASED UPON THE MATERIALS, EQUIPMENT AND SYSTEMS REQUIRED BY THE BIDDING DOCUMENTS WITHOUT EXCEPTION.

1.2 EXISTING CONDITIONS AND COORDINATION

- A. THE BIDDER HAS VISITED THE SITE, BECOME FAMILIAR WITH LOCAL CONDITIONS UNDER WHICH THE WORK IS TO BE PERFORMED AND HAS CORRELATED THE BIDDER'S PERSONAL OBSERVATIONS WITH THE REQUIREMENTS OF THE PROPOSED BIDDING DOCUMENTS.
- B. THE BIDDER SHALL PROPOSE COORDINATION OF WORK SUCH THAT CONFLICTS WITH OTHER TRADES AND SPACE ALLOCATIONS ARE AVOIDED.
- C. THE BIDDER UNDERSTANDS THAT ANY CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR THE TIMELY COMPLETION AND ACCEPTANCE OF THEIR WORK AND THAT ANY ITEMS DAMAGED, LOST OR STOLEN DURING TIME OF CONSTRUCTION SHALL BE REPAIRED OR REPLACED WITHOUT ANY ADDITIONAL COST TO THE OWNER.
- D. PRIOR TO FINAL INSPECTION OF THE WORK, THE TAB SPECIALIST SHALL BALANCE ALL SYSTEMS AS INDICATED ABOVE TO THE REQUIREMENTS OF THE DESIGN.
- E. THE CONTRACTOR SHALL HAVE FURNISH AND INSTALL ALL ADDITIONAL BALANCING EQUIPMENT, PRESSURE TAPS, GAUGES AND OTHER EQUIPMENT AS REQUIRED FOR A PROPERLY BALANCED SYSTEM AT NO ADDITIONAL COST TO THE OWNER. SUCH ADDITIONAL EQUIPMENT SHALL ADHERE IN STRICT ACCORDANCE WITH THE RESPECTIVE EQUIPMENT MANUFACTURER'S RECOMMENDATIONS.
- F. THE CONTRACTOR SHALL HAVE THE TESTING AND BALANCING SPECIALIST COORDINATE ALL WORK OF THIS SECTION WITH THE BUILDING MANAGER. BALANCING WORK SHALL NOT CONFLICT WITH OTHER WORK SO AS TO MAINTAIN COMPLETION WITHIN THE SPECIFIED TIME.
- G. ALL INSTRUMENTS USED FOR TAB SHALL BE MAINTAINED IN GOOD WORKING CONDITION AND ACCURATELY CALIBRATED.
- H. TOLERANCES: PLUS OR MINUS 5 PERCENT OF DESIGN VALUES.
- I. INSPECTIONS: RANDOM CHECKS BY OWNER OR ARCHITECT TO VERIFY FINAL TESTING, ADJUSTING, AND BALANCING REPORT.
- J. ADDITIONAL TESTS: RANDOM TESTS WITHIN 90 DAYS OF COMPLETING TAB TO VERIFY BALANCE CONDITIONS AND SEASONAL TESTS.

END OF SECTION 0001

SECTION 0101 – QUALITY OF WORK

1.1 WORKMANSHIP

- A. ALL WORK SHALL BE FREE FROM DEFECTS IN MATERIALS AND WORKMANSHIP FOR A PERIOD OF ONE YEAR FROM DATE OF FINAL ACCEPTANCE.
- B. ALL DEFECTS WHICH DEVELOP OR ARE DISCOVERED WITHIN THIS PERIOD SHALL BE REPAIRED BY THE CONTRACTOR TO THE SATISFACTION OF THE ARCHITECT OR BUILDING MANAGER AT NO ADDITIONAL COST TO THE OWNER.
- C. UPON COMPLETION OF THE WORK THE CONTRACTOR SHALL REMOVE FROM THE SITE, ALL TOOLS, DEMOLISHED APPLIANCES AND ANY SURPLUS MATERIAL.

1.2 CODE COMPLIANCE

- A. ALL WORK SHALL MEET ALL STATE AND LOCAL CODES HAVING JURISDICTION.

END OF SECTION 0101

SECTION 0102 – REQUIRED DOCUMENTS

1.1 SHOP DRAWINGS

- A. A SET OF PRINTS FOR ANY MECHANICAL WORK INCLUDING BUT NOT LIMITED TO, DUCTWORK AND PIPING LAYOUT SHALL BE SUBMITTED FOR APPROVAL TO THE ENGINEER PRIOR TO CONSTRUCTION OR PURCHASE OF MATERIALS.

1.2 SUBMITTALS

- A. EQUIPMENT SUBMITTALS OF ALL PROPOSED MECHANICAL AND ANCILLARY EQUIPMENT INCLUDING ALL ACCESSORIES SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW. ALL PERTINENT MODELS, SIZES, ACCESSORIES AND CHOICES SHALL BE CLEARLY CHECKED, PRINTED OR OTHERWISE INDICATED ON THE SUBMITTALS.

1.3 RECORD DRAWINGS

- A. UPON COMPLETION OF THE WORK, A RECORD DRAWING SHALL BE SUBMITTED TO THE OWNER DEPICTING ALL SUBSEQUENT CHANGES, ADDITIONS AND OR CORRECTIONS TO THE CONTRACT DRAWINGS AND OR CONTRACT SCOPE MADE DURING CONSTRUCTION. THIS DRAWING SHALL REPRESENT A COMPLETE RECORD OF THE WORK INSTALLED.

1.4 EQUIPMENT OPERATING INSTRUCTIONS

- A. ON COMPLETION AND ACCEPTANCE OF WORK, THIS CONTRACTOR SHALL FURNISH WRITTEN INSTRUCTIONS, EQUIPMENT MANUALS AND DEMONSTRATE TO THE OWNER THE PROPER OPERATION AND MAINTENANCE OF ALL EQUIPMENT AND APPARATUS FURNISHED UNDER THIS CONTRACT.
- B. THESE INSTRUCTIONS SHALL BE TYPED ON 8-1/2 IN. X 11 IN. PAPER AND BOUND IN THREE-RING BINDERS WITH CLEAR ACETATE COVERS. THE CONTRACTOR SHALL GIVE THREE COPIES OF THE INSTRUCTIONS TO THE OWNER AND ONE ELECTRONIC COPY TO THE ENGINEER.

C. THE INSTRUCTION BOOKLET SHALL BE ORGANIZED IN SECTIONS, WITH ONE SECTION PER SYSTEM. THE COVER OF THE INSTRUCTION BOOKLET SHALL BEAR THE NAME, ADDRESS AND PHONE NUMBER OF THE PROJECT, ARCHITECT, ENGINEER, MECHANICAL CONTRACTOR AND SUBCONTRACTORS.

END OF SECTION 0102

SECTION 230593 – TESTING, ADJUSTING, AND BALANCING FOR HVAC

1.1 SUMMARY

- A. TESTING, ADJUSTING, AND BALANCING FOR THE FOLLOWING:

- 1. AIR SYSTEMS: CONSTANT VOLUME.

1.2 QUALITY ASSURANCE

- A. THE CONTRACTOR SHALL PROCUER THE SERVICES OF A TESTING, ADJUSTING AND BALANCING (TAB) SPECIALIST WHO SPECIALIZES IN HEATING, VENTILATION AND AIR CONDITIONING SYSTEMS. THE TAB AGENT SHALL HAVE THE FOLLOWING QUALIFICATIONS: AABC, NEBB OR TABB CERTIFIED.

1.3 EXECUTION

- A. THE TAB SPECIALIST SHALL PERFORM FLOW MEASUREMENTS OF ALL EXISTING AIR AND HYDRONIC SYSTEMS THAT ARE TO REMAIN OR TO BE INCORPORATED INTO NEW WORK PRIOR TO THE STARTING OF WORK IN THE PROJECT SCOPE. A REPORT OF THESE MEASUREMENTS, INDICATING ANY AND ALL DEFICIENCIES SHALL BE SUBMITTED FOR OWNER REVIEW.

- B. THE TAB SPECIALIST SHALL PERFORM FLOW MEASUREMENTS OF ALL NEW AIR AND HYDRONIC SYSTEMS AS LISTED ABOVE IN THE PROJECT SCOPE. A REPORT OF THESE MEASUREMENTS, INDICATING ANY AND ALL DEFICIENCIES SHALL BE SUBMITTED FOR OWNER REVIEW.

- C. THE REPORT SHALL INDICATE A SCHEMATIC DIAGRAM INDICATING LOCATIONS OF ALL EQUIPMENT TESTED AND MEASUREMENT LOCATIONS.

- D. PRIOR TO FINAL INSPECTION OF THE WORK, THE TAB SPECIALIST SHALL BALANCE ALL SYSTEMS AS INDICATED ABOVE TO THE REQUIREMENTS OF THE DESIGN.

- E. THE CONTRACTOR SHALL HAVE FURNISH AND INSTALL ALL ADDITIONAL BALANCING EQUIPMENT, PRESSURE TAPS, GAUGES AND OTHER EQUIPMENT AS REQUIRED FOR A PROPERLY BALANCED SYSTEM AT NO ADDITIONAL COST TO THE OWNER. SUCH ADDITIONAL EQUIPMENT SHALL ADHERE IN STRICT ACCORDANCE WITH THE RESPECTIVE EQUIPMENT MANUFACTURER'S RECOMMENDATIONS.

- F. THE CONTRACTOR SHALL HAVE THE TESTING AND BALANCING SPECIALIST COORDINATE ALL WORK OF THIS SECTION WITH THE BUILDING MANAGER. BALANCING WORK SHALL NOT CONFLICT WITH OTHER WORK SO AS TO MAINTAIN COMPLETION WITHIN THE SPECIFIED TIME.

- G. ALL INSTRUMENTS USED FOR TAB SHALL BE MAINTAINED IN GOOD WORKING CONDITION AND ACCURATELY CALIBRATED.

- H. TOLERANCES: PLUS OR MINUS 5 PERCENT OF DESIGN VALUES.

- I. INSPECTIONS: RANDOM CHECKS BY OWNER OR ARCHITECT TO VERIFY FINAL TESTING, ADJUSTING, AND BALANCING REPORT.

- J. ADDITIONAL TESTS: RANDOM TESTS WITHIN 90 DAYS OF COMPLETING TAB TO VERIFY BALANCE CONDITIONS AND SEASONAL TESTS.

END OF SECTION 230593

SECTION 230713 – DUCT INSULATION

1.1 QUALITY ASSURANCE

SURFACE-BURNING CHARACTERISTICS: ALL INSULATION SHALL HAVE COMPOSITE (INSULATION JACKET OR FACING AND ADHESIVE USED TO ADHERE THE FACING OR JACKET TO THE INSULATION) A FLAME-SPREAD INDEX OF 25, AND SMOKE-DEVELOPED INDEX OF 50 FOR INSULATION INSTALLED INDOOR, 75, AND SMOKE-DEVELOPED INDEX OF 150 FOR INSULATION INSTALLED OUTDOORS; ACCORDING TO ASTM E 84.

1.2 FIELD QUALITY CONTROL

- A. FIELD INSPECTIONS: BY OWNER-ENGAGED AGENCY.

1.3 INDOOR DUCT AND PLENUM INSULATION SCHEDULE:

- A. CONCEALED, RECTANGULAR, ROUND AND FLAT-oval, SUPPLY-RETURN, OUTDOOR-AND EXHAUST-AIR DUCT AND AIR PLENUM INSULATION:

- B. FLEXIBLE ELASTOMERIC, MINERAL-FIBER BLANKET, MINERAL-FIBER BOARD OR POLYOLEFIN WITH MINIMUM INSTALLED THERMAL RESISTANCE AS FOLLOWS:
UNCONDITIONED SPACES WITHIN BUILDING: R-6
WITHIN BUILDING ENVELOPE ASSEMBLY: R-12
OUTSIDE OF BUILDING: R-12

1.4 ITEMS NOT INSULATED:

- 1. FIBROUS-GLASS DUCTS.
- 2. METAL DUCTS WITH DUCT LINER OR SUFFICIENT THICKNESS TO COMPLY WITH ENERGY CODE ANDASHRAE/IESNA 90.1.
- 3. FACTORY-INSULATED FLEXIBLE DUCTS.
- 4. FACTORY-INSULATED PLENUMS AND CASINGS.
- 5. FLEXIBLE CONNECTORS.
- 6. VIBRATION-CONTROL DEVICES.
- 7. FACTORY-INSULATED ACCESS PANELS AND DOORS.
- 8. DUCTS THAT HAVE INTERNAL ACOUSTICAL LINING.

1.5 PRODUCTS

- A. THE FOLLOWING INSULATION MANUFACTURERS WILL BE ACCEPTABLE:

- 1. JOHNS-MANVILLE
- 2. OWENS-CORNING

1.6 ACOUSTICAL TREATMENT

- 1. WHERE SHOWN ON THE DRAWINGS, LOW PRESSURE DUCTWORK SHALL BE LINED WITH 1.5" THICK R-6 AS MANUFACTURED BY DUCTMATE, 1-1/2 POUND MINIMUM DENSITY, NEOPRENE COATED, FLEXIBLE FIBERGLASS DUCT LINER. LINING SHALL COMPLY WITH NFPA 90A AND SHALL HAVE A FLAME SPREAD CLASSIFICATION OF NOT MORE THAN 25 AND A SMOKE DEVELOPED RATING NOT MORE THAN 50. DUCT SIZES WHERE LINING IS INDICATED ON PLANS ARE MINIMUM INSIDE CLEAR DIMENSIONS REQUIRED.

END OF SECTION 230713

SECTION 233113 – METAL DUCTS

1.1 CONSTRUCTION

- A. EACH DUCT SYSTEM SHALL BE CONSTRUCTED FOR THE SPECIFIC SMACNA DUCT PRESSURE CLASSIFICATIONS SHOWN ON THE CONTRACT DRAWINGS. WHERE NO PRESSURE CLASSES ARE SPECIFIED BY THE DESIGNER, THE SMACNA 1 INCH WG PRESSURE, SEAL CLASS "A".

- B. ALL DUCTWORK SHALL BE CONSTRUCTED TO SMACNA 1" WG DESIGN AND NOT LESS THAN THE FOLLOWING STANDARDS:

- 1. CONSTRUCT SO THAT ALL INTERIOR SURFACES ARE SMOOTH. USE SLIP AND DRIVE OR FLANGED AND BOLTED CONSTRUCTION WHEN FABRICATING RECTANGULAR DUCTWORK. USE SPIRAL LOCK SEAM CONSTRUCTION WHEN FABRICATING ROUND SPIRAL DUCTWORK. SHEET METAL SCREWS MAY BE USED ON DUCT HANGERS, TRANSVERSE JOINTS AND OTHER SMACNA APPROVED LOCATIONS IF THE SCREW DOES NOT EXTEND MORE THAN 1/2 INCH INTO THE DUCT.
- 2. SHEET STEEL SHALL COMPLY WITH ASTM A653 STANDARD SPECIFICATION FOR STEEL SHEET METAL, ZINC COATED (GALVANIZED) OR ZINC IRON ALLOY-COATED (GALVANNEALED) BY HOT DIP PROCESS, AND A924 STANDARD SPECIFICATION FOR GENERAL REQUIREMENT FOR SHEET METALLIC-COATED BY HOT DIP PROCESS. ALL ANGLE IRON USED FOR SUPPORT SHALL BE GALVANIZED. CONNECTIONS TO WALLS OR FLOOR SHALL BE AIR TIGHT WITH ANGLE IRON AND CAULKING. SEAL ALL DUCT SEAMS, TRANSVERSE AND LONGITUDINAL, AIR TIGHT. PROVIDE TURNING VANES ALL 90° ELBOWS.

- 3. LONGITUDINAL SEAMS FOR RECTANGULAR DUCTWORK SHALL BE PITTSBURGH LOCK SEAMS WITH SEALING COMPOUND, EQUAL TO BENJAMIN FOSTER NO. 30-03 INSERTED INTO SEAM. ALL SEAMS SHALL BE BRUSHED WITH NO. 30-02 AND COVERED WITH APPROVED SEALING TAPE.
- 4. RECTANGULAR DUCTWORK 18 GAUGE AND HEAVIER, FILLER RODS SHALL BE IN ACCORDANCE WITH SPECIFICATIONS FOR IRON AND STEEL GAS WELDING RODS, ASTM 215; AWG AS2.

- C. WHERE LATEST EDITION OF SMACNA DOES NOT CLEARLY STATE GAUGES AND/OR STIFFENERS TO BE USED OR, WHERE SMACNA STANDARDS REQUIRE INTERPRETATION, THE FOLLOWING MINIMUM METAL GAUGES AND BRACING SHALL BE USED:

USG MAX. SIDE INCHES TRANSVERSE JOINTS AND BRACING

22 UP TO 12 S SLIP, DRIVE SLIP, ONE INCH POCKET LOCK OR 8 FOOT CENTERS

22 13 TO 24 1"X1"X1/8" ANGLES ON 4 FOOT CENTERS

20 25 TO 35 1"X1"X1/8" ANGLES ON 2 FOOT CENTERS

- D. PROVIDE TAPPING IN DUCTS FOR THERMOMETERS WHERE SPECIFIED. IN ADDITION, PROVIDE AN AIRTIGHT PLUGGED TAPPING LOCATED AS FOLLOWS:

1. UPSTREAM OF EACH REHEAT COIL AND VAV BOX.

2. DOWNSTREAM OF EACH REHEAT COIL AND VAV BOX.

- E. FLAT OVAL OR ROUND DUCTWORK MAY BE PROVIDED IN LIEU OF RECTANGULAR DUCTWORK WITH THE REINFORCEMENT FOR FLAT SIDES SAME AS SPECIFIED FOR THE RECTANGULAR DUCTWORK, AND AS PER SMACNA FLAT OVAL DUCT CONSTRUCTION STANDARDS SHOWN IN FIG. 3-6 AND AS SHOWN IN FIG. 3-1 AND 3-2 FOR ROUND DUCTWORK.

- F. ALL DUCTWORK SHALL BE SEALED TO CLASS "A" AND LEAK TESTED TO MEET SMACNA CLASS 6 FOR RECTANGULAR AND CLASS 3 FOR ROUND DUCTS.

1.2 MATERIALS

- A. SINGLE-WALL RECTANGULAR DUCTS AND FITTINGS.
- B. SINGLE-WALL ROUND AND FLAT-oval DUCTS AND FITTINGS.
- C. SHEET METAL MATERIALS:

 - 1. GALVANIZED SHEET STEEL.
 - 2. STAINLESS-STEEL SHEETS.
 - 3. ALUMINUM SHEETS.
 - 4. FACTORY-APPLIED ANTI-MICROBIAL COATING.

- D. DUCT LINER:

 - 1. FIBROUS GLASS, TYPE I, FLEXIBLE.

1.5 PRODUCTS

- A. WITH ANTI-MICROBIAL EROSION-RESISTANT COATING.

- 1. FLEXIBLE ELASTOMERIC.

- 2. NATURAL FIBER.

E. SEALANT MATERIALS:

- 1. TWO-PART TAPE SEALING SYSTEM.
- 2. WATER-BASED JOINT AND SEAM SEALANT.
- 3. SOLVENT-BASED JOINT AND SEAM SEALANT.
- 4. FLANGED JOINT SEALANT.
- 5. FLANGE GASKETS.
- 6. ROUND DUCT JOINT O-RING SEALS.

1.6 DUCT CLEANING

- A. CLEAN EXISTING DUCT SYSTEM(S) BEFORE TESTING, ADJUSTING, AND BALANCING.

- B. CLEAN THE FOLLOWING ITEMS:

- 1. AIR OUTLETS AND INLETS.
- 2. SUPPLY, RETURN, AND EXHAUST FANS.
- 3. AIR HANDLING UNIT.
- 4. COILS AND RELATED COMPONENTS.
- 5. RETURN-AIR DUCTS, DAMPERS, ACTUATORS, AND TURNING VANES.
- 6. SUPPLY-AIR DUCTS, DAMPERS, ACTUATORS, AND TURNING VANES.
- 7. DEDICATED EXHAUST AND VENTILATION COMPONENTS AND MAKEUP AIR SYSTEMS.

1.7 DUCT SCHEDULE

- A. ALL DUCTS SHALL BE GALVANIZED STEEL EXCEPT AS FOLLOWS:

- 1. MOIST ENVIRONMENT DUCT MATERIAL: ALUMINUM.
</ul

3	BULLETIN 3	02/25/25
	PERMIT SET	01/30/25
	90% PROGRESS	01/24/25

ROOTS NATURAL KITCHEN

MECHANICAL FLOOR PLAN

M1.0

GENERAL NOTES

- A. ALL WORK SHALL COMPLY WITH ALL LOCAL CODE & STATE CODE & AUTHORITIES HAVING JURISDICTION.
- B. COORDINATE LOCATIONS AND SIZES OF ROOF OPENINGS WITH OWNER AND STRUCTURAL ENGINEERS.
- C. EQUIPMENT SIZES, DIMENSIONS AND REQUIRED CONNECTIONS SHALL BE VERIFIED WITH THE ACTUAL EQUIPMENT SELECTED VENDOR DRAWINGS BEFORE FABRICATION OF DUCTWORK, PIPING ETC.
- D. CONTRACTOR SHALL COORDINATE ALL ELECTRICAL REQUIREMENTS FOR ALL HVAC BASED ON ACTUAL EQUIPMENT SELECTED PRIOR TO INSTALLATION.
- E. CONTRACTOR SHALL COORDINATE EQUIPMENT WEIGHTS AND SUPPORTS BASED ON ACTUAL EQUIPMENT SELECTED.
- F. TEST AND BALANCE AIR SYSTEMS. PROVIDE REPORT TO G.C. AND OWNER.
- G. CONTRACTOR TO FIELD VERIFY EXISTING DUCTWORK, ASSOCIATED ACCESSORIES AND EXISTING HVAC EQUIPMENT. ALL EXISTING DUCTWORK, ASSOCIATED ACCESSORIES AND EXISTING HVAC EQUIPMENT TO BE REUSED.
- H. ALL ITEMS TO BE RE-USED OR RELOCATED SHALL BE CLEANED, REPAIRED, AND RESTORED TO LIKE NEW CONDITION PRIOR TO RE-USE.
- I. PROVIDE NECESSARY PROTECTIVE DEVICES WHERE REQUIRED AND IN STRICT ACCORDANCE WITH OSHA AND ICRA REGULATIONS.
- J. KEEP ALL ADJOINING AREAS ADJACENT TO THE WORK AREAS CLEAN AND FREE OF DEBRIS.
- K. MATERIAL FROM EXISTING SYSTEM WHICH IS RENDERED USELESS SHALL BE REMOVED AND DISPOSED OF OFF SITE.
- L. REPAIR/ REPLACE EXISTING EQUIPMENT/ MATERIALS NOT SCHEDULED OR NOTED TO BE DEMOLISHED BUT BECOME DAMAGED DURING THE PROGRESS OF THE WORK. MAKE ANY AND ALL SUCH REPAIRS, REPLACEMENTS, MODIFICATIONS TO RESTORE THE DAMAGED ITEMS TO THEIR ORIGINAL CONDITIONS AT THE TIME OF DAMAGE, TO THE SATISFACTION OF AND AT NO ADDITIONAL COST TO THE OWNER. DUCT SIZES SHOWN ON DRAWINGS ARE CLEAR INSIDE DIMENSION.
- M. THE CONTRACTOR SHALL VERIFY EXACT LOCATION OF TRUSSES AND MODIFY DUCTWORK ACCORDINGLY.
- N. PROVIDE FIRE OR FIRE+SMOKE DAMPER WHEREVER DUCTS ARE CROSSING FIRE/SMOKE RATED WALLS/BARRIERS/SLABS. COORDINATE WITH ARCHITECTURAL DRAWING FOR FIRE RATING OF THE WALLS.
- O. DUCT TO EXHAUST FAN CONNECTIONS SHALL BE FLANGED, GASKETED AND BOLTED TO THE INLET OF THE FAN FOR SIDE-INLET UTILITY FANS APPROVED FLEXIBLE CONNECTIONS MAY BE PROVIDED.
- P. ALL WORK SHALL BE SUBJECT TO THE ACCEPTANCE AND APPROVAL OF THE ARCHITECT AND OWNER. THE ARCHITECT SHALL BE NOTIFIED OF ANY AND ALL DISCREPANCIES BETWEEN FIELD CONDITIONS AND THE CONTRACT DOCUMENTS BEFORE PROCEEDING WITH THAT PORTION OF THE WORK. FAILURE OF PROPER NOTIFICATION DOES NOT RELIEVE THE CONTRACTOR. THE CONTRACTOR SHALL CORRECT ANY AND ALL WORK ARISING FROM SUCH FAILURE TO COORDINATE DISCREPANCIES TO THE SATISFACTION OF THE ARCHITECT WITHOUT ADDITIONAL COST TO THE OWNER.
- Q. THE CONTRACTOR SHALL, UPON COMPLETION OF PROJECT, PERFORM A COMPLETE TEST AND BALANCE OF ALL EQUIPMENT. PROVIDE A WRITTEN REPORT TO THE ARCHITECT. ALL CAPACITIES MUST BE SET TO WITHIN $\pm 10\%$ OF AMOUNTS INDICATED ON THE FLOOR PLAN AND SCHEDULES.
- R. PROVIDE CORD OPERATED DAMPERS FOR AIR TERMINALS MOUNTED IN INACCESSIBLE CEILINGS.
- S. PROVIDE DUCT INSULATION AS SPECIFIED WITH MINIMUM VALUES AS FOLLOWS:

 - R-6 SUPPLY & RETURN DUCT INSULATION IN UNCONDITIONED SPACES WITHIN BUILDING.
 - R-12 SUPPLY & RETURN DUCT INSULATION OUTSIDE OF BUILDING

- T. PROVIDE ACOUSTIC INSULATION ON MAIN SUPPLY AND RETURN DUCTS UP TO 10 FT. FROM HVAC UNIT.

KITCHEN EXHAUST NOTES


1. ALL TYPE I GREASE DUCT SHALL BE WRAPPED WITH TWO LAYERS OF 3M™ FIRE BARRIER DUCT WRAP 615+ DUCT ENCLOSURE SYSTEM PROVIDING 2-HOUR FIRE RESISTANT PROTECTION. DUCT WRAP SHALL CONSIST OF 3" PERIMETER AND LONGITUDINAL OVERLAPS WITH ZERO CLEARANCE TO COMBUSTIBLES. DUCT WRAP SHALL COMPLY WITH THE REQUIREMENTS OF NFPA 96 AND ICC-ES EVALUATION REPORT NO. ESR-1255. DUCT WRAP IS UL LISTED. DUCT WRAP SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
2. MATERIAL – STEEL NOT LESS THAN 0.055 INCH (NO. 16 GAGE) IN THICKNESS, WITH JOINTS AND SEAMS MADE WITH A CONTINUOUS LIQUID-TIGHT WELD MADE ON THE EXTERNAL SURFACE OF THE DUCT SYSTEM.
3. ALL TURNS IN KITCHEN EXHAUST DUCT SHALL BE ACHIEVED WITH THE USE OF A 1.5 RADIUS/WIDTH SMOOTH RADIUS ELBOW. REFERENCE DETAILS.
4. HORIZONTAL DUCT SERVING TYPE I HOODS SHALL BE SLOPED NOT LESS THAN 2% TOWARD HOOD.
5. A PERFORMANCE TEST SHALL BE CONDUCTED UPON COMPLETION AND BEFORE FINAL APPROVAL OF THE INSTALLATION OF A VENTILATION SYSTEM SERVING COMMERCIAL COOKING APPLIANCES. THE TEST SHALL VERIFY THE RATE OF EXHAUST AIRFLOW, MAKEUP AIRFLOW, AND PROPER OPERATION AS SPECIFIED IN THE MECHANICAL CODE (INCLUDING CAPTURE AND CONTAINMENT TEST). THE PERMIT HOLDER SHALL FURNISH THE NECESSARY TEST EQUIPMENT AND DEVICES REQUIRED TO PERFORM THE TESTS. COORDINATE ALL TESTS WITH AHJ, INCLUDING FINAL REPORT/SUBMITTAL AND WITNESS REQUIREMENTS.
6. SLOPE ALL HORIZONTAL GREASE DUCT 1" PER FOOT WHERE SPACE ALLOWS, BUT NOT LESS THAN 1/4" PER FOOT AS REQUIRED BY AHJ.
7. CONTRACTOR TO PROVIDE AND INSTALL ALL CODE REQUIRED FIRE RATED ACCESS DOORS IN GREASE DUCTS AT ALL LOCATIONS REQUIRED BY CODE AND LOCAL AUTHORITY HAVING JURISDICTION.
8. PROVIDE CLEANOUTS IN ALL KITCHEN EXHAUST DUCTWORK AT EVERY CHANGE OF DIRECTION AND AT EVERY 12' OF DUCT. PROVIDE ACCESS PANELS AT ALL GREASE DUCT CLEANOUTS. PROVIDE AS PER LOCAL CODE.
9. COORDINATE HOOD INSTALLATION WITH HOOD PLANS. HOOD OPERATION, CAPTURE, SIZE AND ACCESSORIES ARE BASED ON EQUIPMENT AND CLEARANCES INDICATED IN PLANS. FIELD VERIFY AND COORDINATE HOODS WITH EQUIPMENT FURNISHED. COORDINATE HOOD CONNECTIONS WITH HOOD PLANS AND MANUFACTURER PRIOR TO FABRICATION.
10. COORDINATE INTERLOCKS AND HOOD CONTROLS WITH HOOD PLANS AND HOOD MANUFACTURER PRIOR TO INSTALLATION.
11. GREASE DUCT SYSTEMS SERVING A TYPE I HOOD SHALL HAVE A CLEARANCE TO COMBUSTIBLE CONSTRUCTION OF NOT LESS THAN 18 INCHES.

IMPORTANT NOTE:

PROVIDE COPY OF TEST AND BALANCE REPORT TO MECHANICAL INSPECTOR AT TIME OF HAVING FINAL INSPECTION

KEY NOTES


- ① PROVIDE NEW 7-DAY PROGRAMMABLE THERMOSTAT WITH LOCKING COVER. LOCATE THERMOSTAT NEAR SERVICE AREA.. PROVIDE REMOTE SENSOR LOCATED 48" A.F.F. NEAR LOCATION INDICATED. COORDINATE LOCATION ON SITE WITH GENERAL CONTRACTOR AND EQUIPMENT. AVOID LOCATING NEAR OR ABOVE SOURCES OF HEAT. INTERLOCK WITH ASSOCIATED RTU. CONFIRM FINAL LOCATION WITH ARCHITECT/OWNER.
- ② INSTALL TYPE-I GREASE EXHAUST HOOD SUPPORT HOOD PER MANUFACTURER'S INSTALLATION INSTRUCTIONS. PROVIDE TRAPEZE HANGERS FOR ALL THREAD SUPPORT UNDER DUCTWORK AS REQUIRED. TRANSITION FROM HOOD CONNECTION TO WELDED KITCHEN EXHAUST DUCT SIZES SHOWN. THE HOOD AND DUCT SHALL HAVE AN APPROVED FIRE PROTECTION. THE FIRE-EXTINGUISHING SYSTEM SHALL BE INTERCONNECTED TO THE FUEL OR CURRENT SUPPLY SO THAT THE FUEL OR CURRENT SUPPLY IS AUTOMATICALLY SHUT OFF TO ALL EQUIPMENT UNDER THE HOOD WHEN THE SYSTEM IS ACTUATED.
- ③ 24"x10" MAKE-UP AIR DUCT CONNECTION TO HOOD. PROVIDE VOLUME DAMPER AND BALANCE TO 560 CFM.
- ④ Ø12" GREASE EXHAUST DUCT FROM HOOD UP THRU ROOF TO KEF-1(N).
- ⑤ INSTALL TYPE-II EXHAUST HOOD SUPPORT HOOD PER MANUFACTURER'S INSTALLATION INSTRUCTIONS. PROVIDE TRAPEZE HANGERS FOR ALL THREAD SUPPORT UNDER DUCTWORK AS REQUIRED. TRANSITION FROM HOOD CONNECTION TO WELDED KITCHEN EXHAUST DUCT SIZES SHOWN.
- ⑥ 28"x10" MAKE-UP AIR DUCT CONNECTION TO HOOD. PROVIDE VOLUME DAMPER AND BALANCE TO 550 CFM.
- ⑦ Ø14" EXHAUST DUCT FROM HOOD UP THRU ROOF TO KEF-2(N).
- ⑧ Ø10" EXHAUST DUCT FROM HOOD UP THRU ROOF TO KEF-3(N).
- ⑨ PROVIDE CEILING MOUNTED TOILET EXHAUST FAN
- ⑩ TERMINATE Ø8" EXHAUST DUCT UP THROUGH ROOF.
- ⑪ PROVIDE AND INSTALL EMERGENCY MANUAL SHUTDOWN PUSH BUTTON FOR HOOD. PUSH BUTTON SHALL BE IN THE PATH OF EGRESS, A MINIMUM OF 10' AWAY FROM THE HOOD AND A MAXIMUM OF 20'.
- ⑫ GREASE DUCT TO BE PROVIDED WITH KITCHEN EQUIPMENT AND INSTALLED BY MECHANICAL CONTRACTOR. INSTALL PER MANUFACTURER'S INSTRUCTIONS. PROVIDE FIRE WRAP ON DUCT RATED FOR 0" CLEARANCE TO COMBUSTIBLES.
- ⑬ CONDENSATE DRAIN TO NEAREST PLUMBING DRAIN W/ AIR GAP FITTING. COORDINATE W/PLUMBING CONTRACTOR. PROVIDE CONDENSATE PUMP IF REQUIRED.
- ⑭ PROVIDE NEW TEMPERATURE SENSOR AND INSTALL IN RETURN AIR DUCT AND WIRE BACK TO T-STAT.
- ⑮ PROVIDE CONCENTRIC VENT FOR WATER HEATER INTAKE & EXHAUST VENT. INSTALL PER MANUFACTURER'S INSTRUCTIONS.
- ⑯ INSTALL NEW REFRIGERANT PIPING BETWEEN INDOOR AND OUTDOOR UNIT AS PER MANUFACTURER'S RECOMMENDATION. PROVIDE WEATHER PROOF COATING FOR EXPOSED PIPING. PROVIDE INSULATION TO REFRIGERANT PIPING AS PER ENERGY CONSERVATION CODE.
- ⑰ DUCT MOUNTED SMOKE DETECTOR SHALL BE FURNISHED/INSTALLED BY MECHANICAL CONTRACTOR AND WIRED BY ELECTRICAL CONTRACTOR TO SHUT DOWN CORRESPONDING RTU UNDER ALARM CONDITIONS. ALL WIRING SHALL BE IN CONDUIT PER N.E.C. SMOKE DETECTOR SHALL BE SYSTEM SENSOR MODEL DH100ACDCLP OR EQUAL. DUCT DETECTOR SHALL BE INCLUDE AN AUDIBLE AND VISIBLE ALARM/NOTIFICATION WHEN ACTIVATED.




① MECHANICAL FLOOR PLAN

1/4" = 1'-0"

06' 1' 2' 4' 8'




② SECTION A-A'
1/4" = 1'-0"



③ SECTION B-B'
1/4" = 1'-0"


ROOTS NATURAL KITCHEN




① MECHANICAL ROOF PLAN
1/4" = 1'-0"

GENERAL NOTES	
A. COORDINATE LOCATIONS AND SIZES OF ROOF OPENINGS WITH OWNER AND STRUCTURAL ENGINEERS.	
B. EQUIPMENT SIZES, DIMENSIONS AND REQUIRED CONNECTIONS SHALL BE VERIFIED WITH THE ACTUAL EQUIPMENT SELECTED VENDOR DRAWINGS BEFORE FABRICATION OF DUCTWORK, PIPING ETC.	
C. CONTRACTOR SHALL COORDINATE ALL ELECTRICAL REQUIREMENTS FOR ALL HVAC BASED ON ACTUAL EQUIPMENT SELECTED PRIOR TO INSTALLATION.	
D. CONTRACTOR SHALL COORDINATE EQUIPMENT WEIGHTS AND SUPPORTS BASED ON ACTUAL EQUIPMENT SELECTED.	
E. ALL SOURCE OF MECHANICAL INTAKE SHALL MAINTAIN 10 LINEAR FEET SEPARATION BETWEEN ANY SOURCE OF EXHAUST. CONTRACTOR IS RESPONSIBLE TO ADJUST DUCT LENGTH AS NEEDED. NOTIFY ENGINEER IF ANY DISCREPANCIES.	
F. THE CONTRACTOR SHALL VERIFY EXACT LOCATION OF TRUSSES AND MODIFY DUCTWORK ACCORDINGLY.	
G. PROVIDE ACOUSTIC INSULATION ON MAIN SUPPLY AND RETURN DUCTS UP TO 10 FT. FROM HVAC UNIT.	
KEY NOTES	
① COORDINATE FINAL LOCATION OF EQUIPMENT WITH STRUCTURAL ENGINEER/DRAWINGS.	
② NEW ROOFTOP UNITS ARE PROVIDED. PROVIDE FLEXIBLE CONNECTORS ON SUPPLY AND RETURN DUCT CONNECTIONS. SET OUTSIDE AIR AS INDICATED ON ROOFTOP UNIT SCHEDULES. MECHANICAL CONTRACTOR SHALL SCRIBE INTO UNIT POSITION OF OUTSIDE AIR DAMPER AND LABEL OUTSIDE AIR VOLUME AND PERCENT OF OUTSIDE AIR. TRANSITION AND CONNECT SUPPLY AND RETURN DUCTWORK FROM BELOW. COORDINATE ROUTING THROUGH STRUCTURAL TRUSSES AND OFFSET AS REQUIRED IN CURB SPACE.	
③ REUSE EXISTING ROOF CURB & PENETRATIONS AS MUCH AS POSSIBLE. REPAIR/MODIFY/REPLACE AS/IF REQUIRED.	
④ CONTRACTOR TO FIELD VERIFY THAT THE LOCATION OF ANY EXHAUST SOURCE SHOULD BE AT LEAST 10' AWAY FROM THE OUTSIDE AIR INTAKE OPENING OF RTU'S & MAU.	
⑤ EXTEND FULL SIZE SUPPLY & RETURN DUCTWORK FROM ROOFTOP UNITS TO SPACE. EXTEND AS SHOWN. TRANSITION DUCT AS NECESSARY TO MAKE CONNECTION. ACOUSTICALLY LINE THE FIRST 10'-0" OF BOTH SUPPLY AND RETURN MAIN DUCTS.	
⑥ CONTRACTOR TO PROVIDE TEMPERATURE SENSOR IN RETURN AIR DUCT & WIRE BACK TO THE RESPECTIVE RTU.	
⑦ INSTALL NEW CONDENSER UNIT. CONTRACTOR TO VERIFY EXACT LOCATION ON FIELD. CONTRACTOR TO INSTALL OUTDOOR UNIT AS PER MANUFACTURER'S RECOMMENDATIONS.	
⑧ PROVIDE MAKE-UP AIR UNIT. PROVIDE FLEXIBLE CONNECTION ON THE SUPPLY DUCT CONNECTION TRANSITION TO DUCT SIZE INDICATED.	
⑨ PROVIDE GREASE EXHAUST FAN. MAINTAIN A MINIMUM OF 10'-0" FROM ALL OUTSIDE AIR INTAKES.	
⑩ TERMINATE 8" EXHAUST DUCT UP THROUGH ROOF WITH GOOSENECK & WIRE-MESH. MAINTAIN A MINIMUM OF 10'-0" FROM ALL OUTSIDE AIR INTAKES.	
⑪ CONTRACTOR TO RUN CONDENSATE DRAIN FROM MAU & RTU TO NEAREST ROOF DRAIN.	
⑫ PROVIDE 3' TALL WIND BAND FOR EXHAUST FAN. COORDINATE INSTALLATION OF FAN & EXISTING CONDITIONS WITH LANDLORD TO ENSURE THAT EXHAUST OUTLETS SHALL BE LOCATED NOT LESS THAN 10' HORIZONTALLY FROM OR NOT LESS THAN 3' ABOVE AIR INTAKE SOURCE.	
⑬ PROVIDE CONCENTRIC VENT FOR WATER HEATER INTAKE & EXHAUST VENT. INSTALL PER MANUFACTURER'S INSTRUCTIONS.	
⑭ INSTALL NEW REFRIGERANT PIPING BETWEEN INDOOR AND OUTDOOR UNIT AS PER MANUFACTURERS RECOMMENDATIONS. PROVIDE INSULATION TO REFRIGERANT PIPING AS PER ENERGY CONSERVATION CODE. COORDINATE WITH BASE BUILDING ENGINEER FOR PIPE ROUTING AND RISER LOCATION. NOTIFY THE ENGINEER OF ANY DISCREPANCY BEFORE COMMENCING BID.	

MECHANICAL
ROOF PLAN &
SECTIONS



M1.1




NOTE : 1. FOR DUCTS OVER 29" WIDE AND/OR OVER 12" HIGH.

The diagram illustrates a duct system with the following components and installation details:

- Left Component:** A circular duct section labeled "SHEET METAL ROUND DUCT TO TAKE-OFF." It features a "16 GA. HANGER STRAP" and a "JCT" (junction) point where a "ROUND RIGID DUCT" connects to it. A callout specifies: "WRAP ALL BRANCH DUCTS AND COVER CONNECTIONS WITH DUCT WRAP. SEE SPECIFICATIONS".
- Middle Component:** A flexible duct section labeled "UL 181 LABELED INSULATED FLEX DUCT. SEE SPECS. NO SAGS OR SHARP TURNS ALLOWED. MAXIMUM RUN LIMITED TO 3'-0" STRETCH DUCT RUN FOR SMOOTH INTERIOR". It is supported by a "1" x 16 GA. HANGER STRAP" and a "STAINLESS STEEL SCREW DRIVER OPERATED BAND (TYPICAL)".
- Right Component:** A duct section labeled "T-BAR FOR LAY IN ON HARD CEILINGS" and "LAY IN CEILING". It includes a "DIFFUSER" and a vertical dimension of "3'-0" MAX".

NOTES:

1. ALL JOINTS, SEAMS AND CONNECTIONS FOR DUCTS WILL BE IN ACCORDANCE WITH SECTION C403.2.9 OF FBCEC 2020 AND SECTION 603 OF FBCM 2020



PIPE HANGER ROD AND SPACING SCHEDULE

TUBE	5/8	3/4	7/8	1	1 1/2	2	2 1/2
	3/8	3/8	3/8	3/8	3/8	3/8	3/8
WEEN FEET	—	6	—	7	9	10	11
WEEN S-FT.	6	6	6	6	8	9	10


ZE HANGER SPACING SHALL BE BASED ON SPACING OF
EST PIPE ON TRAPEZE. TRAPEZE SHALL BE DESIGNED
A FACTOR OF SAFETY OF 5 FOR CENTER OF SPAN
INTRATED LOAD.

1 LOW PRESSURE BALANCING DAMPER
M5.1 N.T.S



2 TYPICAL DIFFUSER CONNECTION DETAIL

3 METHOD OF HANGING REFRIGERANT PIPING

M5.1 N.T.S



NOTE:
FURNISH THIS TYPE CONNECTION WHEN SINGLE LINE
DUCTWORK IS INDICATED AS THIS



4 SUPPLY AIR DUCTWORK SUB-MAIN/BRANCH DUCT CONNECTION

M5.1 N.T.S

5 ACOUSTICAL TREATMENT DUCT LINING
M5.1 N.T.S


6 LOW VELOCITY DUCTWORK ELBOWS
M5.1 N.T.S

3	BULLETIN 3	02/25/25
	PERMIT SET	01/30/25
	90% PROGRESS	01/24/25

ROOTS NATURAL KITCHEN

MECHANICAL
DETAILS (2 OF 3)

M5.2




3	BULLETIN 3	02/25/25
	PERMIT SET	01/30/25
	90% PROGRESS	01/24/25

ROOTS NATURAL KITCHEN

MECHANICAL
DETAILS (3 OF 3)

M5.3



ROOF TOP UNIT SCHEDULE (GAS HEAT)																								
UNIT ID	MANUFACTURER	MODEL	AREA SERVED	NOMINAL TONS	SUPPLY FAN			COOLING CAPACITY			HEATING CAPACITY (MBH)			ELECTRICAL DATA				THERMAL EFFICIENCY (%)	EER	SEER	IEER	OPERATING WEIGHT (LBS.)	REMARK	
					SUPPLY AIR (CFM)	OUTSIDE AIR (CFM)	MAX. ESP. (IN. OF W.G.)	TOTAL MBH	SENSIBLE MBH	AMBIENT TEMP. DB (°F)	ENTERING TEMP. DB / WB (°F)	GAS INPUT	GAS OUTPUT	VOLTS	PH	Hz	MCA (A)	MOCP (A)						
RTU-1(N)	CARRIER	48FEEA05A2A50A0A0	SEE PLAN	4.0	1600	300	1	52	37	95	80/67	110	88	208-230	3	60	26	30	80	11.8	14	-	800	1-10
RTU-2(N)	CARRIER	48FEEA06B2A50A0A0	SEE PLAN	5.0	2000	400	1	62	46	95	80/67	110	88	208-230	3	60	31	45	80	11.4	14	-	900	1-11
RTU-3(N)	CARRIER	48FEEM09B2A50A0A0	SEE PLAN	8.5	3400	490	1	95	76	95	80/67	180	148	208-230	3	60	39	50	82	11.2	-	15	1200	1-12

NOTES:
1. PROVIDE SIDE/BOTTOM DISCHARGE CONFIGURATION AS PER PLAN.
2. ELECTRICAL CONNECTION TO BE SINGLE POINT AND TO BE THROUGH THE BOTTOM OF THE UNIT.
3. PROVIDE DISCONNECT SWITCH AND AN UNPOWERED GFCI RECEPTACLE.
4. 14" ROOF CURB - CONTRACTOR SHALL FIELD INSULATE. SHIP ASAP AHEAD OF THE UNIT.
5. CONTRACTOR TO BALANCE OUTSIDE AIR & RETURN AIR DAMPERS ON RTU TO MATCH VALUES MENTIONED IN ABOVE TABLE.
6. ANTI SHORT CYCLE TIMER.
7. UNIT TO BE PROVIDED WITH LOW LEAKAGE VOLUME CONTROL DAMPER, NEMA 3R DISCONNECT, FAN WITH VFD, VIBRATION ISOLATION SPRING SUPPORTED BLOWER, INTAKE HOOD, SCREEN INTAKE.
8. PROVIDE COMPRESSORS WITH 5 YEAR WARRANTY
9. PROVIDE VIBRATION ISOLATOR FOR UNIT MOUNTING.
10. 2" MERV STANDARD FILTERS.
11. PROVIDE ENTHALPY ECONOMIZER WITH BAROMETRIC RELIEF & FDD.
12. PROVIDE SMOKE DETECTOR IN RETRUN AIR SIDE

HI WALL INDOOR UNIT SCHEDULE											BASIS OF DESIGN: LG OR EQUIVALENT					
TAG	TYPE	CAP. (TON)	QTY	SUPPLY AIRFLOW (CFM)	TOTAL COOLING CAP. (MBH)	SENSIBLE COOLING CAP. (MBH)	HEATING CAPACITY (MBH)	ELECTRICAL DATA		DIMENSIONS (HxWxD) (IN.)	WEIGHT (LBS.)	CONNECTION SIZE		SOUND RATING (dBA)	MODEL	
								PH/VOLT/HZ	MOCP (A)			LIQ. (IN.)	REFRIGERANT GAS (IN.)	DRAIN (ID) (IN.)		
AC-1(N)	HI WALL TYPE UNIT	1.0	1	388	12	10.56	17	1/208-230/60	INDOOR UNIT IS POWERED BY OUTDOOR UNIT.	12-1/8x32-15/16x7-7/16	20	1/4	3/8	3/4	35	KNUAB091A (OR EQUIVALENT)
AC-2(N)	HI WALL TYPE UNIT	1.0	1	388	12	10.56	17	1/208-230/60	INDOOR UNIT IS POWERED BY OUTDOOR UNIT.	12-1/8x32-15/16x7-7/16	20	1/4	3/8	3/4	35	KNUAB091A (OR EQUIVALENT)

HI WALL CONDENSING UNIT SCHEDULE											BASIS OF DESIGN: LG OR EQUIVALENT						
TAG	LOCATION	INDOOR UNITS	CAP. (TON)	MAX. COOLING CAP. (MBH)	MAX. HEATING CAP. (MBH)	UNIT DIMENSIONS IN. (HxWxD)	WEIGHT (LBS.)	REF. PIPING SIZE (IN.)	ELECTRICAL DATA		SOUND RATING (dBA)	EER	SEER	HSPF	MODEL NO.		
									LIQ.	GAS							
ACCU-1(N)	ROOF	AC-1(N)	1.0	12	17	21-15/32 x 30-5/16x13-29/32	70	1/4	3/8	1/208/60	12	15	47	14.95	14	8.2	KUSAB091A (OR EQUIVALENT)
ACCU-2(N)	ROOF	AC-2(N)	1.0	12	17	21-15/32 x 30-5/16x13-29/32	70	1/4	3/8	1/208/60	12	15	47	14.95	14	8.2	KUSAB091A (OR EQUIVALENT)

KITCHEN MAKE UP AIR UNIT SCHEDULE											BASIS OF DESIGN						
TAG	SERVICE	FLOW RATE	EXTERNAL STATIC	SPEED	HEATING CAPACITY			FAN DATA			WEIGHT (LBS.)	BASIS OF DESIGN		REMARK			
					INPUT CFM	OUTPUT CFM	EFFICIENCY IN W.G.	V/PH/HZ	FLA	MCA (A)	MOCP (A)	HP	BHP	MANUFACTURER	MODEL		
MAU-1(N)	HOOD-1(N) & HOOD-2(N)	225	0.5	1400	171.96	158.236	91	208/3/60	5.7	8.3	15	2.5	1.6	570	ECON-AIR	EA1-D.250-16Z	1,2,3,4

HOOD SCHEDULE									
UNIT ID	MANUFACTURER	LENGTH (FEET-INCH)	MODEL	TYPE	COOKING		EXHAUST		WEIGHT (LBS.)

ROOTS NATURAL KITCHEN

KITCHEN HOOD
DRAWINGS (1 OF 4)

H1.0

NY ENGINEERS
NEARBY ENGINEERS
ADDRESS : 382 NE 191ST STREET,
SUITE 49674, MIAMI, FL 33179
PHONE: (646) 878-9217
EMAIL: sanket@ny-engineers.com

DRAWN
CHECKED
PROJECT NO.

NYE
NYE
240720

**FOR QUESTIONS, CALL THE
Chicago Customer Service Division
PHONE: (646) 377-0000 - 2611
EMAIL: customerservice@root.com.**

HOOD INFORMATION - JOB#72720529

HOOD ID	TAG	MODEL	HAND ACTUATOR	LENGTH	CLEARANCE	TYPE	MAX CLEARANCE	DEPTH	WIDTH	CFM	TOTAL CFM	EXHAUST FLOW	EXHAUST FLOW	VENT	SP	TOTAL	HOOD CAPACITY	SWITCHES	SWITCHES	
1	Item #48- Front	5424 ECON-AIR ES-VIB-G-ND	CEPATE SILENT FILTER	5'	60"	1	HEAVY	1400	1400	4"	1400	1000	1000	0	120	240	SS	ALONE	1 FAN	FRONT, RIGHT
2	Item #50 - Dish	5424 ECON-AIR ES-VIB-G-SP-F-ND	CEPATE SILENT FILTER	5'	70"	1	HEAVY	150	600	4"	100	1000	1000	-0.090"	100	130	SS	ALONE	1 FAN	FRONT, RIGHT
3	Item #502 - Dish	5424 ECON-AIR ES-VIB-G-SP-F-ND	CEPATE SILENT FILTER	5'	70"	1	HEAVY	240	1200	4"	14	1200	1120	-0.042"	100	130	SS	ALONE	1 FAN	FRONT, RIGHT

HOOD INFORMATION

HOOD ID	TAG	TYPE	EFFICIENCY	7 MEDIUM	7 FT	TYPE	GUARD	LOCATION	STATE	TYPE	LOCATION	STATE	TYPE	GUARD	LOCATION	STATE	TYPE	LOCATION	STATE	TYPE	GUARD	LOCATION	STATE
1	Item #48- Front	FIELD WRAPPER	1800"	HIGH	FRONT, LEFT, RIGHT	FIELD BACKSPLASH	BLD	HIGH	450"	SE FILTER	2	RECESSED, ROUND	NO										
2	Item #50 - Dish	FIELD WRAPPER	1800"	HIGH	FRONT, LEFT, RIGHT	FIELD BACKSPLASH	BLD	HIGH	450"	SE FILTER	2	LS5 SERIES E26	NO										
3	Item #502 - Dish	FIELD WRAPPER	1800"	HIGH	FRONT, LEFT, RIGHT	FIELD BACKSPLASH	BLD	HIGH	450"	SE FILTER	0	0	RIGHT	12'-0" x 24'-0"	12'-0" x 24'-0"	TANK	FS	4/0/40	SC-321220MA	2 FAN	ND	ND	

HOOD OPTIONS

HOOD ID	TAG	OPTION	ITEM	DESCRIPTION																		
1	Item #48- Front	CEPATE SILENT FILTER	5'	60" SE FILTER	2	RECESSED, ROUND	NO															
2	Item #50 - Dish	CEPATE SILENT FILTER	5'	70" SE FILTER	2	LS5 SERIES E26	NO															
3	Item #502 - Dish	CEPATE SILENT FILTER	5'	70" SE FILTER	0																	

DUCTED SUPPLY PLenum(S)

HOOD ID	TAG	PLenum	LENGTH	WIDTH	HEIGHT	TYPE	WIDTH	LENGTH	DIA	CFM	SP	RECESSED
1	Item #48- Front	Front	84"	14"	6"	BLD	10"	24"	MA	560	0.0171"	
2	Item #502 - Dish	Front	72"	16"	6"	BLD	10"	24"	MA	560	0.0171"	
3	Item #502 - Dish	Front	72"	16"	6"	BLD	12"	24"	MA	550	0.0171"	

**PLAN VIEW - HOOD #1 (Item #48-
Front)**

**PLAN VIEW - HOOD #2 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424DX-2-PSF-F
HOOD - #1 (Item #48-
Front)**

**SECTION VIEW - MODEL 5424DX-2-PSF-F
HOOD - #2 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #3 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #4 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #5 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #6 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #7 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #8 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #9 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #10 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #11 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #12 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #13 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #14 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #15 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #16 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #17 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #18 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #19 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #20 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #21 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #22 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #23 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #24 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #25 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #26 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #27 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #28 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #29 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #30 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #31 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #32 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #33 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #34 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #35 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #36 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #37 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #38 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #39 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #40 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #41 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #42 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #43 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #44 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #45 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #46 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #47 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #48 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #49 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #50 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #51 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #52 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #53 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #54 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #55 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #56 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #57 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #58 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #59 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #60 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #61 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #62 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #63 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #64 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #65 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #66 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #67 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #68 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #69 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #70 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #71 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #72 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #73 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #74 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #75 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #76 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #77 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #78 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #79 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #80 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #81 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #82 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #83 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #84 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #85 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #86 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #87 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #88 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #89 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #90 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #91 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #92 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #93 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #94 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #95 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #96 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #97 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #98 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #99 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #100 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #101 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #102 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #103 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #104 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #105 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #106 (Item #502 -
Dish)**

**SECTION VIEW - MODEL 5424SS-VIB-C-PSF-F
HOOD - #107**

3	BULLETIN 3	02/25/25
	PERMIT SET	01/30/25
	90% PROGRESS	01/24/25

ROOTS NATURAL KITCHEN

KITCHEN HOOD
DRAWINGS (4 OF 4)

H1.3

REVISIONS
DISCUSSIONS

1120 Oldsmar Drive, St. Cloud, FL 34772-2811 PHONE: (800) 377-2811 FAX: (800) 377-2811 EMAIL: info@econ-air.com
www.econ-air.com

econ-air
Chicago Foodservice Division
www.econ-air.com

Roots - Cochran-Pittsburgh

7

SHEET NO.

Model: SC/FP Series
The Electrical Package, typically FP, is designed to thermostatically activate the exhaust fans for an exhaust hood whenever elevated temperatures are sensed in the exhaust system. This option meets the requirements of IMC 302.11 by providing a thermostatic switch mounted in the duct or hood or located in the exhaust system. The control enclosure shall be NEMA 1 rated and listed for installation inside of the exhaust hood utility cabinet. The control enclosure may be constructed of stainless steel or painted steel. Temperature sensor is also provided for field installation in the kitchen space in order to start the fans based on temperature difference between the room sensor and the exhaust air in the duct, rather than a fixed temperature set point. The system is factory pre-set to activate at 15 degrees F above the room temperature. Once the duct temperature reaches the activation point, the exhaust fan(s) will be activated. The controls also provide hysteresis to prevent cycling of the fans after the cooking appliances have been turned off and the heat in the duct is reduced. The hysteresis is factory pre-set at 2 degrees and will keep the fans running until temperatures fall to 2 degrees below the activation set point. A hysteresis timer is also provided to keep fans running for 30 minutes after being activated by the temperature rise. The activation and hysteresis settings may be field adjusted on the control board interface located inside the control enclosure to meet specific job site needs. The control panel is factory configured to shut down the supply fan, keep the exhaust fans running, turn off the hoods lights, signal electrical outlet shutdown and turn off the hood lights in a fire condition. If fire condition occurs when exhaust fans are off, the fans will turn on.

SYSTEM DESIGN VERIFICATION (SDV).

IF ORDERED, GAS SERVICE WILL PERFORM A SYSTEM DESIGN VERIFICATION (SDV) DURING ALL EQUIPMENT HAS HAD A COMPLETE START UP PER THE OPERATION AND INSTALLATION MANUAL. TYPICALLY, THE SDV WILL BE PERFORMED AFTER ALL INSPECTIONS ARE COMPLETE. ANY FIELD RELATED DISCREPANCIES THAT ARE DISCOVERED DURING THE SDV WILL BE BROUGHT TO THE ATTENTION OF THE GENERAL CONTRACTOR AND CORRESPONDING TRADES ON SITE. THESE ISSUES WILL BE DOCUMENTED AND FORWARDED TO THE APPROPRIATE SALES OFFICE. IF GAS SERVICE HAS RESOLVED A DISCREPANCY THAT IS A FIELD ISSUE, THE GENERAL CONTRACTOR WILL BE NOTIFIED AND BILLED FOR THE WORK. SHOULD A RETURN TRIP BE REQUIRED DUE TO ANY FIELD RELATED AND DISCREPANCIES THAT CANNOT BE RESOLVED DURING THE SDV, THERE WILL BE ADDITIONAL TRIP CHARGES.

DATE: 1/13/2025

DRAWN #:

7270659

DRAWN BY:

VEN


SCALE:

3/4" = 1'-0"

MASTER DRAWING

Do Not Copy

of NY Engineers



3	BULLETIN 3 02/25/25
	PERMIT SET 01/30/25
	90% PROGRESS 01/24/25

ROOTS NATURAL KITCHEN

ELECTRICAL
 SYMBOLS LIST &
 ABBREVIATIONS

E0.1

LIGHTING PLAN LEGEND	
\$A	SWITCH TYPE (SUPERSCRIPT IN UPPERCASE)
\$0	-20A 120V SPST WALL SWITCH (UON)
	SWITCH TAG (SUBSCRIPT IN LOWERCASE)
\$OS	WALL SWITCH WITH OCCUPANCY SENSOR
\$VS	WALL SWITCH WITH VACANCY SENSOR
\$T	WALL SWITCH WITH TIMER
\$DT	WALL SWITCH WITH DIMMER & TIMER
\$3	3 WAY WALL SWITCH (SPDT)
\$4	4 WAY / INTERMEDIATE WALL SWITCH (DPDT)
\$R	WALL SWITCH WITH SPEED REGULATOR
\$M	MOTOR RATED WALL SWITCH
\$TH	THERMOSTAT WALL SWITCH
\$MO	MANUAL OVERRIDE WALL SWITCH
[PC]	PHOTOCELL WALL MOUNTED
[OS]	OCCUPANCY SENSOR WALL MOUNTED
[OS]	OCCUPANCY SENSOR CEILING MOUNTED
[VS]	VACANCY SENSOR CEILING MOUNTED
[DS]	DAY LIGHT SENSOR CEILING MOUNTED
[TC]	TIME CLOCK - DUAL CHANNEL
[LC]	LIGHTING CONTACTOR

ANNOTATION	
[#]	KEYED NOTE
[#]	EQUIPMENT TAG
(-)	CALLOUT: DETAIL NUMBER ON TOP DRAWING NUMBER ON BOTTOM
(○)	DETAIL OR ELEVATION REFERENCE
A:1	CIRCUIT 1 IN PANEL A

CODE COMPLIANCE	
ALL WORK AND MATERIAL SHALL BE PERFORMED AND INSTALLED IN COMPLIANCE WITH THE FOLLOWING CODES AS ADOPTED AND AMENDED BY THE INSPECTING AUTHORITY. NOTHING IN THESE DRAWINGS IS TO BE CONSTRUCTED TO PERMIT WORK NOT CONFORMING TO THESE CODES OR OTHERS APPLICABLE TO THESE PROJECT:	
NEC: NATIONAL ELECTRICAL CODE 2017 (NFPA-70)	
IECC: INTERNATIONAL ENERGY CONSERVATION CODE 2018	

ELECTRICAL DRAWING LIST	
E.01	ELECTRICAL SYMBOLS AND GENERAL NOTES
E.02	ELECTRICAL SPECIFICATION SHEET 1 of 2
E.03	ELECTRICAL SPECIFICATION SHEET 2 of 2
E1.0	ELECTRICAL LIGHTING PLAN
E2.0	ELECTRICAL POWER PLAN
E2.1	ELECTRICAL ROOF POWER PLAN
E3.0	ELECTRICAL DETAILS
E4.0	ELECTRICAL RISER DIAGRAM & PANEL SCHEDULE
E5.0	ELECTRICAL SITE PLAN

POWER AND COMMUNICATION PLAN LEGEND	
[P]	WALL MOUNTED SIMPLEX RECEPTACLE, RATING SHALL BE SAME AS BREAKER OR AS NOTED
[P]	20A 120V SPST WALL SWITCH (UON)
[P]	SWITCH TAG (SUBSCRIPT IN LOWERCASE)
\$OS	WALL SWITCH WITH OCCUPANCY SENSOR
\$VS	WALL SWITCH WITH VACANCY SENSOR
\$T	WALL SWITCH WITH TIMER
\$DT	WALL SWITCH WITH DIMMER & TIMER
\$3	3 WAY WALL SWITCH (SPDT)
\$4	4 WAY / INTERMEDIATE WALL SWITCH (DPDT)
\$R	WALL SWITCH WITH SPEED REGULATOR
\$M	MOTOR RATED WALL SWITCH
\$TH	THERMOSTAT WALL SWITCH
\$MO	MANUAL OVERRIDE WALL SWITCH
[PC]	PHOTOCELL WALL MOUNTED
[OS]	OCCUPANCY SENSOR WALL MOUNTED
[OS]	OCCUPANCY SENSOR CEILING MOUNTED
[VS]	VACANCY SENSOR CEILING MOUNTED
[DS]	DAY LIGHT SENSOR CEILING MOUNTED
[TC]	TIME CLOCK - DUAL CHANNEL
[LC]	LIGHTING CONTACTOR

ELECTRICAL ABBREVIATIONS	
A	AMPERES
AF	AMPERE FRAME / AMP FUSE
AFF	ABOVE FINISHED FLOOR
AS	AMP SWITCH
A/C	AMPS INTERRUPTING CAPACITY
ATS	AUTOMATIC TRANSFER SWITCH
AUTO	AUTOMATIC
AWG	AMERICAN WIRE GAUGE
C	CONDUIT
C/B, CB	CIRCUIT BREAKER
CKT	CIRCUIT
CLG	CEILING
COMM	COMMUNICATION
CT	CURRENT TRANSFORMER
CU	COPPER
°C	DEGREE CELSIUS
CL	CURRENT LIMITER
DWG	DRAWING
DPSP	DOUBLE POLE SINGLE THROW
DPDT	DOUBLE POLE DOUBLE THROW
E	EXISTING
EF	EXHAUST FAN
EM	EMERGENCY
EMT	ELECTRICAL METALLIC TUBING
EQUIP	EQUIPMENT
ER	EXISTING TO BE RELOCATED
ETR	EXISTING TO REMAIN
EOR	ENGINEER OF RECORD
°F	DEGREE FAHRENHEIT
FA	FIRE ALARM
G	GROUND
GFI	GROUND FAULT INTERRUPTER
GC	GENERAL CONTRACTOR
HD	HAND DRYER
HP	HORSEPOWER
Hz	HERTZ
IG	ISOLATED GROUND
IC	INTERRUPTING CAPACITY
JB	JUNCTION BOX
KCMIL	ONE THOUSAND CIRCULAR MILS
KV	KILOVOLT
KVA	KILOVOLT-AMPERES
KW	KILOWATTS
LP	LIGHTING PANEL
LL	LAND LORD
LTG	LIGHTING
MAX	MAXIMUM
MCB	MAIN CIRCUIT BREAKER
MIN	MINIMUM
MLO	MAIN LUGS ONLY
N	NEUTRAL
NIC	NOT IN CONNECT
NL	NIGHT LIGHT
NTS	NOT TO SCALE
PP	POWER PANEL
PVC	POLYVINYL CHLORIDE
PWR	POWER
R	REMOVE
RE	RELOCATED EXISTING
RR	REMOVE & RELOCATE
SPDT	SINGLE POLE DOUBLE THROW
SPST	SINGLE POLE SINGLE THROW
TR	TAMPER RESISTANT
TYP	TYPICAL
USB	USB JACK
UON	UNLESS OTHERWISE NOTED
VA	VOLT AMPERE
VIF	VERIFY IN FIELD
WP	WEATHER PROOF
W	WIRE / WATT
XMER	TRANSFORMER

ELECTRICAL SHEET GENERAL NOTES	
1.	CONTRACTOR SHALL VISIT THE SITE AND BECOME FAMILIAR WITH ALL EXISTING CONDITIONS THAT MAY AFFECT THE WORK. NO ADDITIONAL COMPENSATION WILL BE CONSIDERED FOR FAILURE TO DO SO.
2.	CONTRACTOR SHALL OBTAIN AND PAY FOR ALL PERMITS, TEST REPORTS, AND CERTIFICATIONS FOR TEMPORARY AND FINAL CERTIFICATE OF OCCUPANCY.
3.	FIRE STOP ALL PENETRATIONS OF FIRE RATED CONSTRUCTION IN A CODE APPROVED MANNER IN ORDER TO MAINTAIN FIRE RATING. ALL PENETRATIONS SHALL BE SLEEVED AND SEALED WATERPROOF.
4.	SECURE ALL SUPPORTS TO BUILDING STRUCTURE UTILIZING TOGGLE BOLTS (HOLLOW MASONRY), EXPANSION SHIELDS OR INSERTS (CONCRETE AND BRICK), MACHINE SCREWS (METAL), BEAM CLAMPS (FRAMEWORK), WOOD SCREWS (WOOD) OR PAN THRU STRAPS (METAL DECK). NAILS, RAWL PLUGS AND WOOD PLUGS ARE NOT PERMITTED, WHERE REQUIRED BY STRUCTURE, PROVIDE THRU BOLTS AND FISH PLATES, SUPPORT HORIZONTAL RUNS OF METALLIC RACEWAYS NOT MORE THAN 10 FT APART. SUPPORT RACEWAY RISERS AT EACH FLOOR LEVEL. RUN EXPOSED RACEWAYS PARALLEL WITH OR AT RIGHT ANGLES TO WALLS.
5.	LEAVE WIRES WITH SUFFICIENT SLACK TO PERMIT MAKING FINAL CONNECTIONS. RACEWAYS OVER 10 FT LONG IN WHICH WIRING IS NOT INSTALLED: FURNISH FISH WIRE.
6.	VERIFY LOCATIONS OF OUTLETS AND SWITCHES IN FINISHED ROOMS WITH ARCHITECTURAL DRAWINGS OF INTERIOR DETAILS AND FINISH, IN CENTERING OUTLETS AND LOCATING BOXES AND OUTLETS. ALLOW FOR OVERHEAD PIPES, DUCTS AND MECHANICAL EQUIPMENT, EQUIPMENT, VARIATIONS IN FIREPROOFING AND PLASTERING, WINDOW AND DOOR TRIM, PANELING, HUNG CEILINGS AND THE LIKE. CORRECT ANY INACCURACY RESULTING FROM FAILURE TO DO SO WITHOUT EXPENSE TO OWNER.
7.	CONTRACTOR SHALL PROVIDE A WARRANTY ON ALL MATERIALS, EQUIPMENT, AND WORKMANSHIP FOR A PERIOD OF ONE YEAR FROM THE DATE OF FINAL ACCEPTANCE.
8.	ALL UNUSED MATERIALS AND DEBRIS SHALL BE LEGALLY REMOVED AND DISPOSED OF AWAY FROM THE PREMISES ON A DAILY BASIS.
9.	CONTRACTOR SHALL PATCH, PAINT, AND RESTORE EXISTING SURFACES DAMAGED DURING THE COURSE OF THIS CONSTRUCTION TO PRE-EXISTING CONDITIONS OR BETTER.
10.	MINIMUM SIZE OF CONDUIT SHALL BE $\frac{3}{4}$ IN. AND TYPE SHALL BE ELECTRICAL METALLIC TUBING (EMT), UNLESS OTHERWISE NOTED. PROVIDE NYLON DRAG LINE AND CONDUIT CAP FOR ALL EMPTY CONDUITS.
11.	CONNECT CONDUIT TO MOTOR CONDUIT TERMINAL BOXES WITH FLEXIBLE CONDUIT (MINIMUM 18 IN. LENGTH AND 50% SLACK). DO NOT TERMINATE IN OR FASTEN RACEWAYS TO MOTOR FOUNDATION.
12.	PULL AND JUNCTION BOXES WHERE INDICATED ON THE DRAWINGS, SHALL BE CONSIDERED SHOWN AT THEIR APPROXIMATE LOCATION. THE CONTRACTOR SHALL LOCATE THEM AS FIELD CONDITIONS DICTATE. ADDITIONAL PULL AND JUNCTION BOXES NOT SHOWN ON DRAWINGS SHALL BE PROVIDED WHERE REQUIRED BY APPLICABLE CODE PROVISIONS OR WHERE CALLED FOR BY FIELD CONDITIONS. PULL AND JUNCTION BOXES SHALL BE SURFACE TYPE IN UNFINISHED AREAS AND INSTALLED CONCEALED IN FINISHED AREAS, AND ALL COVERS TO PULL & JUNCTION BOXES SHALL BE READILY ACCESSIBLE.
13.	SUPPORT PANEL, JUNCTION AND PILLBOXES INDEPENDENTLY TO BUILDING STRUCTURE WITH NO WEIGHT BEARING ON RACEWAYS.
14.	FOR EXACT LOCATION AND MOUNTING HEIGHT OF LIGHTING FIXTURES AND SWITCH/RECEPTACLE OUTLETS, REFER TO ARCHITECTURAL REFLECTED CEILING AND POWER PLANS.
15.	ALL ELECTRICAL ACCESSORIES AND EQUIPMENT INSTALLED OUTSIDE OR EXPOSED TO WEATHER SHALL HAVE NEMA 3R ENCLOSURES AND SHALL BE TIGHTLY GASKETED FOR A COMPLETE RAIN-TIGHT INSTALLATION. ALL BUILDING EXTERIOR MOUNTED RECEPTACLES SHALL BE GFCI RATED AND MOUNTED IN WEATHERPROOF ENCLOSURE.
16.	ALL ACCESS PANEL LOCATIONS SHALL BE REVIEWED BY ARCHITECT PRIOR TO INSTALLATION.
17.	ELECTRICAL CONTRACTOR SHALL COORDINATE THE LOCATION AND INSTALLATION OF NEW WORK WITH THE GENERAL CONTRACTOR AND OTHER ASSOCIATED TRADES IN A TIMELY MANNER. THE CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING ALL DIMENSIONS AND CONDITIONS PRIOR TO CONSTRUCTION. REFER TO ALL GENERAL, MECHANICAL, AND ELECTRICAL DRAWINGS AND SPECIFICATIONS FOR THIS PROJECT.
18.	ALL CONDUITS AND EQUIPMENT TO BE CONCEALED IN FINISHED SPACES UNLESS OTHERWISE NOTED. CONDUITS SHALL BE ENCASED IN THE CONCRETE FLOOR SLAB.
19.	ALL EQUIPMENT AND MATERIALS INSTALLED IN PLENUM CEILINGS SHALL BE APPROVED FOR THAT APPLICATION.
20.	OUTLET BOXES AND JUNCTION BOXES ON OPPOSITE SIDES OF FIRE-RATED WALLS SHALL BE SEPARATED BY A HORIZONTAL DISTANCE OF NOT LESS THAN 24 INCHES, UNLESS FIRE-RATED BOXES OR PUTTY PADS ARE UTILIZED.
21.	COORDINATE ALL FLOOR PENETRATIONS WITH THE STRUCTURAL AND ARCHITECTURAL DRAWINGS. CONFIRM PENETRATION LOCATIONS WITH THE ENGINEER AND OWNER BEFORE INSTALLATION.
22.	COORDINATE THE MOUNTING HEIGHT AND LOCATION OF RACEWAYS, COMMUNICATIONS OUTLETS, AND RECEPTACLES WITH THE ARCHITECTURAL CASEWORK DRAWINGS AND DETAILS. COORDINATE LOCATIONS OF LIGHT FIXTURES, SWITCHES, AND RELATED DEVICES WITH THE ARCHITECTURAL DRAWINGS AND DETAILS.
23.	REFER TO ARCHITECTURAL PLANS FOR FINAL LOCATIONS OF ALL LUMINARIES AND SWITCHES, AND FOR ALL FINISHED CEILING HEIGHTS.
24.	REFER TO ARCHITECTURAL PLANS FOR FINAL LOCATIONS OF ALL ELECTRICAL DEVICES, AND FOR FINAL CEILING AND WALL HEIGHTS AND LAYOUTS.
25.	LIGHTING FIXTURES PROVIDED WITH EMERGENCY BATTERY PACKS AND INDICATED WITH SWITCH CONTROL SHALL BE WIRED WITH BATTERY CHARGING/SENSING CIRCUIT WIRED AHEAD OF SWITCH CONTROL.
26.	NUMBER(S) SHOWN AT RECEPTACLES, JUNCTION BOXES AND EQUIPMENT INDICATES CIRCUIT NUMBERS IN PANEL BOARD. PROVIDE WIRE AND CONDUIT TO INTERCONNECT EQUIPMENT AND DEVICES WITH SAME CIRCUIT NUMBERS AND RUN TO PANEL BOARD.

Property

ELECTRICAL SPECIFICATIONS

1. GENERAL:

- A. THE "GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION," AIA DOCUMENT A201, LATEST EDITION, AND THESE SPECIFICATIONS AS APPLICABLE ARE PART OF THIS CONTRACT.
- B. DRAWINGS ARE DIAGRAMMATIC AND INDICATE GENERAL ARRANGEMENT OF SYSTEMS AND WORK. CONDUIT ROUTING IS SHOWN DIAGRAMMATICALLY AND DOES NOT SHOW ALL OFFSETS, DROPS AND RISES OF RUNS. THE CONTRACTOR SHALL ALLOW IN THEIR PRICE FOR ROUTING OF CONDUIT TO AVOID OBSTRUCTIONS. COORDINATION WITH EXISTING SERVICES, INCLUDING THOSE OF OTHER TRADES, IS REQUIRED, MAINTAIN HEADROOM AND SPACE CONDITIONS.
- C. BIDDERS, BEFORE SUBMITTING PROPOSALS, SHALL VISIT AND CAREFULLY EXAMINE THE AREA AFFECTED BY THIS WORK TO FAMILIARIZE THEMSELVES WITH THE EXISTING CONDITIONS AND THE DIFFICULTIES THAT MAY ATTEND THE EXECUTION OF THIS WORK. SUBMISSION OF A PROPOSAL WILL BE CONSIDERED AS EVIDENCE THAT SUCH AN EXAMINATION HAS BEEN MADE, AND LATER CLAIMS WILL NOT BE RECOGNIZED FOR EXTRA LABOR, EQUIPMENT, OR MATERIALS, REQUIRED BECAUSE OF DIFFICULTIES ENCOUNTERED WHICH COULD HAVE BEEN FORESEEN HAD SUCH AN EXAMINATION BEEN MADE.
- D. INSTALL WORK SO AS TO BE READILY ACCESSIBLE FOR OPERATION, MAINTAINANCE AND REPAIR. MINOR DEVIATIONS FROM DRAWING MAY BE MADE TO ACCOMPLISH THIS, BUT CHARGES WHICH INVOLVE EXTRA COST SHALL NOT BE MADE WITHOUT APPROVAL.
- E. REMOVAL AND RELOCATION OF CERTAIN EXISTING WORK MAY BE NECESSARY FOR THE PERFORMANCE OF THE GENERAL WORK. ALL EXISTING CONDITIONS CANNOT BE COMPLETELY DETAILED ON THE DRAWINGS. THE CONTRACTOR SHALL SURVEY THE SITE AND INCLUDE ALL CHARGES AND CHARGES IN MAKING UP THE WORK PROPOSAL.
- F. CONNECTIONS TO EXISTING WORK: INSTALL NEW WORK AND CONNECT TO EXISTING WORK WITH MINIMUM INTERFERENCE TO EXISTING FACILITIES. TEMPORARY SHUTDOWNS OF EXISTING SERVICES SHALL BE PERFORMED AT NO ADDITIONAL CHARGES, AT TIMES NOT TO INTERFERE WITH THE NORMAL OPERATION OF EXISTING FACILITIES AND ONLY WITH THE CONSENT OF OWNER. EXISTING ELECTRICAL SYSTEMS SHALL NOT BE INTERRUPTED TO MAINTAIN CONTINUOUS OPERATION OF EXISTING FACILITIES AS REQUIRED, WITH NECESSARY TEMPORARY CONNECTIONS BETWEEN NEW AND EXISTING WORK. CONNECT NEW WORK TO EXISTING WORK IN NEAT AND ACCEPTABLE MANNER. RESTORE EXISTING DISTURBED WORK TO ORIGINAL CONDITION, INCLUDING MAINTENANCE OF WIRING CONTINUITY AS REQUIRED.
- G. DISCONNECT, REMOVE AND/OR RELOCATE EXISTING MATERIAL, EQUIPMENT AND OTHER WORK AS NOTED OR REQUIRED FOR PROPER INSTALLATION OF NEW WORK.
- H. THE CONTRACTOR SHALL KEEP ALL EQUIPMENT AND MATERIALS, AND ALL PARTS OF THE BUILDING EXTERIOR SPACES AND ADJACENT STREETS, SIDEWALKS AND PAVEMENTS, FREE FROM MATERIAL AND DEBRIS RESULTING FROM THE EXECUTION OF THIS WORK. EXCESS MATERIALS WILL NOT BE PERMITTED TO ACCUMULATE EITHER ON THE INTERIOR OR THE EXTERIOR.
- I. SEAL OPENINGS THROUGH PARTITIONS, WALLS AND FLOORS WITH MINERAL WOOL OR OTHER NONCOMBUSTIBLE MATERIAL, UNLESS OTHERWISE NOTED.
- J. PROVIDE ALL NECESSARY FLASHING AND COUNTER FLASHING TO MAINTAIN THE WATERPROOFING INTEGRITY OF THE BUILDING AS REQUIRED BY THE INSTALLATION OR REMOVAL OF CONDUIT AND EQUIPMENT, PROVIDE EQUIPMENT CURBS AS REQUIRED.
- K. ALL EXISTING MATERIAL, EQUIPMENT AND CONSTRUCTION DEBRIS TO BE REMOVED UNDER THIS CONTRACT SHALL BECOME THE PROPERTY OF THE CONTRACTOR WITH THE EXCEPTION OF SPECIFIC EQUIPMENT OR APPARATUS REQUESTED BY THE BUILDING REPRESENTATIVE, ARCHITECT OR AS NOTED TO BE RELOCATED ON THE DRAWINGS. REMOVED EQUIPMENT SHALL BE PROPERLY DISPOSED OF BY THIS CONTRACTOR.
- L. THE CONTRACTOR'S PROPOSAL FOR ALL WORK SHALL BE BASED ON THE PERFORMANCE OF THE WORK DURING REGULAR WORKING HOURS, WHEN SO DIRECTED. HOWEVER, THE CONTRACTOR SHALL INSTALL WORK DURING OVERTIME HOURS AND THE ADDITIONAL COST TO BE CHARGED THEREFORE SHALL BE ONLY THE "PREMIUM" PORTION OF THE WAGES PAID.
- M. UNLESS OTHERWISE SPECIFICALLY NOTED OR SPECIFIED, INCLUDE ALL CUTTING AND PATCHING OF EXISTING FLOORS, WALLS, PARTITIONS AND OTHER MATERIALS IN THE EXISTING BUILDING. THE CONTRACTOR SHALL RESTORE THESE AREAS TO ORIGINAL CONDITION.
- N. ALL MATERIAL AND EQUIPMENT SHALL BE NEW UNLESS OTHERWISE NOTED AND SHALL BE IN ACCORDANCE WITH BUILDING STANDARDS.
- O. INSURANCE: PROVIDE IN ACCORDANCE WITH OWNER/BUILDING REQUIREMENTS AND SHALL INCLUDE A HOLD HARMLESS CLAUSE FOR OWNER AND ENGINEER.
- P. THE FINAL ACCEPTANCE SHALL BE MADE AFTER THE CONTRACTOR HAS ADJUSTED HIS EQUIPMENT, TESTED THE VARIOUS SYSTEMS, DEMONSTRATED THAT IT FULFILLS THE REQUIREMENTS OF THE DRAWINGS AND SPECIFICATIONS AND HAS FURNISHED ALL THE REQUIRED CERTIFICATE OF INSPECTION AND APPROVAL.

2. GENERAL PROVISIONS FOR ELECTRICAL WORK:

- A. DEFINITIONS:
 - 1) "PROVIDE": TO FURNISH, INSTALL AND CONNECT UP COMPLETE AND READY FOR SAFE AND REGULAR OPERATION THE PARTICULAR WORK REFERRED TO UNLESS SPECIFICALLY OTHERWISE NOTED.
 - 2) "INSTALL": TO ERECT, MOUNT AND CONNECT COMPLETE WITH RELATED ACCESSORIES.
 - 3) "FURNISH" OR "SUPPLY": TO PURCHASE, PROCURE, ACQUIRE, AND DELIVER COMPLETE WITH RELATED ACCESSORIES.
 - 4) "WORK": LABOR, MATERIALS, EQUIPMENT, APPARATUS, CONTROLS, ACCESSORIES AND OTHER ITEMS REQUIRED FOR PROPER AND COMPLETE INSTALLATION.
 - 5) "WIRING": RACEWAY, FITTINGS, WIRE, BOXES, AND RELATED ITEMS.
 - 6) "CONCEALED": EMBEDDED IN MASONRY OR OTHER CONSTRUCTION, INSTALLED IN FURRED SPACES, WITHIN DOUBLE PARTITIONS OR HUNG CEILINGS, IN TRENCHES, IN CRAWL SPACES, OR IN ENCLOSURES.
 - 7) "EXPOSED": NOT INSTALLED UNDERGROUND OR "CONCEALED" AS DEFINED ABOVE.
 - 8) "SIMILAR" OR "EQUAL": EQUAL IN MATERIALS, WEIGHT, SIZE, DESIGN AND EFFICIENCY OF SPECIFIED PRODUCT.
- B. TEMPORARY LIGHT AND POWER: PROVIDE TEMPORARY LIGHT AND POWER SYSTEMS AT EARLIEST POSSIBLE DATE WITHIN THE CONSTRUCTION AREAS FOR THE REQUIREMENTS OF ALL TRADES AS HEREIN DESCRIBED. EXTEND SYSTEMS TO NEW CONSTRUCTION AS SOON AS PHYSICALLY POSSIBLE. MAINTAIN SYSTEM DURING WORKING HOURS. PROVIDE ALL REQUIRED MAINTENANCE, INCLUDING LAMPS AND

- C. SOCKETS:
 - 1) QUALITY OF MATERIALS: ALL EQUIPMENT SHALL BE NEW SPECIFICATION GRADE, FREE FROM DEFECTS AND LISTED BY APPROVED TESTING AGENCY AND BEARING THEIR LABEL MATERIALS AND EQUIPMENT OF SIMILAR APPLICATION SHALL BE OF SAME MANUFACTURER, EXCEPT AS NOTED.
 - 2) GUARANTEE: ALL MATERIALS AND WORKMANSHIP SHALL BE GUARANTEED AS DEFINED IN PARAGRAPH 2.C.
 - 3) HEIGHTS OF OUTLETS: REFER TO ARCHITECTURAL AND/OR INTERIOR DESIGNER'S PLANS FOR DEVICE HEIGHTS IN NON BOH SPACES.
 - a. FROM FINISHED FLOOR TO CENTERLINE OF OUTLETS FOR:
 - RECEPTACLES AND TELEPHONES: 1 FT-6 IN.
 - WALL SWITCHES: 4 FT-0 IN.
 - WALL FIXTURES: 7 FT-0 IN.
 - MOTOR CONTROLLERS: 5 FT-0 IN.
 - CLOCKS: 7 FT 6 IN
 - b. EXCEPTIONS: AT JUNCTION OF DIFFERENT WALL FINISH MATERIALS, ON MOLDING OR BREAK IN WALL SURFACE, IN VIOLATION OF CODE, OR AS NOTED OR DIRECTED.
 - c. REFER TO ARCHITECTURAL AND/OR INTERIOR DESIGNER'S PLANS FOR DEVICE HEIGHTS IN NON BOH SPACES
- D. PRODUCT DELIVERY, STORAGE AND HANDLING:
 - 4) MOVING OF EQUIPMENT: WHERE NECESSARY, SHIP IN CARTED SECTIONS OF SIZE TO PERMIT PASSING THROUGH AVAILABLE SPACES.
 - 5) ACCESSIBILITY: FOR OPERATION, MAINTENANCE AND REPAIR, MINOR DEVIATIONS SHALL BE PERMITTED, CHANGES OF MAGNITUDE OR INVOLVING EXTRA COST ARE NOT PERMISSIBLE WITHOUT REVIEW. GROUP CONCEALED ELECTRICAL EQUIPMENT REQUIRING ACCESS WITH EQUIPMENT FREELY ACCESSIBLE THROUGH ACCESS DOORS.
- E. MATERIALS:
 - 1) NAMEPLATES: PROVIDE BLACK LAMACOID SHEET WITH 3/4 IN. LETTERING FASTENED WITH 100 PERCENT FOR EACH DISCONNECT, CIRCUIT BREAKER, PANEL, CABINET, TRANSFORMER, ENCLOSURE, MOTOR CONTROLLER AND THE LIKE. NAMEPLATES SHALL DESCRIBE THE NAME AND NUMBER OF EACH COMPONENT.
 - 2) CABLE TAGS: TAG EACH CONDUCTOR PASSING THROUGH SPLICE OR PULLBOX WITH A WHITE LINEN TAG, INDICATING POINT OF ORIGIN AND TERMINATION OF THE CIRCUIT.
 - 3) INSERTS AND SUPPORTS:
 - a. INSERTS: STEEL SLOTTED TYPE, FACTORY PAINTED.
 - SINGLE ROD: SIMILAR TO GRINNELL FIG. 281.
 - MULTI-ROD: SIMILAR TO FEE AND MASON SERIES 9000 WITH END CAPS AND CLOSURE STRIPS.
 - CLIP FORM NAILS FLUSH WITH INSERTS.
 - MAXIMUM LOADING 75 PERCENT OF RATING.
 - b. SUPPORTS FROM BUILDING CONSTRUCTION: INSERTS, BEAM CLAMPS, STEEL FISHPLATES (IN CONCRETE FILL ONLY), CANTILEVER BRACKETS OR OTHER MEANS. SUBMIT FOR REVIEW.
 - c. GROUPED LINES AND SERVICES: TRAPEZE HANGERS OF BOLTED ANGLES OR CHANNELS.
 - d. WHERE BUILDING CONSTRUCTION IS INADEQUATE: PROVIDE ADDITIONAL FRAMING. SUBMIT FOR REVIEW.
- F. SUBMIT ELECTRICAL POWER SYSTEM STUDIES INCLUDING SUPPORTING DATA AND RECOMMENDATIONS FOR THE FOLLOWING:
 - 1) SHORT CIRCUIT CURRENT AND PROTECTIVE DEVICE COMBINATION.
 - 2) ARC FLASH HAZARD ANALYSIS.

EQUIPMENT SHOP DRAWINGS SHALL NOT BE SUBMITTED UNTIL THESE STUDIES HAVE BEEN COMPLETED.
- G. PAINT SHALL BE THE BEST GRADE FOR ITS PURPOSE. DELIVER IN ORIGINAL SEALED CONTAINERS AND APPLY IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. COLORS SHALL BE AS SELECTED BY ARCHITECT OR ENGINEER. ULTRALUMINIZED IRON PRIMER ON PANEL AND PULL BOXES. AFTER FABRICATION, UTILIZE HOT DIPPED GALVANIZED OR DIPCOAT IN ZINC BASED PRIMER FOR OUTLET BOXES, JUNCTION BOXES, CONDUIT HANGERS, RODS, INSERTS AND SUPPORTS. ZINC BASED PRIMER WITH FINISH TO MATCH SURROUNDINGS. SHALL BE USED FOR MARRED SURFACES OF STEEL EQUIPMENT AND RACEWAYS. A FIELD-APPLIED ZINC BASED PRIME COAT SHALL BE UTILIZED FOR STEEL OR IRONWORK.
- H. BRUSH AND CLEAN WORK PRIOR TO CONCEALING, PAINTING AND ACCEPTANCE. PAINTED EXPOSED WORK SOILED OR DAMAGED; CLEAN AND REPAIR TO MATCH ADJOINING WORK BEFORE FINAL ACCEPTANCE. REMOVE DEBRIS FROM INSIDE AND OUTSIDE OF MATERIAL AND EQUIPMENT.
- I. FINAL LOCATIONS AND MOUNTING ORIENTATIONS OF ALL SWITCHES, RECEPTACLES AND LIGHT FIXTURES SHALL BE VERIFIED WITH ARCHITECT.
- J. ALL ACCESS DOOR LOCATIONS SHALL BE REVIEWED BY ARCHITECT PRIOR TO INSTALLATION.
- 3. SCOPE OF WORK:
 - G. SCOPE OF WORK SHALL CONSIST OF PROVIDING LABOR, MATERIALS, EQUIPMENT, SERVICES AND FEES NECESSARY FOR COMPLETE AND SAFE INSTALLATION IN CONFORMING WITH THE 2017 NATIONAL ELECTRICAL CODE (NEC) **NYC** AMENDMENTS, AND ALL OTHER APPLICABLE INDUSTRY, NATIONAL AND LOCAL CODES AND AUTHORITIES HAVING JURISDICTION, AS INDICATED ON DRAWINGS AND HEREIN SPECIFIED.
 - H. ALL DRAWINGS, PLANS, DETAILS, SPECIFICATIONS AND SPECIFICATION ADDENDA ARE MADE PART OF THIS CONTRACT AND SHALL APPLY TO ALL WORK UNDER THE CONTRACT UNLESS OTHERWISE AMENDED, MODIFIED, SUPPLIED OR SPECIFIED HEREIN.
 - I. THE CONTRACTOR SHALL FURNISH A WRITTEN GUARANTEE TO REPLACE OR REPAIR, PROMPTLY AND AS SAME RESPONSIBILITY FOR ALL EXPENSES INCURRED FOR ANY WORKMANSHIP AND EQUIPMENT IN WHICH DEFECTS DEVELOP WITHIN ONE YEAR FROM THE DATE OF FINAL CERTIFICATE FOR PAYMENT AND/OR FROM DATE OF ACTUAL USE OF EQUIPMENT OR OCCUPANCY OF SPACES BY OWNER INCLUDED UNDER THE VARIOUS PARTS OF THE WORK, WHICHEVER DATE IS EARLIER. THIS WORK SHALL BE DONE AS DIRECTED BY THE OWNER. THIS GUARANTEE SHALL ALSO PROVIDED THAT WHERE DEFECTS OCCUR, THE CONTRACTOR WILL ASSUME RESPONSIBILITY OF OTHER TRADES AFFECTED BY DEFECTS, REPAIRS OR REPLACEMENTS IN EQUIPMENT SUPPLIED BY THE CONTRACTOR.

- J. THE CONTRACTOR SHALL GIVE NECESSARY NOTICE, FILE DRAWINGS AND SPECIFICATIONS WITH ALL DEPARTMENTS HAVING JURISDICTION, WORK AND PAY ALL FEES THEREFORE. THE CONTRACTOR SHALL ARRANGE FOR INSPECTION AND TESTS OF ANY OR ALL PARTS OF THE WORK IF SO REQUIRED BY AUTHORITY HAVING JURISDICTION AND PAY ALL CHARGES FOR SAME. THE CONTRACTOR SHALL PAY ALL COSTS FOR AND FURNISH TO THE OWNER BEFORE FINAL BILLING, ALL CERTIFICATES NECESSARY AS EVIDENCE THAT THE WORK INSTALLED CONFORMS WITH ALL REGULATIONS WHERE THEY APPLY TO THIS WORK.
- K. CONTRACTOR SHALL PERFORM ALL CONTROLLED INSPECTIONS IN ACCORDANCE WITH THE NYC BUILDING CODE. SECURE ALL REQUIRED PERMITS AND APPROVALS AND TRANSMIT SAME TO OWNER. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL FEES.
- L. AREAS WITH NO ELECTRICAL WORK SHALL REMAIN AS IS. CONTRACTOR SHALL MAINTAIN CONTINUITY OF ALL ELECTRICAL SYSTEMS TO ALL AREAS NOT COVERED BY THIS RENOVATION, AND SHALL PROVIDE 48 HOUR NOTICE TO LANDLORD OF ANY PLANNED POWER INTERRUPTIONS OR SIGNAL SYSTEM OUTAGES.

7. FUSES:

- A. OVERCURRENT AND SHORT CIRCUIT PROTECTION WITHIN FUSIBLE SWITCHES SHALL BE CLASS L CURRENT LIMITING TIME DELAY FUSES FOR SWITCHES RATED 800A AND LARGER AND CLASS RK-1 CURRENT LIMITING TIME DELAY FUSES FOR SWITCHES RATED 600A AND SMALLER. MANUFACTURER SHALL BE BUSSMAN.
- B. INDIVIDUAL MOTOR STARTERS SHALL INCLUDE TWO SETS OF NORMALLY OPEN CONTACTS, ONE SET OF NORMALLY CLOSED CONTACTS, THREE OVERLOAD RELAYS, INDIVIDUALLY FUSED CONTROL TRANSFORMER, HAND OFF AUTO SELECTOR SWITCH FOR AUTOMATIC START AND PILOT LIGHT(S) AS REQUIRED. COMBINATION STARTER DISCONNECTS SHALL INCLUDE FUSIBLE SWITCHES. CONTACTORS SHALL BE NEMA TYPE WITH REPLACEABLE COIL AND CONTACT TIPS. MANUFACTURER SHALL BE EATON, SIEMENS OR SQUARE D.
- C. ALL FUSES SHALL BE PROVIDED BY SAME MANUFACTURER.
- D. PROVIDE 1 SPACE MATCHING FUSE FOR EACH SET OF 3.
- E. CIRCUIT BREAKERS: MOLDED CASE BREAKERS SHALL BE THERMAL-MAGNETIC, QUICK-MAKE, QUICK-BREAK, AND ONLY THOSE MANUALLY OPERATED WITH INSULATED THUMB HANDLE. MULTI-POLE TYPE BREAKERS SHALL CONTAIN INTERNAL TRIP BAR. TERMINALS SHALL BE SUITABLE FOR COPPER OR ALUMINUM CABLE. FURNISH AUXILIARY DEVICES WHERE REQUIRED FOR SHUNT-TRIPPING, OPEN A ND CLOSE MOTOR OPERATOR AND ALARM INDICATION. ENCLOSURES SHALL BE DEAD FRONT, NEMA TYPE 1, EXCEPT AS NOTED. FRAMES, IC AND INTERCHANGEABLE TRIPS SHALL BE AS FOLLOWS, UNLESS OTHERWISE NOTED:
 - 1) 120 VOLTS, 100-AMP FRAME: 10,000 AMPS, 1 POLE.
 - 2) 120/240 VOLTS, 225-AMP FRAME: 22,000 AMPS MINIMUM
- F. SUBMIT SHOP DRAWINGS FOR THE FOLLOWING:
 - 1) SAFETY/DISCONNECT SWITCHES
 - 2) FUSES
 - 3) CIRCUIT BREAKERS
 - 4) DISTRIBUTION EQUIPMENT INCLUDING SWITCHBOARDS, TRANSFORMERS, PANELBOARDS AND LOAD CENTERS.
 - 5) RACEWAYS
 - 6) WIRE AND CABLE
 - 7) LIGHTING CONTROL DEVICES
 - 8) INSERTION RECEPTACLES
 - 9) MOMENTARY CONTACT SWITCHES
 - 10) TIME SWITCHES
 - 11) LIGHTING FIXTURES, BALLASTS AND LAMPS.
 - 12) FIRE ALARM EQUIPMENT AND DEVICES.
 - 13) MOTOR STARTERS.

8. DISTRIBUTION PANELBOARDS, CIRCUIT BREAKER TYPE:

- A. DISTRIBUTION PANELBOARDS SHALL BE FULLY RATED WITH COPPER PHASE, NEUTRAL, AND GROUND BUS, BRACED AT 65000 AIC FOR 480/277 VOLT SYSTEM AND 42000 AIC FOR 208Y/120 VOLT SYSTEM, OR MORE TO BE GREATER THAN THE AVAILABLE SHORT CIRCUIT CURRENT. ISOLATED GROUND BUS SHALL BE AS REQUIRED. MANUFACTURERS SHALL BE EATON, SIEMENS OR SQUARE D.
- B. BRANCH PANELBOARDS SHALL BE FULLY RATED WITH COPPER PHASE, NEUTRAL AND GROUND BUS, BRACED AT 14000 AIC FOR 480/277 VOLT SYSTEM AND 10000 AIC FOR 208Y/120 VOLT SYSTEM, OR MORE TO BE GREATER THAN THE AVAILABLE SHORT CIRCUIT CURRENT. NEUTRAL BUS SHALL BE RATED AT 200 PERCENT WITHIN PANELS SERVING NON-LINEAR LOADS. ISOLATED GROUND BUS SHALL BE AS REQUIRED. MANUFACTURER SHALL BE EATON, SIEMENS, OR SQUARE D.

8. DISTRIBUTION PANELBOARDS, SWITCH AND FUSE:

- A. THREE PHASE, 3 OR 4 WIRE WITH COPPER BUS BARS. ALL THROUGH BUS SHALL BE INSULATED.
- B. NEMA CLASS 1 CONSTRUCTION TO ACCOMMODATE FUSIBLE, INDIVIDUALLY ENCLOSED SWITCHES, FRONT REMOVABLE, SWITCH AND DOOR INTERLOCKS. COVERS TO BE PAD-LOCKABLE.
- C. PANELBOARD SHALL BE CONSTRUCTED OF CODE-GAUGE STEEL, GRAY FINISH OVER RUST INHIBITOR, FOR SURFACE MOUNTING. BOX AND PANEL FRAME SHALL BE FLANGED AND REINFORCED FOR RIGID SUPPORT OF INTERIOR AND ACCURATE ALIGNMENT OF INTERIOR WITH FRONT. TRIMS TO BE FASTENED TO BACK BOX WITH SCREWS.
- D. ALL BRANCH SWITCHES SHALL HAVE INDIVIDUAL ENGRAVED LAMACOID NAMEPLATES (BLACK WITH WHITE CORE).

E. DISCONNECTS

- 1) DISCONNECT SWITCHES SHALL CONFORM TO NEMA AND UL STANDARDS, AND SHALL BE HORSEPOWER RATED.
- 2) SWITCHING MECHANISM SHALL BE QUICK-MAKE, QUICK-BREAK, SINGLE THROW WITH EXTERNAL OPERATING HANDLE MECHANICALLY INTERLOCKED WITH ENCLOSURE COVER TO PROVIDE ACCESS TO INTERIOR WHEN DISCONNECT IS IN OFF POSITION ONLY. PROVIDE MEANS TO LOCK OPERATING HANDLE IN THE OPEN AND CLOSED POSITION. DESIGNATE ON THE ENCLOSURE THE OPEN AND CLOSED POSITION OF THE OPERATING HANDLE.
- 3) SWITCHES SHALL BE OF THE DOUBLE STATIONARY CONTACT TYPE.
- 4) SWITCHES SHALL BE EQUIPPED WITH REJECTION TYPE FUSE HOLDERS, FUSIBLE AS SHOWN ON THE DRAWINGS; PROVIDE COMPLETE WITH FUSES AS SCHEDULED.

F. INSTALLATION

- 1) DISTRIBUTION PANELBOARD SHALL BE MOUNTED TO STRUCTURAL STEEL CHANNEL (KINDOF) WHICH SHALL BE BOLTED TO THE WALL USING EXPANSION ANCHORS FOR LARGE PANELS.

H. IDENTIFICATION

- 1) PROVIDE NAMEPLATE AT EACH SWITCH IDENTIFYING THE LOAD SERVED.
- 2) NAMEPLATES SHALL BE MOUNTED ON THE FRONT COVER SECURED WITH SELF-TAPPING SCREWS OR NUTS AND BOLTS. NAMEPLATES SHALL BE LAMINATED PHENOLIC, BLACK WITH A MINIMUM OF 1/4" HIGH WHITE LETTERING.

- I. DISTRIBUTION AND SUB-DISTRIBUTION PANELBOARDS SHALL BE A MINIMUM OF 30" WIDE AND 10" DEEP.
- J. POWER PANELBOARDS SHALL BE SIMILAR TO GENERAL ELECTRIC TYPE "OMR", AS MANUFACTURED BY ATLAS SWITCH COMPANY, ELECTRIC SWITCHBOARD COMPANY OR APPROVED EQUAL.
- K. PANELBOARD SHALL HAVE MAIN CIRCUIT BREAKER OR MAIN LUGS AS INDICATED ON THE DRAWINGS. QUANTITY, POLES AND TRIP RATINGS OF BRANCH CIRCUIT BREAKERS TO BE AS INDICATED ON DRAWINGS.
- L. PANELBOARD SHALL HAVE ENGRAVED WHITE CORE, BLACK LAMACOID NAMEPLATE SCREWED ONTO PAN TRIM WITH DESIGNATION LISTED (PANELBOARD NAME, VOLTAGE, RATING OR MAINS IN AMPS).

DRAWN NYE
CHECKED NYE
PROJECT NO. 240720

3 BULLETIN 3	02/25/25
PERMIT SET	01/30/25
90% PROGRESS	01/24/25

ELECTRICAL SPECIFICATIONS (CONT.)

3) BOXES:

A. OUTLET BOXES: EXCEPT AS OTHERWISE REQUIRED BY CONSTRUCTION, DEVICES OR WIRING, BOXES SHALL BE STAMPED STEEL, 4 IN. SQUARE OR OCTAGON FOR FIXTURES. BOXES ABOVE CEILING SHALL BE 1-1/2 IN. DEEP, BOXES IN WALL FOR FIXTURES SHALL BE 2-3/4 IN. DEEP. BOXES IN WALL FOR RECEPTACLES AND SWITCHES SHALL BE 1-1/2 IN. DEEP. FURNISH WITH RAISED COVERS AND FIXTURE STUDS WHERE REQUIRED. WITHOUT FIXTURE OF DEVICE, FURNISH BLANK COVER, OFFSET BACK-TO-BACK OUTLETS WITH MINIMUM 6 IN. SEPARATION. MANUFACTURE SHALL BE APPLETON, RACO OR STEEL CITY.

B. JUNCTION AND PULL BOXES: GALVANIZED SHEET STEEL WITH SCREW-ON COVERS, EXCEPT AS NOTED. FURNISH WITH INSULATED SUPPORTS FOR CABLES. LOCATIONS SHALL BE AS NOTED OR REQUIRED AND ACCESSIBLE. PROVIDE BARRIERS IN NEW AND RENOVATED BOXES BETWEEN 120/208 VOLT AND 265/460 VOLT WIRING AND BETWEEN EMERGENCY AND NORMAL WIRING. FLOOR BOXES SHALL BE ADJUSTABLE CONCRETE TIGHT, PRERESSED STEEL, WITH BRASS FLANGE AND COVER. FLOOR BOXES SHALL INCLUDE ACCESS TRIM AND HINGED OUTLET OPERATING COVERS. LISTED RATED POKE-THROUGH FLOOR FITTINGS SHALL BE UL LISTED AND APPROVED FOR THE FLOOR SLAB FIRE RATING. FLOOR MOUNTED SERVICE FITTING FOR SERVICE FITTINGS FOR CONNECTION TO UNDER-FLOOR ELECTRIFIED METAL DECK SHALL BE COMPATIBLE WITH THE DECK MANUFACTURER. ACCESS FLOOR MOUNTED FITTINGS FOR USE WITH RAISED FLOOR SHALL BE FLUSH TYPE WITH SPACE FOR EQUIPMENT CORD PLUG DEVICES AND SUITABLE FLIP TYPE COVER. MANUFACTURER SHALL BE HUBBELL, WIREMOLD, OR STEEL CITY.

C. PROVIDE RACEWAYS ONLY AS HEREIN SPECIFIED, EXCEPT AS NOTED. RACEWAYS SHALL BE RUN CONCEALED, EXCEPT AS NOTED.

PROVIDE RACEWAY SUPPORT UTILIZING CEILING TRAPEZE, STRAP HANGERS, OR WALL BRACKETS. PROVIDE U-BOLTS AT EACH FLOOR LEVEL OF RISER RACEWAYS AND CONNECTED TO ACCEPTABLE SUPPORTS. PROVIDE RISER CLAMPS AT EACH FLOOR LEVEL OF RISER RACEWAYS AND RESTING ON SLAB. FOR THROUGH-THE-FLOOR SYSTEMS, UTILIZE AN ASSEMBLY SIMILAR TO HUBBELL FIRE RATED POKE-THROUGH-FLOOR BOX SYSTEM. FOR ABOVE FLOOR FITTINGS, TELEPHONE SHALL BE BUSHEMENT TYPE AND POWER SHALL BE DUPLEX RECEPTACLE. OTHER AS NOTED, PROVIDE SEPARATION BARRIER BETWEEN POWER AND TELEPHONE COMPARTMENTS. PROVIDE JUNCTION BOX ON UNDERSIDE OF FLOOR, PACK FITTING TO RESTORE FIRE RATING OF FLOOR.

SECURE ALL RACEWAYS TO SUPPORTS WITH PIPE STRAPS OR U-BOLTS. SPACING OF SUPPORTS SHALL BE A MINIMUM OF 10 FT ON CENTER FOR METALLIC RACEWAY AND AS REQUIRED FOR NONMETALLIC RACEWAY. SPACING SHALL BE 5 FT ON CENTER FOR WIREWAYS AND PER CODE AND AS NOTED FOR OTHERS. MOUNT SUPPORTS TO STRUCTURE MASONRY WITH TOGGLE BOLTS, OR HOLLOW MASONRY, EXPANSION SHIELDS OR INSERTS, OR CONCRETE AND CONCRETE BLOCKS WITH METAL BEAM CLAMPS ON FRAMEWORK. WOOD SCREWS ON WOOD, AND PAN THROUGH STRAPS IN METAL DECK. NAILS, RAWL PLUGS OR WOOD PLUGS SHALL NOT BE PERMITTED. WHERE REQUIRED BY STRUCTURE, FURNISH THROUGH BOLTS AND FISHPLATES.

EXPOSED RACEWAYS SHALL BE RUN PARALLEL WITH OR AT RIGHT ANGLES TO WALLS. PROVIDE CLEARANCE WITH WATER, STEAM OR OTHER PIPING (MINIMUM 3 IN. SEPARATION FROM STEAM AND HOT WATER PIPES, EXCEPT 1 IN. FROM PIPE COVER AT CROSSINGS AND 18 IN. FOR PARALLEL RUNS). FOR HUNG CEILING OUTLETS, RUN IN HUNG CEILING AND CONNECT TO CEILING SUPPORT CHANNELS. IN MASONRY AND Poured CONCRETE, RUN VERTICALLY ONLY.

Maintain GROUNDING CONTINUITY OF INTERRUPTED METALLIC RACEWAYS WITH GROUND CONDUCTOR, AND IN FLEXIBLE CONDUIT FOR FEEDERS AND MOTOR TERMINAL CONNECTIONS.

EMPTY RACEWAYS OVER 10 FT LONG: PROVIDE FISH OR PULL WIRE, GALVANIZED OR NYLON ROPE.

RIGID STEEL CONDUIT SHALL BE PERMITTED FOR FEEDERS AND BRANCH CIRCUITS. PAINT MALE THREADS OF FIELD-THREADED CONDUIT WITH GRAPHITE-BASE PIPE COMPOUND AND BUTT COUPLINGS. MALE THREADS OF FIELD-THREADED AND FEMALE THREADS, OR COLD GALVANIZED EMT SHALL BE PERMITTED FOR BRANCH CIRCUITS ONLY IN DRY LOCATIONS, DRY WALLS, HUNG CEILINGS, HOLLOW BLOCK WALLS AND FURRED SPACES. EMT SHALL NOT BE PERMITTED IN RAISED FLOORS.

FLEXIBLE STEEL CONDUIT SHALL BE UTILIZED FOR SHORT CONNECTIONS WHERE RIGID CONDUIT IS IMPRACTICAL. FROM OUTLET BOX TO RECESSED LIGHTING FIXTURES, PROVIDE MINIMUM 4 FT AND MAXIMUM 6 FT LENGTHS. FOR FINAL CONNECTION TO MOTOR TERMINAL BOX, TRANSFORMER AND OTHER VIBRATING EQUIPMENT: PROVIDE WITH POLYVINYL SHEATHING AND GROUND CONDUCTOR. MINIMUM LENGTH: 18 IN. WITH SLACK. CONNECT GROUND CONDUCTOR TO ENCLOSURE OR RACEWAY AT EACH END. FOR EXPANSION JOINT CROSSINGS, CROSS AT RIGHT ANGLES AND ANCHOR ENDS.

CUT CONDUIT ENDS SQUARE, REAM SMOOTH, PAINT MALE THREADS OF FIELD-THREADED RACEWAYS WITH GRAPHITE-BASE PIPE COMPOUND. DRAW UP TIGHT WITH RACEWAY COUPLING.

ALL COUPLINGS SHALL BE COMPRESSION TYPE. NO SET SCREW FITTINGS.

EXPANSION FITTINGS SHALL BE INSTALLED AT RIGHT ANGLES WITH CUP JOINT CENTERED IN EXPANSION JOINT. PROVIDE A LENGTH OF RUN IN ACCORDANCE MANUFACTURER'S RECOMMENDATIONS. PRESET FITTINGS SHALL ALLOW FOR TEMPERATURE VARIATION.

RACEWAYS PASSING THROUGH FIRE-RATED CONSTRUCTION: SEAL OPENING WITH FIRE SEALANT.

D. PROVIDE CABLE SUPPORTS IN ACCORDANCE WITH NATIONAL ELECTRIC CODE ARTICLE 300.19. CABLE SUPPORTS SHALL UTILIZE A ONE-PIECE PLUG WITH POZI-GRIP WEDGING PLUG AS MANUFACTURED BY OZ-GEDNEY. TYPE SF SHALL BE USED FOR ARMORED CABLE.

INSTALL CABLE SUPPORTS AT THE TOP OF A VERTICAL RISE AND PROVIDE INTERMEDIATE ADDITIONAL SUPPORTS AS REQUIRED TO LIMIT SUPPORTED CONDUCTOR LENGTHS TO NOT GREATER THAN THOSE SPECIFIED IN NEC TABLE 300.19(A).

E. ERECT WALL AND SWITCH OUTLETS IN ADVANCE OF FUllING AND FIREPROOFING. OUTLET BOXES SHALL BE SET SQUARE AND TRUE WITH BUILDING FINISH. SECURE TO BUILDING STRUCTURE BY ADJUSTABLE STRAP IRON OR GROUT IN WITH MASONRY. VERIFY OUTLET LOCATIONS IN FINISHED SPACES WITH ARCHITECTURAL DRAWINGS OF INTERIOR DETAILS AND FINISHES. PROVIDE BARRIERS BETWEEN SWITCHES CONNECTED TO DIFFERENT PHASES FOR VOLTAGES EXCEEDING 150 VOLTS TO GROUND.

A. PANEL JUNCTION AND PULL BOXES SHALL BE LOCATED CLEAR OF OTHER TRADES. CONCEAL JUNCTION AND PULL BOXES IN FINISHED SPACES, WHERE NECESSARY, REROUTE RACEWAYS OR MAKE OTHER ARRANGEMENTS FOR CONCEALMENT. BOXES SHALL BE ACCESSIBLE. SUPPORT BOXES FROM BUILDING STRUCTURE, INDEPENDENT OF CONDUIT. PROVIDE FLOOR-TO-CEILING CHANNELS FOR MOUNTING ON DRYWALL AND LIGHTWEIGHT CONSTRUCTION. OUTLET BOXES FOR FIXTURES RECESSED IN CEILING SHALL BE ACCESSIBLE THROUGH OPENING CREATED BY REMOVAL OF FIXTURE. SECURE TO BLACK IRON SUPPORT. MOTOR TERMINAL BOXES: COORDINATE WITH MOTOR BRANCH CIRCUIT CONDUIT AND WIRING; ADD BOX VOLUME WHERE REQUIRED.

B. FIRE SEALANTS: PROVIDE FOR RACEWAYS AND WIRE PASSING THROUGH FLOOR SLOTS, SLEEVES OR OPENINGS IN FIRE-PARTITION ROOMS.

C. PERFORM CONTINUITY TESTS OF RESISTANCE OF FEEDER CONDUITS FROM SERVICE TO POINT OF FINAL DISTRIBUTION USING 1 CONDUCTOR RETURN. MAXIMUM RESISTANCE SHALL BE 25 OHMS.

9. WIRE AND CABLE:

A. PROVIDE WIRE AND CABLE COMPLETE WITH ACCESSORIES. SIZE REFERENCE SHALL BE AWG EXCEPT AS NOTED.

B. CONDUCTORS SHALL BE COPPER, ASTM STANDARD SOLID (NO. 10 AND SMALLER) OR STRANDED (NO. 8 AND LARGER). GENERAL USE CABLING SHALL BE NO. 12 MINIMUM, AT 120 VOLTS AND OVER 100 FT CIRCUIT LENGTH PROVIDE NO. 10 MINIMUM. MANUFACTURER SHALL BE AMERICAN INSULATED WIRE CORP., CERRO, COLLYER, CAPITOL WIRE AND CABLE, OKONITE, SENETOR, SOUTHWIRE OR TRIANGLE.

C. CONTROL AND ALARM CABLING, EXCEPT AS NOTED, SHALL BE NO. 14 MINIMUM, AT 120 VOLTS AND OVER 200 FT CIRCUIT LENGTH. PROVIDE NO. 12 MINIMUM. OTHER VOLTAGES AND PHASES: ADJUST CABLE SIZING AS REQUIRED TO MAINTAIN VOLTAGE DROP. INCREASE RACEWAY SIZES FOR LARGER WIRE AS REQUIRED.

D. INSULATION SHALL BE RUBBER AND THERMOPLASTIC MEETING ASTM AND IPC-EA STANDARDS. TYPE THW OR THWN SHALL BE UTILIZED FOR FEEDERS AND BRANCH CIRCUITS EXCEPT AS NOTED. TYPE SPT-2 SHALL BE UTILIZED FOR BRANCH CIRCUITS LOCATED IN WALKING DISTANCE OF CONVENTIONAL INCORPORATED FIXTURES AND IN AMBIENT TEMPERATURES OVER 90 DEG C. FOR UNGROUNDED ISOLATED BRANCH CIRCUITS PROVIDE CROSS-LINKED POLYETHYLENE INSULATION (TYPE XHHW).

E. ARMORED CABLE (BX) SHALL BE UTILIZED FOR BRANCH CIRCUITS IN DRY HOLLOW LOCATIONS, HUNG CEILINGS, AND BLOCK WALLS. WHEN USED IN LIEU OF WIRING IN CONDUIT, STATE IN PROPOSAL THAT PRICE IS BASED UPON THE USE OF HOSPITAL GRADE 'BX'.

F. METAL-CLAD CABLE, NFPA 70 ARTICLE 330 TYPE MC:

- 1) INTERLOCKED FLEXIBLE GALVANIZED STEEL ARMOR SHEATH, CONFORMING TO UL REQUIREMENTS FOR TYPE MC METAL CLAD CABLE.
- 2) INSULATED COPPER CONDUCTORS, SUITABLE FOR 600 VOLTS, RATED 90C, ONE OF THE TYPES LISTED IN NFPA 70 TABLE 310.13(A) OR OF A TYPE IDENTIFIED FOR USE IN TYPE MC CABLE.
- 3) INTERNAL FULL SIZE COPPER GROUND CONDUCTOR WITH GREEN INSULATION.
- 4) ACCEPTABLE COMPANIES: AFC CABLE SYSTEMS INC., SOUTHWIRE, GENERAL CABLE.
- 5) CONNECTORS FOR MC CABLE: AFC FITTING INC.'S AFC SERIES, ARLINGTON INDUSTRIES INC.'S SADDLE GRIP, OR THOMAS & BETTS CO.'S TITE-BITE WITH ANTI-SHORT BUSHINGS.

G. COLOR CODING SHALL BE AS FOLLOWS:

- 120/208 VOLT SYSTEM:
BLACK FOR A PHASE
RED FOR B PHASE
BLUE FOR C PHASE
- 1) NEUTRAL WIRE SHALL UTILIZE WHITE OUTER COVERING THROUGHOUT. EQUIPMENT GROUND WIRE SHALL UTILIZE GREEN OUTER COVERING THROUGHOUT.

WHERE COLOR-CODED CABLE IS NOT AVAILABLE, CERTIFY IN WRITING AND REQUEST PERMISSION TO OVERLAP CONDUCTORS WITH 6 IN. OF COLOR TAPING IN ACCESSIBLE LOCATIONS.

H. PROVIDE FLAMEPROOF LINEN OR FIBER TAGS IN ACCESSIBLE LOCATIONS. FOR FEEDERS INDICATE FEEDER NUMBER, SIZE, PHASE AND POINTS OF ORIGIN AND TERMINATIONS. FOR CONTROL AND ALARM WIRING INDICATE TYPE (CONTROL OR ALARM), SIZE OF WIRE, AND POINTS OF ORIGIN AND TERMINATIONS.

I. TERMINATIONS, SPLICES AND TAPS UNDER 600 VOLTS: COPPER CONNECTORS NO. 10 AND SMALLER SHALL UTILIZE COMPRESSION-TYPE OF TWIST-ON SPRING-LOADED CONNECTORS, AND CLEAR NYLON-INSULATED COVERING. COPPER CONNECTORS NO. 8 AND LARGER SHALL UTILIZE MECHANICAL BOLTED, PRESSURE, OR HYDRAULIC COMPRESSION TYPE, USING MANUFACTURER'S RECOMMENDED TOOLING. CABLE LUGS AND CONNECTORS SHALL UTILIZE COMPRESSION-TYPE OF SAME METAL AS CONDUCTOR. PROVIDE TO MATCH CABLE, WITH MARKING INDICATING SIZE AND TYPE. COPPER LUG CONNECTIONS TO BUS BARS: USE ANTISEIZE COMPOUND ON TANG.

G. NOT MORE THAN 3 LIGHTING OR CONVENIENCE OUTLET CIRCUITS SHALL BE INSTALLED IN ONE CONDUIT UNLESS OTHERWISE INDICATED. PULL NO THERMOPLASTIC WIRES AT TEMPERATURES LOWER THAN 32 DEG F. PROVIDE SEPARATE RACEWAYS FOR CONDUCTORS OF 120/208 AND 265/460 VOLT SYSTEMS, EXCEPT 460 VOLT MOTOR BRANCH CIRCUIT WIRING, AND RELATED 120 VOLT CONTROL WIRING. THERMOPLASTIC WIRES SHALL NOT BE INSTALLED IN COMPUTER AREA RAISED FLOORS.

F. LEAVE WIRES WITH SUFFICIENT SLACK TO PERMIT MAKING FINAL CONNECTIONS.

G. PERFORM CONTINUITY AND INSULATION TESTS. MEGGER TEST 100 PERCENT OF FEEDERS, 10 PERCENT OF BRANCH CIRCUITS AND ALL MOTOR BRANCH CIRCUITS OVER 25 HP.

PERFORM TESTS PRIOR TO CONNECTING EQUIPMENT AND IN PRESENCE OF AUTHORIZED REPRESENTATIVES. SUBMIT WRITTEN REPORT OF RESULTS, CORRECT OR REPLACE CABLE TESTING BELOW MANUFACTURER'S STANDARDS.

10. WIRING DEVICES:

A. WIRING DEVICES SHALL BE SPECIFICATION GRADE UNLESS OTHERWISE SPECIFIED. ALL DEVICES SHALL BE FLUSH MOUNTED, UNLESS OTHERWISE NOTED. PROVIDE COMPLETE MATERIAL AND ACCESSORIES AS NOTED.

B. LOCAL WALL SWITCHES SHALL BE ROCKER TYPE, QUIET OPERATING, RATED 20 AMP, 120/277 VOLT, AC. SIMILAR TO LEVITON DECORA SERIES A5621 (SINGLE POLE), A5623 (3-WAY) AND A5624 (4-WAY).

C. STRAIGHT BLADE RECEPTACLES SHALL BE COMMERCIAL SPECIFICATION GRADE DUPLEX CONVENIENCE 125 VOLTS, 2 POLE, 3 WIRE, U GROUND SLOT, DECORA SERIES BY LEVITON. GROUNDED, EXCEPT AS NOTED.

1) SINGLE GANG, RECESSED, DUPLEX RECEPTACLE: TAMPER RESISTANT, 2-POLE, 3-WIRE GROUNDING, 15A, 125V, NEMA 5-20R; LEVITON 689 SERIES (COLOR AS SPECIFIED BY ARCHITECT).

D. INSERTION RECEPTACLES SHALL BE HOSPITAL GRADE DUPLEX CONVENIENCE 125 VOLTS, 2 POLE, 3 WIRE, U GROUND SLOT. GROUNDED, EXCEPT AS NOTED.

E. 2) HEALTH CARE FACILITIES:

- a) DUPLEX, 20 AMP, 125 VOLTS, 2 POLE, 3 WIRE, U GROUND SLOT: SIMILAR TO HUBBELL NO. 8300 HOSPITAL GRADE.
- b) SINGLE, 20 AMP, 125 VOLTS, 2 POLE, 3 WIRE, U GROUND SLOT: SIMILAR TO HUBBELL NO. 8310 HOSPITAL GRADE.

3) GROUND FAULT INTERRUPTER RECEPTACLES:

- a. 20 AMP DUPLEX FEED-THROUGH TYPE, SIMILAR TO NO. GF8300.

E. DEVICE PLATES: SEE ARCHITECT FOR TYPE. FOR RECEPTACLES WITH OTHER THAN 120 VOLT, INSCRIBED VOLTAGE AVAILABLE.

F. COLORS: COORDINATE COLORS WITH ARCHITECT.

G. MOUNTING ORIENTATION OF RECEPTACLES (HORIZONTAL OR VERTICAL): COORDINATE WITH ARCHITECT.

11. LIGHTING FIXTURES:

A. FIXTURES TO BE AS SPECIFIED BY ARCHITECT U.O.N. AND SHALL BE COMPLETELY FACTORY ASSEMBLED, WIRED AND EQUIPPED WITH ALL NECESSARY SOCKETS, BALLASTS, SUPPORTING HARDWARE AND ACCESSORIES. REFER TO DRAWINGS FOR INDIVIDUAL FIXTURE DESCRIPTIONS.

B. FIXTURE CATALOG NUMBERS USED TO ILLUSTRATE EQUIPMENT TYPE DO NOT NECESSARILY DENOTE REQUIRED MOUNTING EQUIPMENT OR ACCESSORIES. PROVIDE ACCESSORIES TO SUIT.

C. BALLAST: CLASS P, HIGH POWER FACTOR, LOWEST AVAILABLE NEMA RATED NOISE LEVEL, ET1 AND CBM APPROVED, ENERGY SAVING TYPE, TRIGGER START FOR 24-INCH LAMPS AND RAPID START FOR 48-INCH, TWO LAMP BALLASTS; NO THREE LAMP BALLASTS. BALLASTS SHALL BE ADVANCE MAGNETIC, UNIVERSAL OR EQUAL.

D. LED DRIVERS SHALL BE ELECTRONIC TYPE, LABELED AS COMPLIANT WITH RADIO FREQUENCY INTERFERENCE (RFI) REQUIREMENTS OF FCC TITLE 47, PART 15 AND COMPLY WITH NEMA SSL 1 "ELECTRONIC DRIVERS FOR LED DEVICES, ARRAYS OR SYSTEMS". LED DRIVERS SHALL HAVE A SOUND RATING OF "A", HAVE A MINIMUM EFFICIENCY OF 85% AND BE CAPABLE FOR A THD OF LESS THAN 20% AT ALL INPUT VOLTAGES.

E. DIMMABLE LED DRIVERS SHALL BE CAPABLE OF DIMMING WITHOUT LED STROBING OR FLICKER ACROSS THEIR FULL DIMMING RANGE. PROVIDE TYPE OF LED DRIVER AS PER LIGHTING FIXTURE SCHEDULE, DIMMABLE LED DRIVERS SHALL BE 0-10V WHERE NOT INDICATED.

F. FLUORESCENT LIGHTING FIXTURES, INCLUDING GENERAL CONSTRUCTION, LAMPS AND BALLASTS SHALL CONFORM TO THE ENERGY EFFICIENCY REQUIREMENTS OF CONSOLIDATED EDISON CO. AND QUALITY FOR A UTILITY REBATE TO OWNER UNDER CON EDISON'S ENLIGHTENED ENERGY LIGHTING REBATE PROGRAM. CONTRACTOR SHALL COORDINATE REBATE PROGRAM WITH CON EDISON AND ARRANGE FOR CON EDISON TO PERFORM A SURVEY TO INVENTORY ALL EXISTING FIXTURES PRIOR TO DEMOLITION.

G. EXIT SIGNS SHALL BE PRECISION DIE-CAST ALUMINUM HOUSING WITH LASER-FORMED ACRYLIC LEGEND. EXIT SIGNS SHALL COMPLY WITH UL 924 AND BE MEA APPROVED FOR USE IN THE CITY. AC POWERED WITH PREMIUM LONG-LIFE NICKEL CADMIUM BATTERY WITH STANDARD UL LISTED 3-HOUR RUN TIME. PROVIDE WITH INTEGRAL AUTOMATIC CHARGER IN A SELF CONTAINED POWER PACK. LED INDICATOR WITH PUSH TO TEST SWITCH.

12. GROUNDING AND BONDING:

A. PROVIDE GROUNDING SYSTEM IN ACCORDANCE WITH 2011 NATIONAL ELECTRICAL CODE WITH NYC AMENDMENTS, AND THESE SPECIFICATIONS. THE WIRING SYSTEM SHALL BE INSTALLED AS REQUIRED TO PROVIDE A CONTINUOUSLY GROUNDED SYSTEM.

B. USE EXOTHERMIC WELDING PROCESS FOR INACCESSIBLE CONNECTIONS.

C. EXTEND EXISTING SYSTEM GROUND TO INCLUDE ALL THE ELECTRICAL EQUIPMENT IN THE SCOPE OF WORK.

D. WHERE FLEXIBLE METALLIC CONDUIT IS USED AN INTERNAL BONDING CONDUCTOR SHALL BE INSTALLED.

E. IN ADDITION, FURNISH A SEPARATE INSULATED GREEN EQUIPMENT GROUND CONDUCTOR WHERE INDICATED ON DRAWINGS AND FOR THE FOLLOWING BRANCH CIRCUITS:

- 1) CIRCUITS SERVING ANY WALL BOX DIMMER.
- 2) CIRCUITS SERVING ANY ISOLATED GROUND RECEPTACLES. TERMINATE GROUND DIRECTLY AT AN EQUIPMENT GROUNDING CONDUCTOR TERMINAL OF THE SOURCE AT THE SOURCE, OR AS OTHER WISE NOTED ON DRAWINGS.
- 3) CIRCUITS SERVING ANY DUPLEX OR SIMPLEX COMPUTER RECEPTEACES
- 4) ANY CIRCUIT SERVED VIA AN ISOLATION TRANSFORMER OR COMPUTER POWER DISTRIBUTION UNIT.

13. INTERCOM CONDUIT SYSTEM:

A. PROVIDE COMPLETE SYSTEM OF: RACEWAYS AND ACCESSORIES, J-BOXES, SLEEVES AND FISHWIRES.

B. EQUIPMENT SHALL CONFORM TO REQUIREMENTS OF INTERCOM MANUFACTURER.

C. J-BOXES SHALL BE:

- 1) WALL: 4 IN. SQUARE WITH SINGLE GANG COVER PLATE.

D. PROVIDE FISHWIRES, IN RACEWAYS OVER 10 FT LONG.

E. CONDUIT SHALL BE 3/4 IN. MINIMUM. FURNISH EMPTY CONDUIT FROM EACH APARTMENT TO MAIN INTERCOM CONTROLLER AT ENTRANCE.

GROUND SLOT, DECORA SERIES BY LEVITON. GROUNDED, EXCEPT AS NOTED.

1) SINGLE GANG, RECESSED, DUPLEX RECEPTACLE: TAMPER RESISTANT, 2-POLE, 3-WIRE GROUNDING, 15A, 125V, NEMA 5-20R; LEVITON 689 SERIES (COLOR AS SPECIFIED BY ARCHITECT).

D. INSERTION RECEPTACLES SHALL BE HOSPITAL GRADE DUPLEX CONVENIENCE 125 VOLTS, 2 POLE, 3 WIRE, U GROUND SLOT. GROUNDED, EXCEPT AS NOTED.

E. 2) HEALTH CARE FACILITIES:

a) DUPLEX, 20 AMP, 125 VOLTS, 2 POLE, 3 WIRE, U GROUND SLOT: SIMILAR TO HUBBELL NO. 8300 HOSPITAL GRADE.

b) SINGLE, 20 AMP, 125 VOLTS, 2 POLE, 3 WIRE, U GROUND SLOT: SIMILAR TO HUBBELL NO. 8310 HOSPITAL GRADE.

3) GROUND FAULT INTERRUPTER RECEPTACLES:

a. 20 AMP DUPLEX FEED-THROUGH TYPE, SIMILAR TO NO. GF8300.

E. DEVICE PLATES: SEE ARCHITECT FOR TYPE. FOR RECEPTACLES WITH OTHER THAN 120 VOLT, INSCRIBED VOLTAGE AVAILABLE.

F. COLORS: COORDINATE COLORS WITH ARCHITECT.

G. MOUNTING ORIENTATION OF RECEPTACLES (HORIZONTAL OR VERTICAL): COORDINATE WITH ARCHITECT.

11. LIGHTING FIXTURES:

A. FIXTURES TO BE AS SPECIFIED BY ARCHITECT U.O.N. AND SHALL BE COMPLETELY FACTORY ASSEMBLED, WIRED AND EQUIPPED WITH ALL NECESSARY SOCKETS, BALLASTS, SUPPORTING HARDWARE AND ACCESSORIES. REFER TO DRAWINGS FOR INDIVIDUAL FIXTURE DESCRIPTIONS.

B. FIXTURE CATALOG NUMBERS USED TO ILLUSTRATE EQUIPMENT TYPE DO NOT NECESSARILY DENOTE REQUIRED MOUNTING EQUIPMENT OR ACCESSORIES. PROVIDE ACCESSORIES TO SUIT.

C. BALLAST: CLASS P, HIGH POWER FACTOR, LOWEST AVAILABLE NEMA RATED NOISE LEVEL, ET1 AND CBM APPROVED, ENERGY SAVING TYPE, TRIGGER START FOR 24-INCH LAMPS AND RAPID START FOR 48-INCH, TWO LAMP BALLASTS; NO THREE LAMP BALLASTS. BALLASTS SHALL BE ADVANCE MAGNETIC, UNIVERSAL OR EQUAL.

D. LED DRIVERS SHALL BE ELECTRONIC TYPE, LABELED AS COMPLIANT WITH RADIO FREQUENCY INTERFERENCE (RFI) REQUIREMENTS OF FCC TITLE 47, PART 15 AND COMPLY WITH NEMA SSL 1 "ELECTRONIC DRIVERS FOR LED DEVICES, ARRAYS OR SYSTEMS". LED DRIVERS SHALL HAVE A SOUND RATING OF "A", HAVE A MINIMUM EFFICIENCY OF 85% AND BE CAPABLE FOR A THD OF LESS THAN 20% AT ALL INPUT VOLTAGES.

E. DIMMABLE LED DRIVERS SHALL BE CAPABLE OF DIMMING WITHOUT LED STROBING OR FLICKER ACROSS THEIR FULL DIMMING RANGE. PROVIDE TYPE OF LED DRIVER AS PER LIGHTING FIXTURE SCHEDULE, DIMMABLE LED DRIVERS SHALL BE 0-10V WHERE NOT INDICATED.

F. FLUORESCENT LIGHTING FIXTURES, INCLUDING GENERAL CONSTRUCTION, LAMPS AND BALLASTS SHALL CONFORM TO THE ENERGY EFFICIENCY REQUIREMENTS OF CONSOLIDATED EDISON CO. AND QUALITY FOR A UTILITY REBATE TO OWNER UNDER CON EDISON'S ENLIGHTENED ENERGY LIGHTING REBATE PROGRAM. CONTRACTOR SHALL COORDINATE REBATE PROGRAM WITH CON EDISON AND ARRANGE FOR CON EDISON TO PERFORM A SURVEY TO INVENTORY ALL EXISTING FIXTURES PRIOR TO DEMOLITION.

G. EXIT SIGNS SHALL BE PRECISION DIE-CAST ALUMINUM HOUSING WITH LASER-FORMED ACRYLIC LEGEND. EXIT SIGNS SHALL COMPLY WITH UL 924 AND BE MEA APPROVED FOR USE IN THE CITY. AC POWERED WITH PREMIUM LONG-LIFE NICKEL CADMIUM BATTERY WITH STANDARD UL LISTED 3-HOUR RUN TIME. PROVIDE WITH INTEGRAL AUTOMATIC CHARGER IN A SELF CONTAINED POWER PACK. LED INDICATOR WITH PUSH TO TEST SWITCH.

12. GROUNDING AND BONDING:

A. PROVIDE GROUNDING SYSTEM IN ACCORDANCE WITH 2011 NATIONAL ELECTRICAL CODE WITH NYC AMENDMENTS, AND THESE SPECIFICATIONS. THE WIRING SYSTEM SHALL BE INSTALLED AS REQUIRED TO PROVIDE A CONTINUOUSLY GROUNDED SYSTEM.

B. USE EXOTHERMIC WELDING PROCESS FOR INACCESSIBLE CONNECTIONS.

C. EXTEND EXISTING SYSTEM GROUND TO INCLUDE ALL THE ELECTRICAL EQUIPMENT IN THE SCOPE OF WORK.

D. WHERE FLEXIBLE METALLIC CONDUIT IS USED AN INTERNAL BONDING CONDUCTOR SHALL BE INSTALLED.

E. IN ADDITION, FURNISH A SEPARATE INSULATED GREEN EQUIPMENT GROUND CONDUCTOR WHERE INDICATED ON DRAWINGS AND FOR THE FOLLOWING BRANCH CIRCUITS:

1) CIRCUITS SERVING ANY WALL BOX DIMMER.


2) CIRCUITS SERVING ANY ISOLATED GROUND RECEPTACLES. TERMINATE GROUND DIRECTLY AT AN EQUIPMENT GROUNDING CONDUCTOR TERMINAL OF THE SOURCE AT THE SOURCE, OR AS OTHER WISE NOTED ON DRAWINGS.

3) CIRCUITS SERVING ANY DUPLEX OR SIMPLEX COMPUTER RECEPTEACES

4) ANY CIRCUIT SERVED VIA AN ISOLATION TRANSFORMER OR COMPUTER POWER DISTRIBUTION UNIT.

13. INTERCOM CONDUIT SYSTEM:

3 BULLETIN 3	02/25/25
PERMIT SET	01/30/25
90% PROGRESS	01/24/25

ROOTS NATURAL
KITCHEN

3	BULLETIN 3	02/25/25
	PERMIT SET	01/30/25
	90% PROGRESS	01/24/25


ELECTRICAL POWER PLAN GENERAL NOTES :	
1.	E.C. SHALL COORDINATE WITH ARCHITECT/OWNER FOR EXACT LOCATION OF EXISTING METER, CT CABINET & DISCONNECT IN THE FIELD.
2.	E.C. SHALL COORDINATE WITH THE ARCHITECT/OWNER FOR THE EXACT LOCATION OF THE EXISTING ELECTRICAL PANEL IN THE FIELD. ALSO, ENSURE CLEAR WORKING AND DEDICATED SPACE HAVE BEEN PROVIDED AS PER NEC 110.26.
3.	E.C. SHALL COORDINATE WITH ARCHITECT/EQUIPMENT VENDOR FOR EXACT CONNECTION TYPE, POWER REQUIREMENT & LOCATION OF EQUIPMENT IN THE FIELD. PROVIDE ACCORDINGLY AS REQUIRED.
4.	WALK-IN UNIT LIGHTING ARE FACTORY PRE-WIRED TO THE LIGHT SWITCH. CONDUCTOR SHALL PROVIDE RACEWAY AND CONDUCTORS FROM J-BOX DOWN THROUGH TOP OF BOX TO LIGHT WITH J-BOX INSIDE COMPARTMENT. PROVIDE WATERTIGHT SEAL FOR ALL PENETRATIONS THROUGH TOP OF WALK-IN-BOX. SEAL ALL RACEWAYS AIRTIGHT WITHIN 6" OF WALK-IN.
5.	E.C. SHALL COORDINATE WITH THE MECHANICAL CONTRACTOR FOR THE EXACT LOCATION AND ELECTRICAL CONNECTION REQUIREMENT OF THE HVAC UNIT IN THE FIELD. PROVIDE CIRCUIT AND CONTROLS AS REQUIRED.
6.	E.C. SHALL COORDINATE WITH THE PLUMBING CONTRACTOR FOR THE EXACT LOCATION AND ELECTRICAL CONNECTION REQUIREMENT OF THE UNIT IN THE FIELD. PROVIDE CIRCUIT AND CONTROL AS REQUIRED.
7.	E.C. TO WIRE DROP-CORD FROM JUNCTION BOX AT CEILING TO DUPLEX WITH TWIST-LOCK AT 48" AFF.
8.	THE EXHAUST FAN IN THE ROOM SHALL BE CIRCUITED AND CONTROLLED ALONG WITH THE LIGHTING FIXTURES IN THE SAME ROOM.
9.	PLYWOOD-BACKED OUTLETS FOR DATA AND TELEPHONE SERVICES. COORDINATE WITH THE ARCHITECT/OWNER/SERVICE PROVIDER FOR OTHER REQUIREMENTS. PROVIDE CONDUIT AND CONNECTION AS REQUIRED.
10.	THE ELECTRICAL EQUIPMENT UNDER THE HOOD SHALL BE PROVIDED WITH THE SHUNT TRIP BREAKERS AND FIRED EQUIPMENT SHALL HAVE A GAS SHUT-OFF (SOLENOID) VALVE TO DISCONNECT THE COOKING EQUIPMENT WHEN THE FIRE SUPPRESSION SYSTEM IS ACTIVATED. E.C. TO PROVIDE COMPLETE ELECTRICAL CONNECTION AND ENSURE THE PROPER WORKING OF THE FIRE SUPPRESSION SYSTEM.

ELECTRICAL POWER PLAN KEY NOTES: #	
1.	E.C. SHALL COORDINATE WITH ARCHITECT/OWNER FOR EXACT LOCATION OF EXISTING METER, CT CABINET & DISCONNECT IN THE FIELD.
2.	E.C. SHALL COORDINATE WITH THE ARCHITECT/OWNER FOR THE EXACT LOCATION OF THE EXISTING ELECTRICAL PANEL IN THE FIELD. ALSO, ENSURE CLEAR WORKING AND DEDICATED SPACE HAVE BEEN PROVIDED AS PER NEC 110.26.
3.	E.C. SHALL COORDINATE WITH ARCHITECT/EQUIPMENT VENDOR FOR EXACT CONNECTION TYPE, POWER REQUIREMENT & LOCATION OF EQUIPMENT IN THE FIELD. PROVIDE ACCORDINGLY AS REQUIRED.
4.	WALK-IN UNIT LIGHTING ARE FACTORY PRE-WIRED TO THE LIGHT SWITCH. CONDUCTOR SHALL PROVIDE RACEWAY AND CONDUCTORS FROM J-BOX DOWN THROUGH TOP OF BOX TO LIGHT WITH J-BOX INSIDE COMPARTMENT. PROVIDE WATERTIGHT SEAL FOR ALL PENETRATIONS THROUGH TOP OF WALK-IN-BOX. SEAL ALL RACEWAYS AIRTIGHT WITHIN 6" OF WALK-IN.
5.	E.C. SHALL COORDINATE WITH THE MECHANICAL CONTRACTOR FOR THE EXACT LOCATION AND ELECTRICAL CONNECTION REQUIREMENT OF THE HVAC UNIT IN THE FIELD. PROVIDE CIRCUIT AND CONTROLS AS REQUIRED.
6.	E.C. SHALL COORDINATE WITH THE PLUMBING CONTRACTOR FOR THE EXACT LOCATION AND ELECTRICAL CONNECTION REQUIREMENT OF THE UNIT IN THE FIELD. PROVIDE CIRCUIT AND CONTROL AS REQUIRED.
7.	E.C. TO WIRE DROP-CORD FROM JUNCTION BOX AT CEILING TO DUPLEX WITH TWIST-LOCK AT 48" AFF.
8.	THE EXHAUST FAN IN THE ROOM SHALL BE CIRCUITED AND CONTROLLED ALONG WITH THE LIGHTING FIXTURES IN THE SAME ROOM.
9.	PLYWOOD-BACKED OUTLETS FOR DATA AND TELEPHONE SERVICES. COORDINATE WITH THE ARCHITECT/OWNER/SERVICE PROVIDER FOR OTHER REQUIREMENTS. PROVIDE CONDUIT AND CONNECTION AS REQUIRED.
10.	THE ELECTRICAL EQUIPMENT UNDER THE HOOD SHALL BE PROVIDED WITH THE SHUNT TRIP BREAKERS AND FIRED EQUIPMENT SHALL HAVE A GAS SHUT-OFF (SOLENOID) VALVE TO DISCONNECT THE COOKING EQUIPMENT WHEN THE FIRE SUPPRESSION SYSTEM IS ACTIVATED. E.C. TO PROVIDE COMPLETE ELECTRICAL CONNECTION AND ENSURE THE PROPER WORKING OF THE FIRE SUPPRESSION SYSTEM.

EQUIPMENT SCHEDULE GENERAL NOTES :	
A.	FOR EQUIPMENT RATED FOR OTHER THAN THE SERVICE VOLTAGE, THE CONTRACTOR SHALL EITHER PROVIDE EQUIVALENT EQUIPMENT AT SERVICE VOLTAGE (IN COORDINATION WITH OWNER/ARCHITECT) OR PROVIDE AN ADAPTER/TRANSFORMER FOR THAT EQUIPMENT.
B.	VERIFY ALL MCA, MOCP, CONNECTION TYPE, AND OTHER INSTALLATION REQUIREMENTS WITH FOOD SERVICE CONSULTANT AND EQUIPMENT MANUFACTURER BEFORE BID.
C.	LOCATIONS OF DISCONNECTS FOR EACH PIECE OF EQUIPMENT MAY NOT BE SHOWN ON PLANS. IF DISCONNECT FOR EQUIPMENT IS NOT SHOWN, THE CONTRACTOR TO FIELD COORDINATE LOCATION PER CODE.
D.	FUSED DISCONNECTS SHALL HAVE FUSES SIZED AS LISTED ON THE EQUIPMENT NAMEPLATE, OTHERWISE MATCH THE UPSTREAM OVER CURRENT DEVICE IF NO MAXIMUM OVER-CURRENT SIZE IS LISTED ON THE EQUIPMENT, UNLESS NOTED OTHERWISE.
E.	THE CONTRACTOR IS RESPONSIBLE FOR FURNISHING AND INSTALLING ALL CONDUITS, WIRE, SUPPORT SYSTEM, DISCONNECTS, AND OUTLETS TO ALLOW FOR A COMPLETE CODE-COMPLIANT KITCHEN INSTALLATION.

ELECTRICAL EQUIPMENT SCHEDULE												
TAG	QTY	EQUIPMENT DESCRIPTION	MAKE	MODEL	LOAD IN VA	VOLTS	PHASE	AMPS	BREAKER	CONNECTION	DATA/TEL	NOTES
1	1	REFRIGERATED SELF-SERVICE COUNTER CASE	OASIS	C33R-UC	965	110-120	1	10.85	20A/1P	NEMAS-15P	-	-
3	1	DROP IN HOT FOOD WELL	WELLS	-	2400	208	1	11.54	20A/2P	-	-	1,2,3
4	1	DROP IN COLD FOOD WELL	DELFIELD	8145-EFP	444	115	1	3.7	20A/1P	NEMAS-15P	-	-
5	1	DROP IN COLD FOOD WELL	DELFIELD	8145-EFP	444	115	1	3.7	20A/1P	NEMAS-15P	-	-
6	1	DROP IN HOT FOOD WELL	WELLS	-	1650	120	1	13.75	20A/1P	-	-	1,2,3
8	1	REFRIGERATED MERCHANDISER	STRUCTURAL CONCEPTS	B67R	3328	208-240V	1	16	20A/2P	NEMAS-20P	-	-
9	1	REACH IN REFRIGERATOR W/ GLASS DOORS	ATOSA USA	MCF8709GR	504	120	1	4.2	20A/1P	NEMAS-15P	-	-
10	2	RICE COOKER	TOWN	57155	3330	230	1	15	20A/2P	NEMAS-20P	-	2,3,6
11	2	DRAWER WARMER	HATCO	HDW-2N	890	208	1	4.3	15A/2P	NEMAS-15P	-	2,3
15	1	WORK TABLE	JOHN BOOS	-	1800	120	1	15	20A/1P	NEMAS-20R	-	-
15.1	1	WORK TABLE	JOHN BOOS	-	1800	120	1	15	20A/1P	NEMAS-20R	-	-
17	1	GRIDDLE	SOUTHBEND (MIDDLEBY)	HDG-72	-	-	-	-	-	-	-	3,4,5
17.1	1	REFRIGERATED EQUIPMENT STAND	ATOSA USA	MGF8458GR	276	115	1	2.3	20A/1P	NEMAS-15P	-	-
18	1	REACH-IN REFRIGERATOR	ATOSA USA	MBF8005GR	384	115	1	3.2	20A/1P	NEMAS-15P	-	-
19	2	HOT FOOD WELL	IEI	-	1650	120	1	13.75	20A/1P	-	-	1,2,5
21	2	REFRIGERATED SANDWICH/SALAD PREP TABLE	TRAULSEN	CLPT-7230-DW	312	115	1	2.6	20A/1P	NEMAS-15P	-	-
23	2	HOT FOOD WELL	IEI	-	1650	120	1	13.75	20A/1P	J.B VERIFY	-	1,2,5
27	1	DISHWASHER- ELECTRIC HEAT	HOBERT	AM16T-BAS-2	9690	208-240	3	26.9	30/3P	VERIFY	-	3,5
27	1	DISHWASHER- BOOSTER CONTROL	HOBERT	AM16T-BAS-2	9220	208-240	3	25.6	30/3P	VERIFY	-	3,5
34.2	1	FIRE SUPPRESSION SYSTEM	-	-	-	-	-	-	-	-	-	1,2,3,5
35	1	CONVECTION OVEN	SOUTHBEND (MIDDLEBY)	PCE155/SD	7500	208	3	20.82	30/3P	-	-	2,3,5
36	1	WORK TABLE	JOHN BOOS	-	1800	120	1	15	20A/1P	NEMAS-20R	-	-
36.1	2	WORK TABLE	JOHN BOOS	-	1800	120	1	15	20A/1P	NEMAS-20R	-	-
37	1	WALK-IN-COOLER	THERM	-	1800	120	1	15	20A/1P	-	-	1,2,3,5
37.1	1	WALK-IN-COOLER EVAPORATOR COIL	THERM	-	220	120	1	1.8	20A/1P	-	-	1,2,3,5
37.2	1	WALK-IN-COOLER CONDENSING UNIT	THERM	-	3120	208	1	15	20A/2P	-	-	1,2,3,5
43	1	ICE & WATER DISPENSER	MANITOWOC	CNF0201A	1184.5	115	1	10.3	20A/1P	NEMAS-15P	-	-
44	2	BEVERAGE DISPENSER	GRINDMASTER-UNIC-CRATHCO	E49-3	720	115	1	6	20A/1P	NEMAS-15P	-	-
46	1	HEATED CABINET	FEW	UHS-4	1300	120	1	10.8	20A/1P	NEMAS-15P	-	-
50	2	POS SYSTEM	-	-	0.72	120	1	6	-	-	YES	2,3,5

1. COORDINATE EXACT MAKE/MODEL NUMBER WITH THE OWNER/ARCHITECT.
2. COORDINATE EXACT POWER REQUIREMENT WITH THE EQUIPMENT VENDOR.
3. COORDINATE EXACT CONNECTION TYPE WITH THE VENDOR PRIOR TO ROUGH IN.
4. GAS FIRED EQUIPMENT, COORDINATE WITH PLUMBING.
5. PROVIDE CIRCUIT BREAKER, WIRING, JUNCTION BOX, RECEPTACLES, DISCONNECTS AS REQUIRED.
6. SELECT EQUIPMENT RATED FOR SERVICE VOLTAGE ELSE PROVIDE THE ADAPTER/TRANSFORMER AS NEEDED.



ELECTRICAL ROOF POWER PLAN GENERAL NOTES :	
A. ALL THE ELECTRICAL ELEMENT VIZ. CONDUITS, WIRING, AND DISCONNECT SWITCHES SHALL BE RATED FOR THE EXTERIOR USE.	
B. THE DISCONNECT SWITCHES FOR THE BRANCH CIRCUIT SHOWN ON THE PLAN SHALL BE RATED EQUAL TO OR HIGHER THAN THE BREAKER RATING. REFER BREAKER RATING IN THE PANEL SCHEDULE AND PROVIDE DISCONNECT AS NEEDED.	
C. GFI MARKED ON THE PLAN INDICATES THAT THE CIRCUIT SHALL BE GFI PROTECTED. E.C. SHALL PROVIDE A GFI BREAKER IN THE PANEL FOR THE INDICATED CIRCUIT IF EITHER THE RECEPTACLE IS NOT AVAILABLE OR NOT ACCESSIBLE.	
D. A 125-VOLT, SINGLE-PHASE, 15- OR 20-AMPERE-RATED RECEPTACLE OUTLET SHALL BE INSTALLED AT AN ACCESSIBLE LOCATION WITHIN 7.5 M (25 FT) OF THE EQUIPMENT AS SPECIFIED IN 210.63(A) AND (B) AS PER NEC 210.63.	

ELECTRICAL ROOF PLAN KEY NOTES: #	
1. E.C. SHALL COORDINATE WITH THE MECHANICAL CONTRACTOR FOR THE EXACT LOCATION AND ELECTRICAL CONNECTION REQUIREMENT OF THE HVAC UNIT IN THE FIELD. PROVIDE CIRCUIT AND CONTROLS AS REQUIRED.	


DRAWN NYE
CHECKED NYE
PROJECT NO. 240720

3	BULLETIN 3	02/25/25
	PERMIT SET	01/30/25
	90% PROGRESS	01/24/25

ROOTS NATURAL KITCHEN

ELECTRICAL ROOF POWER PLAN

E2.1






3	BULLETIN 3	02/25/25
	PERMIT SET	01/30/25
	90% PROGRESS	01/24/25

ROOTS NATURAL KITCHEN

ELECTRICAL DETAILS

E3.0



3	BULLETIN 3	02/25/25
	PERMIT SET	01/30/25
	90% PROGRESS	01/24/25

ROOTS NATURAL KITCHEN

ELECTRICAL RISER DIAGRAM & PANEL SCHEDULE

E4.0

ELECTRICAL RISER DIAGRAM

RISER DIAGRAM SYMBOLS

- NEW
- EXISTING ITEM/FEEDER TO REMAIN
- X EXISTING ITEM/FEEDER TO BE REMOVE & DO=ISCONNECTED

ELECTRICAL RISER DIAGRAM GENERAL NOTES :

A. E.C. SHALL VERIFY/COORDINATE THE FOLLOWING INFORMATION IN THE FIELD WITH THE UTILITY/LANDLORD/OWNER AND INFORM THE ENGINEER OF RECORD OF ANY DISCREPANCY BEFORE BID.

B. THE ELECTRICAL WORK SHALL BE PERFORMED IN COMPLIANCE WITH THE NEC, LOCAL CODES AND AHJ.

C. THE EXACT POWER DISTRIBUTION AND SCOPE OF WORK WITH THE LANDLORD/OWNER BEFORE BID.

D. COORDINATE AVAILABLE FAULT CURRENT WITH UTILITY/LANDLORD/OWNER. CALCULATE THE EXACT AIC RATING OF EACH EQUIPMENT IN THE FIELD. PROVIDE THE EQUIPMENT ACCORDINGLY. AIC RATING SHALL BE WRITTEN ON EACH EQUIPMENT PER STANDARD.

E. ENSURE THE COMBINED VOLTAGE DROP OF THE FEEDER AND BRANCH CIRCUIT SHALL NOT EXCEED 5% PER CODE.

F. ADDITION OR ALTERATION TO THE EXISTING SYSTEM SHALL NOT BE DONE WITHOUT THE WRITTEN CONSENT OF THE OWNER.

G. THE PART OF RISER MARKED AS EXISTING IS FOR REFERENCE PURPOSE ONLY. E.C. SHALL VERIFY THE EXACT POWER DISTRIBUTION (INCLUDING RISER) IN THE FIELD. INFORM THE ENGINEER OF THE RECORD OF ANY DISCREPANCY FOUND.

H. SPARE AMPS AVAILABLE IN THE EXISTING ELECTRICAL SERVICE SHALL BE MORE THAN THE NEWLY ADDED DEMAND AMPS.

I. VERIFY THE LOCATION, RATING, AND OPERABLE CONDITION OF ALL THE EXISTING DEVICES INTENDED TO BE REUSED. REPLACE IF FOUND INOPERABLE (WITHIN THE SCOPE OF WORK). BASE BID ACCORDINGLY.

J. REUSE OF THE EXISTING EQUIPMENT IS SUBJECT TO THE VERIFICATION OF THE AVAILABILITY, LOCATION, RATING, OPERABLE CONDITION AND FAULT CURRENT IN THE FIELD. REPLACE THE EXISTING EQUIPMENT WITH A NEW ONE IF THE EXISTING EQUIPMENT CAN NOT BE REUSED DUE TO ANY OF THE REASONS MENTIONED EARLIER.

ELECTRICAL PANEL SCHEDULES GENERAL NOTES :

A. CONTRACTOR SHALL VERIFY BREAKER AND BRANCH CIRCUIT REQUIREMENTS FOR THE EQUIPMENT IN THE FIELD.

B. THE ELECTRICAL LOAD IS BALANCED WITHIN 10% FOR ALL 3 PHASES.

C. THE VOLTAGE DROP FOR THE BRANCH CIRCUIT SHALL NOT EXCEED 3% OR 5% IN COMBINATION WITH THE FEEDER CIRCUIT.

D. GFI MARKED ON THE PLAN INDICATES THAT THE CIRCUIT SHALL BE GFI PROTECTED. E.C. SHALL PROVIDE A GFCI BREAKER IN THE PANEL FOR THE INDICATED CIRCUIT IF EITHER THE RECEPTACLE IS NOT AVAILABLE OR NOT READILY ACCESSIBLE.

E. COORDINATE AVAILABLE FAULT CURRENT (AIC RATING) WITH UTILITY/LANDLORD/OWNER. CALCULATE THE EXACT AIC RATING OF EACH PANEL IN THE FIELD. AIC RATING SHALL BE WRITTEN ON EACH PANEL AS PER STANDARD.

F. PROVIDE BREAKER LOCKING DEVICES IN THE PANELS, WHERE EVER REQUIRED BY CODE. INCLUDING BUT NOT LIMITED TO EMERGENCY LIGHTING, FIRE ALARM CIRCUITS, AND HARD-WIRED EQUIPMENT.

G. THE CONTRACTOR SHALL MODIFY THE BREAKERS OF THE EXISTING PANEL (WHEREVER REQUIRED) TO BE IN LINE WITH THE PANEL SCHEDULE.

H. REPLACE THE EXISTING OR PROVIDE A NEW BREAKER IF THE EXISTING IS INOPERABLE.


I. THE CONTRACTOR IS TO PROVIDE A CIRCUIT DIRECTORY FOR EACH PANEL BOARD.

ELECTRICAL PANEL SCHEDULE

PANEL	MDP	(EXISTING)	PHASE	3	WIRE	4	DEMAND LOAD IN KVA	128.70	DEMAND CURRENT IN AMPS	357.66	MOUNTING:	SURFACE
208Y/120 VOLTS	600A	MCB									PANEL LOCATION:	BACK OF HOUSE
											FED FROM:	ELECT.METER/DISC
ELECTRICAL PANEL SCHEDULE												
CKT NO.	TRIP AMPS	DESCRIPTION OF LOAD	LOAD TYPE	LOAD (KVA)	NOTES	PER PHASE (KVA)	NOTES	LOAD (KVA)	LOAD TYPE	DESCRIPTION OF LOAD	TRIP AMPS	CKT NO.
1	200/3P	TO PANEL-B		O 11.31		12.87		E 1.56		EQ37.2_WALK-IN-COOLER	20/2P	2
3				O 11.31		12.87		E 1.56		CONDENSING UNIT		4
5				O 11.31		23.48						6
7	15/3P	KEF-2(N)		M 0.24		12.41						8
9				M 0.24		3.36						10
11				M 0.24		3.36						12
13				E 2.50		5.62						14
15	30/3P	EQ35_CONVECTION OVEN		E 2.50		2.95						16
17				E 2.50		2.95						18
19		SHUNT TRIP				0.00						20
21		SPACE				3.23						22
23		SHUNT TRIP				3.23						24
25	30/3P	EQ27_DISHWASHER- BOOSTER CONTROL		E 3.07		6.30						26
27				E 3.07		4.32						28
29				E 3.07		4.32						30
31				E 2.50		3.50						32
33	30/3P	EQ35_CONVECTION OVEN		E 2.50		3.50						34
35				E 2.50		3.50						36
37		SHUNT TRIP				4.68						38
39	15/2P	ACCU-2(N), AC-2(N)		H 1.25		5.93						40
41				H 1.25		5.93						42
43				M 0.31		4.03						44
45	15/3P	KEF-1(N)		M 0.31		4.03						46
47				M 0.31		4.03						48
						49.41		40.19		50.80		

PANEL	B	(EXISTING)	PHASE	3	WIRE	4	DEMAND LOAD IN KVA	33.92	DEMAND CURRENT IN AMPS	94.26	MOUNTING:	RECESSED	
208Y/120 VOLTS	200A	MLO									PANEL LOCATION:	BACK OF HOUSE	
											FED FROM:	MDP	
ELECTRICAL PANEL SCHEDULE													
CKT NO.	TRIP AMPS	DESCRIPTION OF LOAD	LOAD TYPE	LOAD (KVA)	NOTES	PER PHASE (KVA)	NOTES	LOAD (KVA)	LOAD TYPE	DESCRIPTION OF LOAD	TRIP AMPS	CKT NO.	
1	20/1P	INTERIOR LIGHTING DINNING	R	0.60	3	2.25		RWC	1.65	E	EQ19_HOT FOOD WELL	20/1P	2
3	20/1P	EXTERIOR LIGHTING	L	0.25		1.90		RWC	1.65	E	EQ19_HOT FOOD WELL	20/1P	4
5	20/1P	INTERIOR LIGHTING KITCHEN BOH	L	0.65		2.30		RWC	1.65	E	EQ23_HOT FOOD WELL	20/1P	6
7	20/1P	INTERIOR LIGHTING DINNING	L	1.60	3	3.25		RWC	1.65	E	EQ23_HOT FOOD WELL	20/1P	8
9	20/1P	INTERIOR LIGHTING TRACK LIGHTS	L	1.05		2.85		RWC	1.80	E	EQ36.1_WORK TABLE	20/1P	10
11	20/1P	SHOW WINDOW RECEPTACLE	L	1.80		3.60		RWC	1.80	E	EQ36.1_WORK TABLE	20/1P	12
13	20/1P	SHOW WINDOW RECEPTACLE	L	1.80		3.60		RWC	1.80	E	EQ37_WALK IN COOLER	20/1P	14
15	20/1P	SHOW WINDOW RECEPTACLE	L	1.60		1.82		RWC	0.22	E	EQ37.1_WALK-IN-COOLER EVAPORATOR COIL	20/1P	16
17	20/1P	TIME CLOCK	O	0.50		1.80		RWC	1.30	E	EQ46_HEATED CABINET	20/1P	18
19	20/1P	WH-1 (WATER HEATER)	O	0.10		1.70		RWC	1.60	L	SHOW WINDOW RECEPTACLE	20/1P	20
21	20/1P	RCP-1 (RECIRCULATING PUMP)	M	1.00		1.90		RWC	0.90	L	BUSINESS SIGNAGE	20/1P	22
23	20/1P	SHOW WINDOW RECEPTACLE	L	1.80		3.00		RWC	1.20	L	EXTERIOR SIGNAGE	20/1P	24
25	20/1P	EQ18 REACH-IN REFRIGERATOR	E	0.38		0.68		RWC	0.30	R	DATA/TELEPHONE RACK	20/1P	26
27	20/1P	EQ15.1 WORK TABLE	R	1.80		2.52		RWC	0.72	R	ROOF RECEPTACLE	20/1P	28
29	20/1P	EQ36 WORK TABLE	R	1.80		1.80		RWC			SPARE	20/1P	30
						11.48		10.99		12.50			

PANEL	D	(EXISTING)	PHASE	1	WIRE	3	DEMAND LOAD IN KVA	24.34	DEMAND CURRENT IN AMPS	117.02	MOUNTING:	SURFACE	
208Y/120 VOLTS	200A	MLO									PANEL LOCATION:	BACK OF HOUSE	
											FED FROM:	MDP	
ELECTRICAL PANEL SCHEDULE													
CKT NO.	TRIP AMPS	DESCRIPTION OF LOAD	LOAD TYPE	LOAD (KVA)	NOTES	PER PHASE (KVA)	NOTES	LOAD (KVA)	LOAD TYPE	DESCRIPTION OF LOAD	TRIP AMPS	CKT NO.	
1	20/2P	EQ08_REFRIGERATED MERCHANTISER	E	1.66		6.08		RWC	4.42	O	TO PANEL-C	50/2P	2
3			E	1.66		6.08		RWC	4.42	O			4
5	20/2P	EQ10_RICE COOKER	E	1.67		2.11		RWC	0.45	E	EQ11_DRAWER WARMER	20/2P	6
7			E	1.67		2.11		RWC	0.45	E			8
9	20/2P	EQ3_DROP IN HOT FOOD WELL	E	0.12		0.57		RWC	0.45	E	EQ11_DRAWER WARMER	20/2P	10
11			E	0.12		0.57		RWC	0.45	E			12
13	20/1P	EQ1_REFRIGERATED SELF-SERVICE COUNTER CASE	E	0.97		1.41		RWC, NBEP	0.44	E	EQ4_DROP IN COLD FOOD WELL	20/1P	14
15	20/1P	EQ15 WORK TABLE	R	1.80		2.24		RWC, NBEP	0.44	E	EQ5_DROP IN COLD FOOD WELL	20/1P	16
17	20/1P	EQ6_DROP IN HOT FOOD WELL	E	1.65		2.37		RWC, NBEP	0.72	R	KITCHEN GENERAL RECEPTACLE	20/1P	18
19	20/1P	EQ9_REACH IN REFRIGERATOR	E	0.50		0.60		RWC, NBEP	0.10	R	EQ17_GRIDDLE	20/1P	20



① ELECTRICAL SITE POWER PLAN
 1/16" = 1'-0"

01' 2' 4' 8' 16'

ROOTS NATURAL
 KITCHEN

E5.0
 ELECTRICAL SITE
 PLAN

DRAWN
 CHECKED
 PROJECT NO.
 NYE
 NYE
 240720

3 BULLETIN 3		02/25/25
PERMIT SET		01/30/25
90% PROGRESS		01/24/25

3 BULLETIN 3	02/25/25
PERMIT SET	01/30/25
90% PROGRESS	01/24/25

PLUMBING SYMBOLS LIST

— SAN —	SANITARY SEWER (BELOW GROUND)
— GSAN —	GREASE SANITARY SEWER
— — — —	VENT PIPING
— — — —	HOT WATER PIPING
— — — —	HOT WATER RETURN PIPING
— — — —	COLD WATER PIPING
— G —	GAS PIPING
— ○ —	P-TRAP
— ○ —	PIPE UP
— ○ —	PIPE DROP
— ○ — II	CLEANOUT
— ○ — II	PLUGGED OUTLET/CLEANOUT
— ○ —	FLOOR DRAIN

PLUMBING ABBREVIATIONS

WCO	WALL CLEANOUT
CO	CLEANOUT
CW	COLD WATER
HW	HOT WATER
HWR	HOT WATER RETURN
SAN	SANITARY
V	VENT
W	WASTE
LAV	LAVATORY
WC	WATER CLOSET
TYP.	TYPICAL
DN	DOWN
AFF	ABOVE FINISH FLOOR
FD	FLOOR DRAIN
N.I.S	NOT IN SCOPE
BFP/RPZ	BACK FLOW PREVENTER
VTR	VENT THROUGH ROOF
ET	EXPANSION TANK
WH	ELECTRIC WATER HEATER
RCP	HOT WATER CIRCULATION PUMP

PLUMBING DRAWING LIST

P0.1	PLUMBING SYMBOLS, NOTES, ABBREVIATIONS AND SPECIFICATIONS (01 of 02)
P0.2	PLUMBING SPECIFICATION (02 of 02)
P1.0	PLUMBING SANITARY FLOOR PLAN
P1.1	PLUMBING WATER AND GAS FLOOR PLAN
P1.2	GAS ROOF PLAN
P3.0	PLUMBING DETAILS (01 of 02)
P3.1	PLUMBING DETAILS (02 of 02)
P4.0	PLUMBING SCHEDULES
P4.0	PLUMBING RISER DIAGRAMS

APPLICABLE CODES

IBC	2018 INTERNATIONAL BUILDING CODE
IFC	2018 INTERNATIONAL FIRE CODE
IMC	2018 INTERNATIONAL MECHANICAL CODE
IPC	2018 INTERNATIONAL PLUMBING CODE
IECC	2018 INTERNATIONAL ENERGY CONSERVATION CODE
NEC	2017 NATIONAL ELECTRICAL CODE W/LOCAL AMENDMENTS
IFGC	2018 INTERNATIONAL FUEL GAS CODE

BUILDING DEPARTMENT PLUMBING NOTES

- ALL PLUMBING SYSTEMS (SANITARY, WASTE, VENT, WATER) AND ASSOCIATED EQUIPMENT SHALL BE INSTALLED, OPERATED AND MAINTAINED IN ACCORDANCE WITH THE REQUIREMENTS OF 2018 INTERNATIONAL PLUMBING CODE.
- INSTALLATION OF UNDERGROUND PIPING SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION PC 702.2
- PROTECTION OF PIPING AND PLUMBING SYSTEM COMPONENTS AS PER SECTION PC 305.
- TRENCHING, EXCAVATION AND BACKFILL AS PER SECTION PC 306.
- RODENT PROOFING AS PER PC 304
- MATERIALS USED IN PLUMBING SYSTEMS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION PC 303, PC 605, PC 702, PC 902, PC 1102.
- EQUIPMENT CONNECTIONS AND JOINING OF PIPING SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF CHAPTERS 4, 5, 6, 7 AND 9.
- DEEP SEAL TRAPS FOR FLOOR DRAINS SHALL BE PROVIDED AS PER PC 1002, AND CLEAN-OUTS SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION PC 708
- VERTICAL AND HORIZONTAL PIPING SHALL BE SUPPORTED IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION PC 308
- WATER SUPPLY SYSTEMS SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE REQUIREMENTS OF CHAPTER 6 SECTION PC 601-603, 604, 606, 607, 608, 610
- THE SANITARY DRAINAGE SYSTEM SHALL BE SIZED AND INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF CHAPTER 7 SECTION PC 701, 704, 705, 706, 707, 708, 711.
- VENT PIPING FOR THE SANITARY DRAINAGE SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF CHAPTER 9 SECTIONS PC 901 THROUGH PC 912 THROUGH PC 917
- INSPECTION AND TESTING OF PLUMBING SYSTEMS SHALL BE IN ACCORDANCE WITH SECTION PC 312.

PLUMBING SPECIFICATIONS

- BASIC PLUMBING REQUIREMENTS, MATERIALS AND METHODS
- SCOPE
 - PROVIDE ALL MATERIAL, TOOLS, SUPERVISION AND LABOR INCLUDING ALL MISCELLANEOUS AND INCIDENTAL ITEMS REQUIRED FOR COMPLETE AND OPERABLE PLUMBING INSTALLATIONS AS SHOWN OR DESCRIBED ON THE DRAWINGS AND IN THESE SPECIFICATIONS.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING AND NEW CONDITIONS AND MATERIALS WITHIN THE CONSTRUCTION AREA. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE OWNER'S SATISFACTION.
 - OBTAIN ALL PERMITS, PAY ALL PERMIT FEES AND SCHEDULE ALL REQUIRED INSPECTIONS. COPIES OF ALL PERMITS AND INSPECTION CERTIFICATES SHALL BE FORWARDED TO THE OWNER FOR RECORD.
 - THE GENERAL CONDITIONS OF THE CONTRACT AND ALL DIVISION 1 REQUIREMENTS APPLY TO THE WORK OF THIS SECTION.
- THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO SUBMITTING BID TO DETERMINE CONDITIONS AND THE EXTENT OF THE WORK. BY COMMENCING WORK, THE CONTRACTOR ACKNOWLEDGES HIS CONFIRMATION OF ALL CONDITIONS AS ACCEPTABLE WITH REFERENCE TO HIS CONTRACT, SCOPE OF WORK AND BID PRICE SUCH THAT NO ADDITIONAL COMPENSATION SHALL BE FORTHCOMING FOR UNFORESEEN EXISTING CONDITIONS.
- IN ALL AREAS SUBJECT TO FREEZING CONDITIONS, THE CONTRACTOR SHALL PROVIDE FREEZE PROTECTION FOR ALL DOMESTIC WATER PIPING INSTALLED UNDER HIS CONTRACT.
- ALL ELECTRICAL REQUIREMENTS SHALL BE COORDINATED WITH THE CONTRACTOR FOR ELECTRICAL WORK. THIS CONTRACTOR IS RESPONSIBLE FOR ALL LOW VOLTAGE WIRING FOR EQUIPMENT INSTALLED UNDER HIS CONTRACT. THE CONTRACTOR FOR ELECTRICAL WORK IS RESPONSIBLE FOR LINE VOLTAGE POWER WIRING ONLY.
- COLOR AND FINISH SELECTIONS FOR ALL MATERIALS, INCLUDING PAINTING OF PIPING, SHALL BE AS DIRECTED AND/OR APPROVED BY THE ARCHITECT.
- MINOR DETAILS NOT SHOWN OR SPECIFIED, BUT NECESSARY FOR THE PROPER AND ACCEPTABLE CONSTRUCTION, INSTALLATION OR OPERATION OF ANY PART OF THE WORK AS DETERMINED BY THE ENGINEER SHALL BE INCLUDED AS IF SPECIFIED OR INDICATED ON THE DRAWINGS.
- THIS CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIREMENTS FOR THE INSTALLATION, CONNECTION, EXTENSION OR MODIFICATION TO ALL UTILITY SERVICES WITH RESPECTIVE PROVIDERS INCLUDING PAYMENT OF ALL ASSOCIATED FEES.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL PAINTING ASSOCIATED WITH CUTTING AND PATCHING. ALL PAINTING IN AREAS WITH COMPLETE FINISH RENOVATIONS SHALL BE PROVIDED BY THE GENERAL CONTRACTOR.

K. THE CONTRACTOR IS RESPONSIBLE FOR ALL PAINTING ASSOCIATED WITH CUTTING AND PATCHING. ALL PAINTING IN AREAS WITH COMPLETE FINISH RENOVATIONS SHALL BE PROVIDED BY THE GENERAL CONTRACTOR.

1.02 SUBMITTALS

- SUBMITTAL REQUIREMENTS SHALL BE COORDINATED WITH THE ARCHITECT AND AUTHORITIES HAVING JURISDICTION. UNLESS OTHERWISE DIRECTED, CONTRACTOR SHALL PROVIDE SUBMITTALS AS LISTED BELOW.
 - PIPE AND FITTINGS
 - VALVES
 - HANGERS AND SUPPORTS
 - PLUMBING PIPING LAYOUT
 - TESTS
 - PLUMBING FIXTURES
 - WATER HEATERS & ACCESSORIES
 - MIXING VALVES
 - ALL SCHEDULED PLUMBING EQUIPMENT
- SUBMITTALS FROM SUPPLIERS OR MANUFACTURERS WHICH DO NOT BEAR THE STAMP OF THE SUBMITTING CONTRACTOR INDICATING THAT THE CONTRACTOR HAS REVIEWED THE SUBMITTAL FOR CONFORMANCE WITH THE PROJECT REQUIREMENTS WILL BE RETURNED REJECTED.
- THE ENGINEER'S REVIEW OF SUBMITTALS IS A COURTESY WHICH DOES NOT RELIEVE THE CONTRACTOR FROM CONFORMING WITH THE CONSTRUCTION DOCUMENTS, REGARDLESS OF THE ACTION INDICATED BY THE SHOP DRAWINGS STAMP.
- REVIEW OF SHOP DRAWINGS BY THE ENGINEER SHALL BE LIMITED TO THE INITIAL REVIEW, AND A SECOND REVIEW OF ANY REQUIRED RESUBMITTED DATA. IF THE ENGINEER IS REQUIRED TO REVIEW SHOP DRAWINGS FOR A THIRD (OR MORE) SUBMISSION OF THE SAME ITEM, THE CONTRACTOR SHALL BE LIABLE FOR COMPENSATING THE ENGINEER FOR THESE SUBSEQUENT REVIEWS AS PER THE ENGINEER'S CURRENT HOURLY RATE SCHEDULE.
- SUBMIT PROOF OF APPROVAL AND/OR CONFIRMATION OF SATISFACTORY TEST RESULTS TO THE OWNER AND THE ARCHITECT.
- SUBMIT TO THE OWNER'S MAINTENANCE PERSONNEL OPERATION AND MAINTENANCE DATA FOR ALL SYSTEM COMPONENTS, SERVICING REQUIREMENTS, INSPECTION DATA, REPLACEMENT PART NUMBERS AND AVAILABILITY AND CONTACT INFORMATION FOR SERVICE/SUPPLY COMPANY.
- FOR ALL BELOW GRADE PIPING WHERE ACTUAL INSTALLATION DEVIATES FROM CONSTRUCTION DRAWINGS, THE CONTRACTOR SHALL PROVIDE AS-BUILT DRAWINGS INDICATING BELOW GRADE PIPE LOCATIONS DIMENSIONED TO NEAREST COLUMN LINES.
- RECORD AS-BUILT DRAWINGS SHALL BE SUPPLIED TO THE OWNER/TENANT AFTER COMPLETION OF THE WORK SHOWING ANY ALTERATIONS, ADDITIONS AND/OR DELETIONS TO THE SYSTEM(S) INSTALLED.
- SUBSTITUTIONS
 - ALL EQUIPMENT SHALL BE PRODUCTS OF THE SPECIFIED MANUFACTURER OR MANUFACTURERS. ALL BIDS SHALL BE BASED ON THE SPECIFIED MANUFACTURER OR MANUFACTURER'S EQUIPMENT. FOR SUBSTITUTIONS OF OTHER MANUFACTURER'S EQUIPMENT TO BE CONSIDERED, THE SUBSTITUTION MUST BE INDICATED PRIOR TO BIDDING WITH THE REASON FOR THE PROPOSED SUBSTITUTION IDENTIFIED, AND THE PROPOSED CREDIT TO THE OWNER INDICATED. THE ENGINEER SHALL DETERMINE THE ACCEPTABILITY OF ANY PROPOSED SUBSTITUTIONS.
 - THE CONTRACTOR ASSUMES ALL RESPONSIBILITY FOR COORDINATING THE WORK OF OTHER TRADES WHICH MAY BE AFFECTED BY SUBSTITUTIONS, INCLUDING ALL RELATED COSTS.
- DEFINITIONS
 - FURNISH: TO PURCHASE, PROCURE, ACQUIRE AND DELIVER, COMPLETE WITH RELATED ACCESSORIES.
 - INSTALL: TO ERECT, MOUNT AND CONNECT, COMPLETE WITH RELATED ACCESSORIES.
 - PROVIDE: TO FURNISH AND INSTALL.
 - PLUMBING CONTRACTOR, THE CONTRACTOR, THIS CONTRACTOR: THE CONTRACTOR FOR PLUMBING WORK WHICH IS SPECIFIED HEREIN AND SHOWN ON THESE DRAWINGS.
- DRAWINGS
 - THE DRAWINGS ARE DIAGRAMMATIC AND ARE INTENDED TO ILLUSTRATE THE GENERAL ARRANGEMENT AND ROUTING OF PIPING AND GENERAL LOCATIONS OF EQUIPMENT. PRECISE LOCATIONS OF EQUIPMENT, RISERS AND STACKS, AND ROUTING AND ELEVATION OF ALL PIPING SYSTEMS SHALL BE COORDINATED IN THE FIELD WITH THE ARCHITECT, ARCHITECTURAL DRAWINGS, THE WORK OF OTHER TRADES, EXISTING AND NEW BUILDING CONDITIONS AND/OR THE PREFERENCES OF THE OWNER/TENANT AS CONSTRUCTION PROCEEDS. ALL PIPING SHALL BE INSTALLED CONCEALED IN FINISHED SPACES, UNLESS NOTED OTHERWISE.
 - PROVIDE ALL NECESSARY INCIDENTAL MATERIALS AND ACCESSORIES REQUIRED TO MAKE THE WORK COMPLETE IN ALL RESPECTS, EVEN IF NOT PARTICULARLY SHOWN OR SPECIFIED.
 - REFER TO PLUMBING EQUIPMENT/FIXTURE SCHEDULE ON THE DRAWINGS FOR ALL FIXTURE AND EQUIPMENT SPECIFICATIONS.
 - REFER TO FIXTURE CONNECTION SIZE SCHEDULE FOR ALL FIXTURE ROUGHING SIZE REQUIREMENTS.
 - VERIFY ALL INDICATED CONDITIONS BEFORE STARTING WORK AND REPORT ANY DISCREPANCIES. THE DRAWINGS REFLECT CONDITIONS WHICH CAN BE REASONABLY INTERPRETED FROM THE EXISTING VISIBLE CONDITIONS OR FROM DRAWINGS AND INFORMATION FURNISHED BY THE OWNER.
 - LOCATE ALL FIXTURES AND EQUIPMENT AS PER THE FINAL ARCHITECTURAL DRAWINGS.
- PRODUCTS
 - SANITARY AND VENT PIPING:
 - SANITARY PIPING SHALL BE HUBLESS CAST IRON PIPE WITH STAINLESS STEEL COUPLINGS AND ELASTOMERIC GASKETS WITH A MINIMUM 4 BANDS PER COUPLING. PVC PIPING AS PER INTERNATIONAL CODE 2018, TABLE 702.1 AND TABLE 702.2 MAY BE USED IF APPROVED BY LOCAL AUTHORITIES.

1.06 PRODUCTS

- SANITARY PIPING SHALL BE HUBLESS CAST IRON PIPE WITH STAINLESS STEEL COUPLINGS AND ELASTOMERIC GASKETS WITH A MINIMUM 4 BANDS PER COUPLING. PVC PIPING AS PER INTERNATIONAL CODE 2018, TABLE 702.1 AND TABLE 702.2 MAY BE USED IF APPROVED BY LOCAL AUTHORITIES.

D. VALVES:

- PROVIDE GATE VALVES, BUTTERFLY OR BALL VALVES FOR SHUT-OFF DUTY ON MAIN AND BRANCH SUPPLY LINES. FOR ALL PIPE RUNS 2" AND SMALLER (I.D.), VENT PIPING SHALL BE PITCHED TO DRAIN.
- ALL CAST IRON SOIL PIPE AND FITTINGS SHALL BE MARKED WITH THE COLLECTIVE TRADEMARK OF THE CAST IRON SOIL PIPE INSTITUTE (CISPI) AND BE LISTED BY NSF INTERNATIONAL.
- DOMESTIC WATER PIPING:
 - ABOVE GRADE WATER PIPING SHALL BE TYPE 'L' HARD-DRAWN COPPER TUBE.
 - FITTINGS IN DOMESTIC WATER PIPING SHALL BE WROUGHT COPPER OR CAST BRASS.
 - JOINTS SHALL BE MADE WITH LEAD-FREE SOLDER.
 - THE ENTIRE DOMESTIC WATER DISTRIBUTION SYSTEM SHALL BE INSULATED INCLUDING ALL VALVES, FITTINGS, ETC.
 - COMPLY WITH NSF 61 FOR MATERIALS FOR WATER-SERVICE PIPING AND SPECIALTIES FOR DOMESTIC WATER.
 - AS PER 2018 INTERNATIONAL ENERGY CONSERVATION CODE (IECC2018), C403.12.3, PIPING FROM A WATER HEATER TO THE TERMINATION OF HEATED WATER FIXTURE SUPPLY PIPE SHALL BE INSULATED IN ACCORDANCE WITH TABLE OF MINIMUM PIPE INSULATION THICKNESS.
- PLUMBING FIXTURES AND EQUIPMENT TO HAVE SHUT-OFF VALVES ON SUPPLY LINES.
- ALL BRANCH LINES TO HAVE SHUT-OFF VALVES.
- ALL VALVES SHALL BE ACCESSIBLE. PROVIDE ACCESS DOORS WHERE REQUIRED FOR VALVE ACCESS.
- PROVIDE GLOBE VALVES FOR THROTTLING/BALANCING OF THE HOT WATER CIRCULATING SYSTEM.
- GAS PIPING:
 - GAS PIPING SHALL BE SIZED IN ACCORDANCE WITH PIPE SIZING TABLES OR SIZING EQUATIONS IN ACCORDANCE WITH 2018 INTERNATIONAL FUEL GAS CODE SECTION 402.4.
 - METALLIC PIPE SHALL COMPLY WITH SECTIONS 403.4.1 THROUGH 403.4.4.
 - PLUMBING SYSTEM INSTALLATION SHALL COMPLY WITH REQUIREMENTS OF 2018 INTERNATIONAL FUEL GAS CODE SECTION 404.
 - AS PER 2018 INTERNATIONAL FUEL GAS CODE SECTION 404.4; UNDERGROUND PIPING, WHERE INSTALLED BELOW GRADE THROUGH THE OUTER FOUNDATION OR BASEMENT WALL OF A BUILDING, SHALL BE ENCASED IN A PROTECTIVE PIPE SLEEVE. THE ANNUAL SPACE BETWEEN THE GAS PIPING AND THE SLEEVE SHALL BE SEALED.
 - PLUMBING INSTALLED UNDERGROUND BENEATH BUILDINGS IS PROHIBITED EXCEPT WHERE THE PIPING IS ENCASED IN A CONDUIT OF WROUGHT IRON OR STEEL PIPE DESIGNED TO WITHSTAND THE SUPERIMPOSED LOADS. THE CONDUIT SHALL BE PROTECTED FROM CORROSION IN ACCORDANCE WITH SECTION 404.11 AND SHALL BE INSTALLED IN ACCORDANCE WITH SECTION 404.11.1 OR 404.11.2 OF 2018 INTERNATIONAL FUEL GAS CODE.
 - AS PER 2018 INTERNATIONAL FUEL GAS CODE SECTION 404.12; UNDERGROUND PIPING SYSTEMS SHALL BE INSTALLED A MINIMUM DEPTH OF 12 INCHES BELOW GRADE.
 - THE GAS PIPING IS ENCASED IN A CONDUIT OF WROUGHT IRON OR STEEL PIPE TO WITHSTAND THE SUPERIMPOSED LOADS.
 - SHUTOFF VALVES SHALL BE LOCATED IN PLACES SO AS TO PROVIDE ACCESS FOR OPERATION AND SHALL BE INSTALLED SO AS TO BE PROTECTED FROM DAMAGE.
 - INSTALL PIPING TO CONSERVE BUILDING SPACE. DO NOT INTERFERE WITH USE OF BUILDING SPACE AND THE WORK OF OTHER TRADES. ALL PIPING RUN IN CEILING SHALL BE INSTALLED TIGHT TO THE STRUCTURE ABOVE.
 - INSTALL PIPING TO ALLOW FOR EXPANSION AND CONTRACTION WITHOUT STRESSING PIPE, JOINTS OR CONNECTED EQUIPMENT. PROVIDE PIPE ANCHORS, GUIDES AND EXPANSION JOINTS OR LOOPS IN ALL HOT WATER AND HOT WATER CIRCULATING MAIN SUPPLY PIPING AND SEGMENTS OF SUCH PIPE THAT EXCEED 30'-0" IN LENGTH.
 - IN ALL AREAS WITH FINISHED SURFACES, SYSTEM PIPING AND COMPONENTS SHALL BE CONCEALED ABOVE OR WITHIN FINISHED SURFACES.
 - REDUCTIONS IN PIPE SIZES SHALL BE MADE WITH ONE-PIECE REDUCING FITTINGS. BUSHINGS ARE NOT ACCEPTABLE. USE FLANGED FITTINGS AT THE BASE OF RISERS.
 - VENT PENETRATIONS THROUGH THE ROOF SHALL BE FLASHED.
 - IF WATER PRESSURE EXCEEDS 80 PSI, A WATER PRESSURE REDUCING VALVE SHALL BE INSTALLED IN WATER PIPING AT CONNECTION TO MAIN.
 - PROVIDE DIELECTRIC FITTINGS BETWEEN DISSIMILAR METALS.
 - PROVIDE ACCESS DOORS/PANELS FOR SERVICE AND ACCESS TO ALL VALVES AND OTHER SYSTEM COMPONENTS ENCLOSED IN WALLS AND CEILINGS. ACCESS DOORS SHALL BE FURNISHED BY THIS CONTRACTOR, INSTALLED BY THE GENERAL CONTRACTOR.
 - ALL FIXTURES REQUIRING VACUUM BREAKERS SHALL BE EQUIPPED WITH INTEGRAL VACUUM BREAKERS.
 - ANY PENETRATIONS THROUGH FIRE RATED PARTITIONS, FLOORS, OR CEILINGS SHALL BE STEEL SLEEVED AND SEALED WITH 3M BRAND UL RATED FIRE BARRIER CAULK OR APPROVED EQUAL.
 - WHEN THE WATER PIPING SYSTEM IS COMPLETE, THOROUGHLY FLUSH ALL DIRT, SEDIMENT, SOLDER, ETC., OUT OF THE SYSTEM, REMOVING ALL STRAINERS, VALVE STEM SEATS, ETC., REQUIRED TO ACCOMPLISH THE FLUSHING.
 - AT ALL INDIRECT WASTE DRAINS, MAINTAIN AIR GAP AS REQUIRED BY CODE.
 - INSTALL SLEEVES FOR ALL PIPES WHICH PASS THROUGH WALLS, FLOORS, AND CEILINGS. WHERE PIPES ARE TO BE INSULATED, THE SLEEVE SHALL BE LARGE ENOUGH TO ACCOMMODATE INSULATION. SLEEVES SHALL BE FLUSH WITH FINISHED SURFACES AT BOTH ENDS. ON FINISHED SURFACES IN EXPOSED AREAS PROVIDE ESCUTCHEONS COMPATIBLE WITH FINISH.

MINIMUM PIPE INSULATION THICKNESS		NOMINAL PIPE OR TUBE SIZE (INCHES)	CONDUCTIVITY BTU IN./H FT2 °F	NOMINAL PIPE OR TUBE SIZE (INCHES)					
CONDUCTIVITY BTU IN./H FT2 °F	MEAN RATING TEMPERATURE, °F	<1							

3 BULLETIN 3	02/25/25
PERMIT SET	01/30/25
90% PROGRESS	01/24/25

2. INSTALLATION

2.01 GENERAL

- A. ALL WORK WHICH REQUIRES DISRUPTION OF THE ROOFING SHALL BE DONE BY A CONTRACTOR CERTIFIED BY THE ROOFING MANUFACTURER AS REQUIRED TO MAINTAIN ANY EXISTING ROOF WARRANTIES.
- B. EXTERIOR INSTALLATIONS TO BE WEATHER PROOF IN ALL RESPECTS.
- C. EXTERIOR MATERIALS AND EQUIPMENT SHALL BE PAINTED TO PREVENT CORROSION, COLOR PER ARCHITECT.
- D. COORDINATE THE PLUMBING WORK WITH ALL OTHER AFFECTED WORK AND THE CONSTRUCTION SCHEDULE.
- E. REAM PIPE AND TUBE ENDS. REMOVE BURRS. BEVEL PLAIN AND FERROUS END PIPE.
- F. REMOVE SCALE AND FOREIGN MATERIAL, FROM INSIDE AND OUTSIDE, BEFORE ASSEMBLY.
- G. PREPARE PIPING CONNECTIONS TO EQUIPMENT WITH FLANGES AND UNIONS.
- H. COORDINATION WITH THE WORK OF OTHER TRADES IS REQUIRED. PROVIDE OFFSETS IN PIPING SYSTEMS OR MINOR DEVIATIONS TO THE INDICATED PIPE ROUTING IN ORDER TO COORDINATE THE PLUMBING WORK WITH THE WORK OF ALL OTHER TRADES AND THE GENERAL BUILDING CONDITIONS.
- I. NO DOMESTIC WATER PIPING SHALL BE INSTALLED IN UNHEATED SPACES.
- J. PRIOR TO DISCONNECTING AND CONNECTING NEW WORK TO EXISTING SYSTEMS, THE PLUMBING CONTRACTOR SHALL NOTIFY THE PROPERTY MANAGER AND OFFER A PROPOSED SCHEDULE OF WORK. ESB WILL AUTHORIZE CONNECTIONS AND COORDINATE NECESSARY SHUT DOWNS AND DRAIN DOWNS AS REQUIRED. SHUT DOWNS AND DRAIN DOWNS MAY BE PERFORMED BY THE PLUMBING CONTRACTOR ONLY AFTER RECEIVING ESB AUTHORIZATION, AND SHOULD BE PERFORMED UNDER SUPERVISION OF ESB PERSONNEL. THREE (3) DAYS ADVANCE NOTICE TO THE PROPERTY MANAGER IS REQUIRED.
- K. THE PLUMBING CONTRACTOR IS ADVISED THAT DUE TO THE NATURE OF THE OPERATIONS AND TENANT REQUIREMENTS, CONNECTIONS TO EXISTING SYSTEMS MAY HAVE TO BE MADE AFTER REGULAR WORKING HOURS. THE PROPERTY MANAGER WILL ADVISE THE PLUMBING CONTRACTOR OF THE TIME CONSTRAINTS UPON RECEIPT AND APPROVAL OF THE PLUMBING CONTRACTOR'S REQUEST FOR SHUT DOWN AND CONNECTION TO EXISTING SYSTEMS.
- L. WHEN CONNECTING TO EXISTING STACKS AND RISERS, PROVISION IS TO BE MADE FOR FUTURE CONNECTIONS BY PROVIDING CAPPED AND VALVED OUTLETS ON DOMESTIC WATER RISERS AND PLUGGED OUTLETS ON THE SANITARY AND VENT STACKS.

2.02 ABOVE GRADE

- A. INSTALL PLUMBING PIPING IN ACCORDANCE WITH RECOGNIZED INDUSTRY PRACTICES TO ENSURE THAT PIPING COMPLIES WITH REQUIREMENTS AND SERVES INTENDED PURPOSES.
- B. ROUTE PIPING IN AN ORDERLY MANNER, PLUMB AND PARALLEL TO BUILDING STRUCTURE. MAINTAIN GRADIENT, SLOPE PIPING AND ARRANGE SYSTEMS TO DRAIN. IN DOMESTIC WATER SYSTEMS, PROVIDE DRAIN VALVES AT MAIN SHUT-OFF VALVES AND ALL LOW POINTS IN PIPING.
- C. USE EXISTING CONNECTIONS AT MAINS WHERE AVAILABLE FOR NEW BRANCH PIPING. LOCATE ALL RISERS AND PIPING BEFORE CONSTRUCTION COMMENCES AND TAKE CARE NOT TO DAMAGE SAME. ANY DAMAGE OCCURRING TO THE EXISTING PIPING WILL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

3. TESTING

- A. AT THE COMPLETION OF THE PLUMBING WORK, COMPLETELY TEST THE ENTIRE INSTALLATION OF ALL SYSTEMS FOR PROPER OPERATION AND COMPLIANCE WITH APPLICABLE CODES AND LOCAL REQUIREMENTS. CORRECT ALL DEFICIENCIES FOUND.
- B. TESTING OF THE INSTALLED SYSTEMS SHALL BE MADE BY THE CONTRACTOR IN THE PRESENCE OF A REPRESENTATIVE OF THE OWNER.
- C. THE CONTRACTOR SHALL NOT COVER UP OR PERMANENTLY CONCEAL PIPING, DEVICES OR ANY PORTION OF NEWLY CONSTRUCTED PLUMBING SYSTEM(S) UNTIL SUCH SYSTEM, OR PORTION OF THE SYSTEM, HAS BEEN TESTED IN THE PRESENCE OF A REPRESENTATIVE OF THE OWNER AND INSPECTED BY THE LOCAL INSPECTOR AND APPROVED IN WRITING, EXCEPT PIPING PASSING THROUGH FLOORS, WALLS, PARTITIONS, OR BEAMS, FOR DISTANCES EQUAL TO THE THICKNESS OF SUCH FLOOR, WALL, PARTITION OR BEAM.
- D. THIS CONTRACTOR SHALL NOTIFY THE VARIOUS DEPARTMENTS, BUREAUS AND INDIVIDUALS AT LEAST TWO WEEKS IN ADVANCE OF THE TIME THAT THE TESTS ARE TO BE CONDUCTED.
- E. ALL DEFECTIVE PARTS SHALL BE REPLACED OR CORRECTED BY THIS CONTRACTOR AND AN EXTRA TEST OR TESTS SHALL BE MADE UNTIL THE OPERATION IS SATISFACTORY. ALL ARRANGEMENTS AND EXPENSES NECESSARY TO CONDUCT ALL TESTS REQUIRED BY THESE SPECIFICATIONS AND THE VARIOUS AGENCIES HAVING JURISDICTION OVER THE WORK INSTALLED UNDER THIS CONTRACT SHALL BE MADE BY THIS CONTRACTOR. NO EXTRA COMPENSATION WILL BE ALLOWED FOR THESE TESTS, THE COST THEREOF BEING INCLUDED IN THE LUMP SUM BID FOR THIS CONTRACT.
- F. WHERE ANY EVIDENCE OF STOPPAGE IS FOUND IN PIPING OR EQUIPMENT, THIS CONTRACTOR SHALL DISCONNECT, CLEAN, REPAIR AND RECONNECT ALL OBSTRUCTED PIPING OR EQUIPMENT AND SHALL ALSO PAY FOR ALL NECESSARY CUTTING AND REPAIRS TO ADJOINING WORK.
- G. ALL PIPING AND EQUIPMENT SHALL BE THOROUGHLY CLEANED INSIDE AND OUT, OF DIRT, CUTTINGS, OILS AND OTHER FOREIGN SUBSTANCES AND SHALL BE LEFT CLEAN.

H. ALL REQUIRED TESTS SHALL BE WITNESSED BY LOCAL AUTHORITIES AND THE OWNER'S REPRESENTATIVE.

I. ALL EQUIPMENT WILL BE FACTORY TESTED.

J. CONTRACTOR SHALL IDENTIFY TO THE OWNER'S REPRESENTATIVE ANY LEAKS OR DAMAGE THAT OCCURS AS A RESULT OF SYSTEM TESTING. CONTRACTOR SHALL TAKE NECESSARY PRECAUTIONS TO LIMIT ANY POTENTIAL DAMAGE. CORRECTIVE ACTION REQUIRED AS A RESULT OF TESTING SHALL BE PERFORMED IMMEDIATELY AND AT THE CONTRACTOR'S EXPENSE.

K. REPORT IN WRITING TO AUTHORITIES HAVING JURISDICTION, THE ARCHITECT AND THE OWNER THE RESULTS OF ALL TESTING.

L. TESTING REQUIREMENTS.

a. UPON COMPLETION OF A SECTION OF OR THE ENTIRE WATER SUPPLY SYSTEM, THE SYSTEM, OR PORTION COMPLETED, SHALL BE TESTED AND PROVED TIGHT UNDER A WATER PRESSURE NOT LESS THAN THE WORKING PRESSURE OF THE SYSTEM; OR, FOR PIPING SYSTEMS OTHER THAN PLASTIC, BY AN AIR TEST OF NOT LESS THAN 50 PS (344 KPA). THIS PRESSURE SHALL BE HELD FOR NOT LESS THAN 15 MINUTES. THE WATER UTILIZED FOR TESTS SHALL BE OBTAINED FROM A POTABLE SOURCE OF SUPPLY. THE REQUIRED TESTS SHALL BE PERFORMED IN ACCORDANCE WITH THIS SECTION AND SECTION 113.

b. TESTS SHALL BE WITNESSED BY THE BUILDING ENGINEER.

c. THE PLUMBING CONTRACTOR WILL BE HELD RESPONSIBLE FOR ALL DAMAGE DUE TO TEST FAILURES AND LEAKAGE IN THE TEST AREA AND ADJACENT TENANT OR ESB SPACES.

M. REFILL ENTIRE POTABLE HOT AND COLD WATER SUPPLY SYSTEM WITH CHLORINE SOLUTION (HTH OLIN CHEMICAL CORP.) AT A STRENGTH TO MEET STANDARDS OF THE DEPARTMENT OF HEALTH, AND FOR A PERIOD OF RETENTION AS STIPULATED.

N. THOROUGHLY FLUSH PIPING SYSTEM WITH FRESH WATER IMMEDIATELY PRIOR TO FINAL ACCEPTANCE.

4. WARRANTY

A. EQUIPMENT, MATERIALS AND WORKMANSHIP FURNISHED UNDER THIS CONTRACT SHALL BE GUARANTEED BY THE CONTRACTOR FOR A PERIOD OF ONE YEAR FROM THE DATE OF FINAL ACCEPTANCE OF THE WORK BY THE OWNER. THE CONTRACTOR SHALL KEEP THE WORK IN GOOD REPAIR FOR ONE YEAR AFTER THE DATE OF FINAL APPROVAL. THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, PROMPTLY CORRECT AND REPAIR ANY AND ALL BREAKS, FAILURES OR WEAR DUE TO FAULTY MATERIALS, WORKMANSHIP OR EQUIPMENT. ALL SETTLEMENTS OF SURFACES THAT MAY OCCUR WITHIN THAT PERIOD SHALL ALSO BE PROMPTLY REPAIRED.

Property of NY Engineers

GENERAL NOTES:	
A.	REFER RISER DIAGRAMS FOR PIPE SIZING.
B.	UNLESS OTHERWISE NOTED, SLOPE OF DRAINAGE SYSTEM TO BE 1/8" PER FOOT OF RUN FOR PIPE 3" OR LARGER AND 1/4" PER FOOT FOR PIPE SMALLER THAN 3".
C.	CONTRACTOR TO FIELD VERIFY FEASIBILITY OF SLAB PENETRATION AS PER STRUCTURAL REQUIREMENT.
D.	PROVIDE ACCESS PANELS FOR WATER HAMMER ARRESTOR, CLEANOUTS & SHUT-OFF VALVES AS REQUIRED.
E.	PROVIDE TRAP PRIMER/ SEAL IN FLOOR DRAIN AS PER LOCAL JURISDICTION.


PLUMBING SANITARY KEYED NOTES:	
1	EXTEND AND CONNECT NEW 4" SANITARY LINE TO EXISTING SANITARY LINE IN SPACE. CONTRACTOR TO FIELD VERIFY EXISTING SANITARY PIPE SIZE, LOCATION AND INVERT OF EXISTING SANITARY LINE. BASE BID ACCORDINGLY. REFER CIVIL SITE PLAN FOR MORE DETAILS.
2	EXTEND AND CONNECT NEW 3" VENT PIPE TO EXISTING VENT PIPE. CONTRACTOR TO FIELD VERIFY CONDITION, SIZE AND LOCATION OF EXISTING VENT PIPE. UPGRADE IF REQUIRED AND BASE BID ACCORDINGLY.
3	EXTEND AND CONNECT NEW 4" GREASE WASTE PIPING TO EXISTING GREASE WASTE LINE IN SPACE. CONTRACTOR TO FIELD VERIFY SIZE, ROUTING AND INVERT. CONTRACTOR TO FIELD VERIFY THE LOCATION, CONDITION AND CAPACITY OF GREASE INTERCEPTOR IS MORE OR EQUAL THAN 100GPM AND PROVIDE NEW IF EXISTING IS NOT SUFFICIENT. REFER CIVIL SITE PLAN FOR MORE DETAILS.
4	INDIRECT WASTE FROM DOOR TYPE DISH MACHINE(27) AND SOLID DISHABLE SINK(28) TO FLOOR SINK WITH APPROVED AIR GAP.
5	INDIRECT WASTE FROM DROP IN HOT FOOD WELL(3) AND DROP IN COLD FOOD WELL(4) TO FLOOR SINK WITH APPROVED AIR GAP.
6	INDIRECT WASTE FROM 3-COMPARTMENT(31) SINK TO FLOOR SINK WITH APPROVED AIR GAP.
7	INDIRECT WASTE FROM ICE AND WATER DISPENSER(43) TO FLOOR SINK WITH APPROVED AIR GAP.
8	INDIRECT WASTE FROM KETTLE/POT FILLER(51) TO FLOOR SINK WITH APPROVED AIR GAP.
9	INDIRECT WASTE FROM 2-COMPARTMENT(40) SINK TO FLOOR SINK WITH APPROVED AIR GAP.
10	INDIRECT WASTE FROM HOT FOOD TABLE(19) SINK TO FLOOR SINK WITH APPROVED AIR GAP.
11	INDIRECT WASTE FROM HOT FOOD TABLE(23) SINK TO FLOOR SINK WITH APPROVED AIR GAP.
12	CONDENSATE DRAIN FROM WALK-IN COOLER TO FLOOR SINK WITH APPROVED AIR GAP.

ROOTS NATURAL KITCHEN

PLUMBING
SANITARY FLOOR
PLAN

P1.0

① PLUMBING SANITARY FLOOR PLAN
1/4" = 1'-0"



0 6'1" 2' 4' 8'

GENERAL NOTES:

- A. REFER RISER DIAGRAMS FOR PIPE SIZING.
- B. UNLESS OTHERWISE NOTED, SLOPE OF DRAINAGE SYSTEM TO BE 1/8" PER FOOT OF RUN FOR PIPE 3" OR LARGER AND 1/4" PER FOOT FOR PIPE SMALLER THAN 3".
- C. CONTRACTOR TO FIELD VERIFY FEASIBILITY OF SLAB PENETRATION AS PER STRUCTURAL REQUIREMENT.
- D. PROVIDE ACCESS PANELS FOR WATER HAMMER ARRESTOR, CLEANOUTS & SHUT-OFF VALVES AS REQUIRED.
- E. PROVIDE TRAP PRIMER/ SEAL IN FLOOR DRAIN AS PER LOCAL JURISDICTION.

PLUMBING SANITARY KEYED NOTES:

- 1 EXTEND AND CONNECT NEW 4" SANITARY LINE TO EXISTING SANITARY LINE IN SPACE. CONTRACTOR TO FIELD VERIFY EXISTING SANITARY PIPE SIZE, LOCATION AND INVERT OF EXISTING SANITARY LINE. BASE BID ACCORDINGLY. REFER CIVIL SITE PLAN FOR MORE DETAILS.
- 2 EXTEND AND CONNECT NEW 3" VENT PIPE TO EXISTING VENT PIPE. CONTRACTOR TO FIELD VERIFY CONDITION, SIZE AND LOCATION OF EXISTING VENT PIPE. UPGRADE IF REQUIRED AND BASE BID ACCORDINGLY.
- 3 EXTEND AND CONNECT NEW 4" GREASE WASTE PIPING TO EXISTING GREASE WASTE LINE IN SPACE. CONTRACTOR TO FIELD VERIFY SIZE, ROUTING AND INVERT. CONTRACTOR TO FIELD VERIFY THE LOCATION, CONDITION AND CAPACITY OF GREASE INTERCEPTOR IS MORE OR EQUAL THAN 100GPM AND PROVIDE NEW IF EXISTING IS NOT SUFFICIENT. REFER CIVIL SITE PLAN FOR MORE DETAILS.
- 4 INDIRECT WASTE FROM DOOR TYPE DISH MACHINE(27) AND SOLID DISHABLE SINK(28) TO FLOOR SINK WITH APPROVED AIR GAP.
- 5 INDIRECT WASTE FROM DROP IN HOT FOOD WELL(3) AND DROP IN COLD FOOD WELL(4) TO FLOOR SINK WITH APPROVED AIR GAP.
- 6 INDIRECT WASTE FROM 3-COMPARTMENT(31) SINK TO FLOOR SINK WITH APPROVED AIR GAP.
- 7 INDIRECT WASTE FROM ICE AND WATER DISPENSER(43) TO FLOOR SINK WITH APPROVED AIR GAP.
- 8 INDIRECT WASTE FROM KETTLE/POT FILLER(51) TO FLOOR SINK WITH APPROVED AIR GAP.
- 9 INDIRECT WASTE FROM 2-COMPARTMENT(40) SINK TO FLOOR SINK WITH APPROVED AIR GAP.
- 10 INDIRECT WASTE FROM HOT FOOD TABLE(19) SINK TO FLOOR SINK WITH APPROVED AIR GAP.
- 11 INDIRECT WASTE FROM HOT FOOD TABLE(23) SINK TO FLOOR SINK WITH APPROVED AIR GAP.
- 12 CONDENSATE DRAIN FROM WALK-IN COOLER TO FLOOR SINK WITH APPROVED AIR GAP.

Property of NY Engineers

GENERAL NOTES:	
A.	CW/HW PIPING TO BE PROVIDED WITH INSULATION AS PER INTERNATIONAL ENERGY CODE 2018 (REFER SHEET P.01)
B.	REFER RISER DIAGRAMS FOR PIPE SIZING.
C.	PROVIDE BRANCH PRV IF PRESSURE EXCEEDS 80 PSI.
D.	CONTRACTOR TO FIELD VERIFY FEASIBILITY OF SLAB PENETRATION AS PER STRUCTURAL REQUIREMENT.
E.	PROVIDE ACCESS PANELS FOR WATER HAMMER ARRESTOR, CLEANOUTS & SHUT-OFF VALVES AS REQUIRED.


3	BULLETIN 3	02/25/25
	PERMIT SET	01/30/25
	90% PROGRESS	01/24/25

ROOTS NATURAL KITCHEN

PLUMBING WATER AND GAS FLOOR PLAN

① PLUMBING WATER AND GAS FLOOR PLAN
1/4" = 1'-0"

06'1" 2' 4' 8'



GENERAL NOTES:

- CW/HW PIPING TO BE PROVIDED WITH INSULATION AS PER INTERNATIONAL ENERGY CODE 2018 (REFER SHEET P.01)
- REFER RISER DIAGRAMS FOR PIPE SIZING.
- PROVIDE BRANCH PRV IF PRESSURE EXCEEDS 80 PSI.
- CONTRACTOR TO FIELD VERIFY FEASIBILITY OF SLAB PENETRATION AS PER STRUCTURAL REQUIREMENT.
- PROVIDE ACCESS PANELS FOR WATER HAMMER ARRESTOR, CLEANOUTS & SHUT-OFF VALVES AS REQUIRED.


PLUMBING WATER AND GAS KEYED NOTES:

- EXTEND AND CONNECT NEW 1-1/2" CW PIPING TO THE PROPOSED 1-1/2" WATER LINE FROM WATER METER AND BFP. CONTRACTOR TO FIELD VERIFY PROPOSED WATER LINE LOCATION AND SIZE. REFER CIVIL SITE UTILITY PLAN FOR MORE DETAILS.
- PROVIDE ASSE 1070 OR SIMILAR THERMOSTATIC MIXING VALVE AT ALL HAND SINK AND LAVATORIES. SET AT 110°F MAXIMUM.
- ROUTE CONDENSATE DRAIN FROM PROPOSED WATER HEATER TO THE FLOOR DRAIN WITH APPROVED AIR GAP.
- PROVIDE ASSE 1022 APPROVED BACKFLOW PREVENTOR (BFP) FOR ICE MAKER.
- PROVIDE ADEQUATE INLET PRESSURE TO WATER HEATER, GRIDDLE AND MECHANICAL EQUIPMENTS.
- CONTRACTOR TO COORDINATE WATER FILTRATION SYSTEM LOCATION WITH ARCHITECT AND ROUTE PIPING ACCORDINGLY.
- 1/2" FILTERED WATER TO ICE AND WATER DISPENSER(43).

3	BULLETIN 3	02/25/25
	PERMIT SET	01/30/25
	90% PROGRESS	01/24/25

ROOTS NATURAL KITCHEN

GAS ROOF PLAN



GENERAL NOTES:

- CONTRACTOR TO FIELD VERIFY FEASIBILITY OF SLAB PENETRATION AS PER STRUCTURAL REQUIREMENT.
- REFER RISER DIAGRAMS FOR ALL PIPE SIZES.
- PROVIDE GAS PRESSURE REGULATOR ON EACH GAS FIRED EQUIPMENT IF REQUIRED.



PLUMBING WATER AND GAS KEYED NOTES:

- CONNECT NEW 2-1/2" GAS LINE TO EXISTING GAS LINE AVAILABLE IN SPACE. CONTRACTOR TO FIELD VERIFY EXISTING GAS LINE LOCATION AND SIZE. UPGRADE EXISTING PIPE SIZE IF REQUIRED.
- PROVIDE ADEQUATE INLET PRESSURE TO WATER HEATER, GRIDDLE AND MECHANICAL EQUIPMENT.


ROOTS NATURAL KITCHEN

PLUMBING DETAILS
(01 OF 02)


P3.0



3	BULLETIN 3	02/25/25
	PERMIT SET	01/30/25
	90% PROGRESS	01/24/25



ROUTE PIPE INCONSPICULOUSLY AND UNOBTRUSIVELY, SECURED BY MEANS OF CLAMPS OR BRACKETS TO THEIR OWN EQUIPMENT UNITS AND ROUTED TO THEIR SPECIFIC FLOOR SINKS. THERE SHALL NOT BE ANY LOOSE OR DANGLING WASTE LINES, NOR WASTE LINES LYING ON THE FLOOR. DO NOT INSULATE INDIRECT DRAIN PIPE WHEN INSTALLED EXPOSED IN FOOD SERVICE FACILITY. REFER TO LOCAL CODES FOR FURTHER INFORMATION.



1 INDIRECT/CONDENSATE DRAIN

P3.1 N.T.S

2 FLOOR CLEANOUT DETAIL
P3.1 N.T.S

FLOOR SINK DETAILS


3
P3.1 N.T.S

FINISHED FLOOR
DOME STRAINER
FLOOR SINK GRATE
INSIDE CAULK
4" DEEP SEAL "P" TRAP


VE
TE
TYPICAL UNION
DIAL TYPE PRESSURE GAUGE (0-100 PSI)
GAUGE COCK
AQUASTAT
IN-LINE CIRCULATION

4 INLINE RECIRCULATING PUMP DETAIL


P3.1 N.T.S



5 GAS FIRED HOT WATER HEATER (FLOOR MOUNTED) DETAIL
P3.1 N.T.S



6 3 COMPARTMENT SINK DETAILS



7 HOT WATER HEATER BALANCING VALVE PIPING DETAIL
P3.1 N.T.S

3 BULLETIN 3 02/25/25
PERMIT SET 01/30/25
90% PROGRESS 01/24/25

ROOTS NATURAL KITCHEN

PLUMBING FIXTURE SCHEDULE

LEGEND	PLUMBING FIXTURE	CONNECTION SIZE - INCHES						
		TRAP	SOIL/WASTE	VENT	COLD WATER	HOT WATER	THERMOSTATIC MIXING VALVE	
WC-1	WATER CLOSET	4"	4"	2"	3/4"	-	-	FLUSH TANK
LAV-1	LAVATORY	1/2"	2"	1 1/2"	1/2"	1/2"	PROVIDE	P-TRAP
MS-1	MOP SINK	3"	3"	2"	3/4"	3/4"	PROVIDE	P-TRAP
UR-1	URINAL	2"	2"	1 1/2"	3/4"	-	PROVIDE	P-TRAP
3	DROP IN HOT FOOD WELL	-	3/4"	-	-	-	-	IW TO FLOOR SINK
4&5	DROP IN COLD FOOD WELL	-	3/4"	-	-	-	-	IW TO FLOOR SINK
6	DROP IN HOT FOOD WELL	-	3/4"	-	-	-	-	IW TO FLOOR SINK
14	HAND SINK	2"	2"	1 1/2"	1/2"	1/2"	-	P-TRAP
17	GRIDDLE	-	-	-	-	-	-	-
19	HOT FOOD TABLE	-	1/2"	-	-	-	-	IW TO FLOOR SINK
23	HOT FOOD TABLE	-	1/2"	-	-	-	-	IW TO FLOOR SINK
27	DOOR TYPE DISH MACHINE	-	3"	-	3/4"	3/4"	-	IW TO FLOOR SINK
29	PRE-RINSE FAUCET	2"	3"	2"	1/2"	1/2"	-	P-TRAP
31	3-COMP. SINK	-	3"	-	3/4"	3/4"	-	IW TO FLOOR SINK
40	2-COMP. SINK	-	3"	-	3/4"	3/4"	-	IW TO FLOOR SINK
43	ICE AND WATER DISPENSER	-	1/2"	-	1/2"	-	-	IW TO FLOOR SINK
51	KETTLE/POT FILLER FAUCET	-	1/2"	-	1/2"	-	-	IW TO FLOOR SINK
FS-1	FLOOR SINK	3"	3"	2"	-	-	-	-

NOTE: CONTRACTOR TO COORDINATE WITH ARCHITECTURAL DRAWINGS FOR ALL PLUMBING FIXTURES SPECIFICATIONS AND MOUNTING HEIGHT INSTALLATION.

Fixture Unit Calculation

TAG	QTY	EQUIPMENT	Fixture Units			
			D.F.U.	TOTAL D.F.U.	W.S.F.U.	TOTAL W.S.F.U.
WC-1	2	WATER CLOSET	6	12	5	10
LAV-1	2	LAVATORY	1	2	0.5	1
MS-1	1	MOP SINK	5	5	2.25	2.25
UR-1	1	URINAL	4	4	5	5
3	1	DROP IN HOT FOOD WELL	-	-	0.25	0.25
4&5	1	DROP IN COLD FOOD WELL	-	-	0.25	0.25
6	1	DROP IN HOT FOOD WELL	-	-	0.25	0.25
14	3	HAND SINK	1	3	0.5	1.5
17	1	GRIDDLE	-	-	-	-
19	2	HOT FOOD TABLE	-	-	0.25	0.5
23	2	HOT FOOD TABLE	-	-	0.25	0.5
27	1	DOOR TYPE DISH MACHINE	-	-	2	2
29	2	PRE-RINSE FAUCET	-	-	0.25	0.5
31	1	3-COMP. SINK	-	-	3	3
40	1	2-COMP. SINK	-	-	3	3
43	1	ICE AND WATER DISPENSER	-	-	0.25	0.25
51	1	KETTLE/POT FILLER FAUCET	-	-	0.25	0.25
FS-1	11	FLOOR SINK	5	55	-	-
TOTAL FIXTURE UNITS			81		30.5	

W.S.F.U. VALUES AS PER INTERNATIONAL PLUMBING CODE 2018 (IPC 2018) TABLE E
103.3(2) = 30.50 W.S.F.U.

D.F.U. VALUES AS PER INTERNATIONAL PLUMBING CODE 2018 (IPC 2018) TABLE 709.1 FOR
B1 D.F.U. = 4" PIPING HORIZONTAL @ 1/8" PER FOOT SLOPE.

NOTE -
AS PER 2018 INTERNATIONAL PLUMBING CODE SECTION 610.1, THE SYSTEM OR PART THEREOF SHALL BE FILLED WITH A WATER/CHLORINE SOLUTION CONTAINING NOT LESS THAN 50 PARTS PER MILLION (50 MG/L) OF CHLORINE AND THE SYSTEM OR PART THEREOF SHALL BE VALVED OFF AND ALLOWED TO STAND FOR 24 HOURS; OR THE SYSTEM OR PART THEREOF SHALL BE FILLED WITH A WATER/CHLORINE SOLUTION CONTAINING NOT LESS THAN 200 PARTS PER MILLION (200 MG/L) OF CHLORINE AND ALLOWED TO STAND FOR 3 HOURS.

GAS TYPE STORAGE WATER HEATER SCHEDULE

TAG No.	QUANTITY	LOCATION	INPUT (BTU/HR)	STOR. CAP (GAL)	RECOVERY CAP. (GPH) @90° RISE	TYPE	MANUFACTURER & MODEL NO.	REMARKS
WH-1	1	UTILITY ROOM	199,000	100	261	GAS STORAGE TYPE WATER HEATER (FLOOR MOUNTED)	A.O.SMITH BTH-199(A)	-DIMENSIONS 27-3/4"D X 75-1/2"H -PROVIDE EXPANSION TANK (ET-1) AS PER SCHEDULE -FLOOR MOUNTED

NOTE: NSF RATED. PROVIDE CONDENSATE COLLECTOR, DRAIN TO FLOOR DRAIN. PROVIDE WITH VACUUM RELIEF VALVE. MOUNT ON FLOOR & COORDINATE EXACT LOCATION WITH OWNER IN FIELD.

PIPE INSULATION : PROVIDE HOT WATER PIPING WITH 1" INSULATION HAVING CONDUCTIVITY OF 0.27BTU PER INCH.

PUMP SCHEDULE

TAG	DESCRIPTION	TYPE	CAPACITY		ELECTRICAL DATA			SELECTION BASED ON		REMARKS/OPTIONS
			GPM	HEAD (ft.)	HP	V	PH	MANUFACTURER	MODEL NUMBER	
RCP-1	HOT WATER RECIRC. PUMP	IN-LINE	2.0	9	1/12	120	1	BELL & GOSSETT	PL-30-B	NOTE 1,2
OPTIONS (ALL RCP UNITS)										
• AQUA-STAT & NIGHT TIMER • BALANCING VALVE & CHECK VALVE										
• FLANGED PUMP • MAINTENANCE BALL VALVES ON BOTH SIDES OF PUMP										

NOTES:

1. SET AQUA-STAT WITH SET POINT 10 DEGREES BELOW SYSTEM SUPPLY TEMP.

2. INSTALL RECIRCULATION PUMP PER MANUFACTURER'S REQUIREMENTS.

EXPANSION TANK

UNIT	QUANTITY	MANUFACTURER & MODEL NUMBER	SERVICE	TANK VOLUME (GAL)	MAX. ACCEPTANCE VOLUME (GAL)	PRESSURE RATING (PSI)	DIMENSIONS		OPERATING WEIGHT (LBS)	MOUNTING	NOTES
ET-1	1	AMTROL	ST-12C-DD	6.4	3.2	150	12	18	17	NEAR WH-1	1,2

GENERAL NOTES:

1. SET THE TANK PRESSURE TO EQUAL THE SYSTEM OPERATING PRESSURE. TANK MUST BE DRAINED BEFORE ADJUSTING SET PRESSURE.

2. INSTALL PER MANUFACTURER'S RECOMMENDATIONS ON INCOMING COLD WATER LINE.

GREASE INTERCEPTOR SIZING CALCULATION

Fixture	Quantity	Dimensions		Volume	Percentage Usage(%)	Actual Usage (Gallons)	Flow Rate(GPM)	
		Length						

DRAWN
 CHECKED
 PROJECT NO.

NYE
 NYE
 240720

ROOTS NATURAL KITCHEN

PLUMBING RISER DIAGRAMS

P4.1

