


MECHANICAL PLAN NOTES

- 1 EXTEND FULL SIZE SUPPLY & RETURN DUCTWORK FROM 4-TON ROOFTOP UNIT TO SPACE. EXTEND AS SHOWN. ACOUSTICALLY LINE THE FIRST 10'-0" OF BOTH SUPPLY AND RETURN MAIN DUCTS.
- 2 INSTALL AND WIRE NEW 7-DAY PROGRAMMABLE THERMOSTAT. COORDINATE EXACT LOCATION WITH ARCHITECT AND OWNER PRIOR TO ROUGH-IN.
- 3 ROUTE 10" EXHAUST DUCT UP THROUGH ROOF WITH TALL CONE FLASHING, WEATHER SKIRT, AND VENT CAP. MAINTAIN A MINIMUM OF 10'-0" FROM ALL OUTSIDE AIR INTAKES AND TERMINATES 36" ABOVE ROOF.
- 4 PROVIDE 4" DRYER VENT & RECESSED DRYER BOX. EXTEND TO EXTERIOR WITH DRYER VENT CAP. PROVIDE INLINE BOOSTER FAN AS NECESSARY PER MANUFACTURER INSTRUCTIONS.


BRANCH DUCT SIZE	
CFM	DUCT SIZE
0-100	6"
101-250	8"
251-400	10"
401-650	12"

MECHANICAL ROOFTOP PLAN NOTES


- 1 PROVIDE AND INSTALL NEW ROOFTOP UNIT. PROVIDE FLEXIBLE CONNECTORS ON SUPPLY AND RETURN DUCT CONNECTIONS. SET OUTSIDE AIR AS INDICATED ON ROOFTOP UNIT SCHEDULES. MECHANICAL CONTRACTOR SHALL SCRIBE INTO UNIT POSITION OF OUTSIDE AIR DAMPER AND LABEL OUTSIDE AIR VOLUME AND PERCENT OF OUTSIDE AIR.
- 2 10" EXHAUST DUCT UP THROUGH ROOF WITH TALL CONE FLASHING, WEATHER SKIRT, AND VENT CAP. MAINTAIN A MINIMUM OF 10'-0" FROM ALL OUTSIDE AIR INTAKES AND TERMINATES 36" ABOVE ROOF.



1 MECHANICAL FIRST FLOOR PLAN  
SCALE: 1/4" = 1'-0"



2 MECHANICAL ROOF FLOOR PLAN  
SCALE: 1/4" = 1'-0"



LUMINAIRE SCHEDULE:

Fixture Type	LAMP	WATTAGE	VOLTAGE	DESCRIPTION	CATALOG NUMBER
A	MFPEL LED	50W	120	MFPEL LED FLAT PANEL 2X4 WITH FROSTED LENS AND WHITE, ALUMINUM HOUSING.	MOBERN LIGHTING #MFPEL24-LED50-DMVWH40
B	MFPEL LED	40W	120	MFPEL LED FLAT PANEL 2X2 WITH FROSTED LENS AND WHITE, ALUMINUM HOUSING.	MOBERN LIGHTING #MFPEL22-LED40-DMVWH40
C	700MHU D	9W	120	4" DIAMETER PENDANT LIGHT FIXTURE. VERIFY SUSPENSION HEIGHT WITH ARCHITECT.	TECH LIGHTING #700MP-WS-LED5930
EX1	LED	2W	120	CEILING MOUNTED EXIT (TYPE X) SIGN FIXTURE LED ILLUMINATED, EMERGENCY BATTERY PACK BACKUP.	COMPASS #CER
BP1	LED	1W	120	WALL MOUNTED EMERGENCY LIGHT FIXTURE. ADJUSTABLE HEADS EBU TYPE.	COMPASS #CU2
BP2	LED	5W	120	EXTERIOR WALL MOUNTED EMERGENCY LIGHT FIXTURE.	EXITRONIX #LL6-18-0-W-NO HEADS

LUMINAIRE SCHEDULE GENERAL NOTES:



1. VERIFY ALL LUMINAIRE COLORS, TRIMS, LENGTHS, ETC. WITH THE ARCHITECT PRIOR TO PLACING FINAL PURCHASE ORDERS. SUBMISSION PF SHOP DRAWINGS WILL BE INTERPRETED AS HAVING BEEN COORDINATED WITH THE ARCHITECTURAL DRAWINGS .
2. PROVIDE ALL LENGTHS, FEEDS, ACCESSORIES, CONNECTORS, WIRING, POWER SUPPLIES, DRIVERS ETC. FOR A COMPLETE INSTALLATION. THE E.C. SHALL VERIFY THE COMPLETE BILL OF MATERIAL WITH MANUFACTURER'S REPRESENTATIVE AND ENSURE ALL EQUIPMENT ARE INCLUDED IN BID PRICE. COORDINATE INSTALLATION WITH ARCHITECTURAL DETAILS.
3. VERIFY FINAL LUMINAIRE LOCATIONS WITH OTHER CEILING MOUNTED EQUIPMENTS SUCH AS DIFFUSER WITH ARCHITECTURAL REFLECTED CEILING PLANS.
4. VERIFY EXACT MOUNTING HEIGHT AND LOCATIONS OF ALL WALL MOUNTED LUMINAIRE WITH ARCHITECTURAL PLANS AND ELEVATIONS PRIOR TO ROUGH-IN
5. CONNECTIONS TO RECESSED LUMINAIRES SHALL BE MADE WITH MINIMUM 1/2" FLEXIBLE METAL CONDUIT (FMC) FROM LUMINAIRE TO OUTLET BOX. LENGTH OF FMC SHALL NOT CONNECTIONS TO RECESSED LUMINAIRES SHALL BE MADE WITH MINIMUM 1/2" FLEXIBLE METAL CONDUIT (FMC) FROM LUMINAIRE TO OUTLET BOX. LENGTH OF FMC SHALL NOT EXCEED 6'-0".
6. AT THE CONCLUSION OF WORK, EACH LUMINAIRE SHALL BE CLEANED AND EQUIPPED WITH THE PROPER TYPE, NUMBER OF LAMPS, INCLUDING KELVIN TEMPERATURE AND WATTAGE, AT THE CONCLUSION OF WORK, EACH LUMINAIRE SHALL BE CLEANED AND EQUIPPED WITH THE PROPER TYPE, NUMBER OF LAMPS, INCLUDING KELVIN TEMPERATURE AND WATTAGE, ALL IN GOOD OPERATING CONDITION
7. ALL LIGHTING SUPPLIES MUST BE PURCHASED FROM "CED NATIONAL ACCOUNTS". CONTACT JEREMY WEST, NATIONAL ACCOUNTS REPRESENTATIVE, (817) 923-1983, ALL LIGHTING SUPPLIES MUST BE PURCHASED FROM "CED NATIONAL ACCOUNTS". CONTACT JEREMY WEST, NATIONAL ACCOUNTS REPRESENTATIVE, (817) 923-1983, JEREMY.WEST@CED.COM.

ELECTRICAL LIGHTING PLAN KEYED WORK NOTES:

1. EXHAUST FAN IN THIS ROOM SHALL BE CONTROLLED ALONG WITH THE LIGHT FIXTURES.
2. CONNECT ALL EMERGENCY EGRESS AND NIGHT LIGHTING FIXTURES TO NEAREST LIGHTING BRANCH CIRCUIT AHEAD OF ALL SWITCHING AND CONTROLS PER STATE AND LOCAL CODES. EXIT SIGNS SHALL NOT EXCEED 5 WATTS PER FACE.
3. PROVIDE POWER/JUNCTION BOX(ES) FOR EXTERIOR SIGNAGE. COORDINATE EXACT LOCATION WITH SIGNAGE PROVIDER. CIRCUIT EXTERIOR SIGN(S) TROUGH LCP. VERIFY QUANTITY AND LOCATION WITH ARCHITECTURAL DRAWINGS.
4. LIGHT FIXTURES IN THIS AREA SHALL BE CONTROLLED BY DAYLIGHT SENSOR.

GENERAL LIGHTING PLAN NOTES


1. ALL EXIT SIGNS, EMERGENCY LIGHTING BATTERY PACKS, EMERGENCY LUMINAIRES (ON GENERATOR OR EMERGENCY LIGHTING BATTERY PACKS INTEGRAL TO LUMINAIRES), AND NIGHT LIGHTS (DENOTED "NL") SHALL BE CONNECTED TO THE LOCAL LIGHTING CIRCUIT AHEAD OF ANY CONTROLS SUCH AS: SWITCHES (DEVICE), OCCUPANCY SENSORS AND/OR RELAY CONTROLS.
2. EXACT LOCATION OF ALL LUMINAIRES, AND EXACT MOUNTING HEIGHT OF ALL PENDANT MOUNTED LUMINAIRES SHALL BE COORDINATED WITH ARCHITECTURAL DRAWINGS PRIOR TO ANY ROUGH-INS.
3. MINIMUM CONDUCTOR SIZE FOR 120 VOLT BRANCH CIRCUITS SHALL BE 12-AWG. FOR 120 VOLT BRANCH CIRCUITS WITH HOMERUNS OVER 100 LINEAR FEET, A MINIMUM WIRE SIZE OF 10-AWG SHALL BE PROVIDED FROM FIRST JUNCTION/OUTLET BOX TO BRANCH CIRCUIT PANELBOARD. FOR 120 VOLT BRANCH CIRCUITS WITH HOMERUN OVER 150 LINEAR FEET, A MINIMUM WIRE SIZE OF 8-AWG SHALL BE PROVIDED FROM FIRST JUNCTION/OUTLET BOX TO BRANCH CIRCUIT PANELBOARD.
4. ALL WIRING SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBER(S) IN ALL CABINETS, JUNCTION BOXES, WIRING TROUGHS, ENCLOSURES, SPLICE OR TERMINATION POINTS, ETC.
5. A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.



OCCUPANCY SENSOR SWITCH WIRING DIAGRAM  
SCALE: N.T.S.

NOTES:

1. ALL LOW VOLTAGE WIRING AND TERMINATIONS TO BE BY ELECTRICAL CONTRACTOR.
2. OCCUPANCY/VACANCY SENSOR SHALL BE "SENSOR SWITCH" WSX-PDT-SA-WH OR APPROVED EQUAL. ALL EXPOSED CONTROL WIRING SHALL BE IN CONDUIT.




PANELBOARDS																		
PANEL:	A (EXISTING)														MOUNTING:		SURFACE	
208Y/120	VOLTS,		3	PHASE,		4	WIRE											
MAIN CB	225A			BUS		225A	MIN,	INTERRUPTING RATING			22 KAIC							
CKT NO.	TRIP AMPS	DESCRIPTION OF LOAD			LOAD TYPE	LOAD (KVA)	PER PHASE (KVA)			LOAD (KVA)	LOAD TYPE	DESCRIPTION OF LOAD			TRIP AMPS	CKT NO.		
							A	B	C									
1	20	LIGHTING			L	0.65	1.65			1.00	E	COLDPACK FRIDGE			20	2		
3	20	LIGHTING			L	0.60		1.6		1.00	E	HYDROCOLLATOR/COLD PACK			20	4		
5	20	EM/NIGHT LIGHTING			L	0.20			0.56	0.36	R	BOH RECEPTACLE			20	6		
7	20	RESTROOM+BOH LIGHTING			L	0.55	1.75			1.20	E	ELECTRIC WATER COOLER			20*	8		
9	20	EXTERIOR SIGNAGE			L	0.10		0.46		0.36	R	RESTROOM RECEPTACLES			20*	10		
11	20	LCP			E	0.10			1.3	1.20	E	MICROWAVE			20	12		
13	20	WAITING AREA/DESK RECEPTACLE			R	0.54	1.74			1.20	E	FRIDGE			20*	14		
15	20	PRINTER RECEPTACLE			R	0.36		1.56		1.20	R	LAUNDRY RECEPTACLE			20*	16		
17	20	HOSPITALITY RECEPTACLE			R	0.36			1.56	1.20	R	DATA CLOSET/LCP			20	18		
19	20	TREATMENT RECEPTACLE			R	1.08	2.28			1.20	R	TTB			20	20		
21	60/2P	TO PANEL B			E	6.11		7.31		1.20	R	LAUNDRY/MECH RECEPTACLE			20*	22		
23					E	6.11			8.99	2.88	H					24		
25		RECEPTACLES			R	0.36	3.24			2.88	H	RTU-1			45*12P	26		
27		TREATMENT RECEPTACLE			R	0.36		3.24		2.88	H					28		
29		SHOW WINDOW RECEPTACLE			R	0.36			3.24	2.88	H					30		
31	20	TV RECEPTACLE			R	0.36	3.24			2.88	H	RTU-2			45*12P	32		
33	20	TREATMENT RECEPTACLE			R	1.08		3.96		2.88	H					34		
35	20	COUNTER RECEPTACLE			R	0.18			0.28	0.10	L	EXTERIOR LIGHTING			20	36		
37	20	ICE MAKER DISPENSER			R	0.18	0.18					SPARE			20	38		
39	20	HOSPITALITY RECEPTACLE			R	0.18		0.18				SPARE			20	40		
41	20	SPARE							0			SPARE			20	42		
TOTAL LOAD (KVA)						14.08	18.31	15.93	PANEL DATA			TOTAL	LTG	HVAC		REC	EQUI.	MISC.
TOTAL LTG		2.2	X	1.00 DEM	=	2.2												
TOTAL HVAC		17.28	X	1.00 DEM	=	15.552			KW PHASE A	14.08	1.20	5.76		3.72	3.40	0.00		
TOTAL RECEPT.		10.92	X	1.00 DEM	=	5.46			KW PHASE B	18.31	0.70	5.76		4.74	7.11	0.00		
TOTAL EQUI.		17.92	X	0.65 DEM	=	12.544			KW PHASE C	15.93	0.30	5.76		2.46	7.77	0.00		
TOTAL MISC.		0	X	0.70 DEM	=	0												


PANEL: B (NEW)												MOUNTING: SURFACE					
208Y/120	VOLTS,		1	PHASE,		3	WIRE										
MAIN CB		60A				BUS		100A		MIN,		INTERRUPTING RATING		22 KAIC			
CKT NO.	TRIP AMPS	DESCRIPTION OF LOAD				LOAD TYPE	LOAD (KVA)	PER PHASE (KVA)		LOAD (KVA)	LOAD TYPE	DESCRIPTION OF LOAD				TRIP AMPS	CKT NO.
								A	B								
1	20/2P	TREADMILL RECEPTACLE				R	0.18	2.68		2.50	E	WATER HEATER (WH-1)				30*12P	2
3		TREADMILL RECEPTACLE				R	0.18		2.68	2.50	E						4
5		TREADMILL RECEPTACLE				R	0.18	2.68		2.50	E	DRYER					6
7	20/2P	TREADMILL RECEPTACLE				R	0.18		2.68	2.50	E					30*12P	8
9		20	FSD				H	0.10	1.6		1.50	E	WASHER				20*
11	20*	ROOF RECEPTACLE				R	0.36		0.36			SPARE				20	12
13	20	SPARE						0				SPARE				20	14
15	20	SPARE							0			SPARE				20	16
17	20	SPARE						0				SPARE				20	18
19	20	SPARE							0			SPARE				20	20
21	20	SPARE						0				SPARE				20	22
23	20	SPARE							0			SPARE				20	24
25	20	SPARE						0				SPARE				20	26
27	20	SPARE							0			SPARE				20	28
29	20	SPARE						0				SPARE				20	30
				TOTAL LOAD (KVA)				6.96	5.72								
TOTAL LTG		0.00	X	1.00 DEM	=	0.00											
TOTAL HVAC		0.10	X	0.90 DEM	=	0.09		PANEL DATA		TOTAL		LTG		HVAC		REC	
TOTAL RECEPT.		1.08	X	0.50 DEM	=	0.54		KW PHASE A		6.96		0.00		0.10		0.36	
TOTAL EQUIP.		11.50	X	0.70 DEM	=	8.05		KW PHASE B		5.72		0.00		0.00		0.72	
TOTAL MECH.		0.00	X	0.80 DEM	=	0.00											

ABBREVIATIONS:	NOTE:
L = LIGHTING , R = RECEPTACLE , H = HVAC , E = EQUI. , M = MISCELLANEOUS	- * INDICATES GFCI CIRCUIT BRAEKERS.

ELECTRICAL RISER DIAGRAM



PATIENT CARE AREA WIRING NOTE:  
WIRING IN PATIENT CARE AREAS AND EXAM ROOMS SHALL COMPLY WITH NEC ARTICLE 517.13. ALL BRANCH CIRCUITS SHALL BE PROVIDED WITH AN EFFECTIVE GROUND-FULT CURRENT PATH BY INSTALLATION IN A METAL RACEWAY SYSTEM OR CABLE HAVING A METALLIC ARMOR ASSEMBLY. THE ASSEMBLY OR RACEWAY SHALL ITSELF QUALIFY AS AN EQUIPMENT GROUNDING CONDUCTOR IN ACCORDANCE WITH NEC 250.118. PROVIDE INSULATED COPPER EQUIPMENT GROUNDING CONDUCTOR WITHIN OR PART OF THE ASSEMBLY OR RACEWAY AND BOND RECEPTACLES AND ALL NON-CURRENT CARRYING CONDUCTIVE SURFACES OR FIXED ELECTRICAL EQUIPMENT. SIZE GROUNDING CONDUCTOR IN ACCORDANCE WITH TABLE 250.122.



1 POWER PLAN  
SCALE: 1/4" = 1'-0"

ELECTRICAL POWER PLAN KEYED WORK NOTES:


- DATA AND POWER FOR TV. STUB DATA CONDUIT TO 6" ABOVE CEILING WITH PULL STRING. COORDINATE EXACT LOCATION WITH ARCHITECTURAL PLANS PRIOR TO ROUGH IN.
- RECEPTACLE FOR EXERIOSE EQUIPMENT. COORDINATE EXACT LOCATION WITH ARCHITECTURAL PLANS PRIOR TO ROUGH-IN. CONFIRM POWER REQUIREMENT OF THE EQUIPMENTS WITH OWNER/VENDOR.
- ELECTRICAL FLOOR BOX TO BE LEGRAND (RFB4E) WITH EVOLUTION COVER. ENSURE CONCRETE ABOVE FLOOR BOX IS SMOOTH AND LEVEL. PROVIDE (3) RFB6DP AND (1) RFB6B BRACKETS FOR EQUIPMENT INSTALLATION (NO SUBSTITUTIONS).
- ELECTRICAL DRYER (208V, 1-PH, 5KW): PROVIDE A NEMA 6-30R RECEPTACLE AND TYPE "SO" CORD AND MATCHING PLUG. WIRING SHALL BE 2#10, 1#10(G), 3/4"C. COORDINATE EXACT LOCATION WITH ARCHITECTURAL PLANS PRIOR TO ROUGH-IN.
- ROOFTOP UNITS RTU-1 & RTU-2 (30MCA-208V-3 PH): PROVIDE A 60A-3P UNFUSED DISCONNECT SWITCH MOUNTED ON/AT UNIT AS REQUIRED. COORDINATE FINAL LOCATION IN FIELD. WIRING SHALL BE 3#8, 1#10 (G), 3/4"C. TO THE 45A-3P CIRCUIT BREAKER INDICATED ON DRAWING. COORDINATE WITH MECHANICAL DRAWINGS FOR EXACT LOCATION OF ROOFTOP UNITS.
- COORDINATE EQUIPMENT RECEPTACLE LOCATION AND MOUNTING HEIGHT WITH ARCHITECTURAL ELEVATIONS PRIOR TO ROUGH-IN.
- RECEPTACLE FOR TELECOM EQUIPMENT. COORDINATE EXACT LOCATION WITH ARCHITECTURAL PLANS PRIOR TO ROUGH IN.
- MICROWAVE RECEPTACLE. COORDINATE EXACT LOCATION WITH ARCHITECTURAL PLANS PRIOR TO ROUGH-IN.
- TREATMENT TABLE RECEPTACLE. COORDINATE EXACT LOCATION WITH ARCHITECT.
- WATER HEATER (208V-1, 5 KW): PROVIDE 30A 2-POLE HEAVY DUTY DISCONNECT SWITCH AT UNIT. WIRING SHALL BE 2#10, 1#10(G), 3/4"C. COORDINATE EXACT LOCATION WITH
- RECEPTACLE FOR THE SHOW WINDOW. COORDINATE EXACT LOCATION WITH ARCHITECT PRIOR TO ROUGH-IN.

2 PROPOSED ROOF PLAN  
SCALE: 1/4" = 1'-0"

GENERAL POWER PLAN NOTES:

- EXACT LOCATION OF MECHANICAL, PLUMBING, KITCHEN, FURNITURE SYSTEMS, OWNER FURNISHED EQUIPMENT ETC. THAT REQUIRE ELECTRICAL CONNECTIONS ARE SHOWN ON THE MECHANICAL, PLUMBING, AND/OR ARCHITECTURAL DRAWINGS. COORDINATE EXACT LOCATIONS WITH RESPECTIVE CONTRACTORS AND/OR VENDORS PRIOR TO ANY ROUGH-INS.
- REVIEW AND COORDINATE WITH ALL TRADES CONTRACT DOCUMENTS TO DETERMINE SPECIFIC MOUNTING LOCATIONS FOR EQUIPMENT WITH ELECTRICAL CONNECTIONS. COORDINATE EXACT MOUNTING LOCATIONS WITH THE SPECIFIC TRADE AND ARCHITECT.
- MINIMUM CONDUCTOR SIZE FOR 120V BRANCH CIRCUITS SHALL BE 12-AWG. FOR 120V BRANCH CIRCUITS WITH HOMERUN OVER 100 LINEAR FEET, A MINIMUM WIRE SIZE OF 10-AWG SHALL BE PROVIDED FROM FIRST JUNCTION/OUTLET BOX TO BRANCH CIRCUIT PANELBOARD. FOR 120V BRANCH CIRCUITS WITH HOMERUN OVER 150 LINEAR FEET, A MINIMUM OF 8-AWG SHALL BE PROVIDED FROM FIRST JUNCTION/OUTLET BOX TO BRANCH CIRCUIT PANELBOARD.
- ALL WIRINGS SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBERS IN ALL CABINETS, JUNCTION BOXES, WIRING TROUGHS, ENCLOSURES, SPLICE OR TERMINATION POINTS, ETC.
- A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.






1 DOMESTIC WATER & GAS PIPING PLAN  
SCALE: 1/4" = 1'-0"

DOMESTIC WATER AND GAS PIPING PLAN NOTES:


- ROUTE NEW 1" CW PIPING WITH SHUT OFF VALVE AND TIE-INTO THE EXISTING WATER SERVICE. CONTRACTOR TO FIELD VERIFY SIZE, ROUTING AND ANY WATER SUBMETER REQUIREMENTS WITH LANDLORD PRIOR TO BID.
- PROVIDE A TEMPERING VALVE FOR LAVATOIRES. POWER HYFROGUARD SERIES LM495, ASSE. 1070 OR EQUAL. SET TEMPERATURE TO A MAXIMUM OF 110° F.
- ROUTE T&P RELIEF TO DRAIN IN MOP SINK.
- TRAP PRIMER (TP-1) EXTEND AND CONNECT 1/2" TRAP PRIMER PIPING TO FLOOR DRAINS WITH TRAP PRIMER CONNECTIONS. COORDINATE ROUTING.
- CONTRACTOR TO INSTALL NEW EXPANSION TANK THERM-X-TROL MODEL ST-5, 2 GAL PER LOCAL CODE REQUIREMENTS.
- ALL EXISTING GAS PIPING IS RUNNING ON ROOF, SHOWN ON PLAN FOR REFERENCE ONLY.
- CONTINUE EXISTING GAS PIPE LINE TO EXISTING GAS METER.



2 SANITARY PIPING PLAN  
SCALE: 1/4" = 1'-0"

SANITARY PIPING PLAN NOTES:

- CONNECT NEW 4" SANITARY WASTE PIPING TO EXISTING SANITARY WASTE LINE OF ADEQUATE SIZE. CONTRACTOR TO FIELD VERIFY SIZE, ROUTING AND INVERT ON SITE.
- CONTRACTOR TO FILED VERIFY AND CONNECT NEW 2" VENT TO EXISTING VENT IN EXISTING TOILET AREA.
- SANITARY PIPING RUNNING UNDERGROUND SHOWN FOR REFERENCE. CONTRACTOR TO COORDINATE WITH EXISTING STRUCTURAL AND REROUTE AS REQUIRED TO AVOID ANY CONFLICTS AS PER FILED CONDITIONS.



SANITARY ISOMETRIC DIAGRAM NOTES:


- CONNECT NEW 4" SANITARY WASTE PIPING TO EXISTING SANITARY WASTE LINE OF ADEQUATE SIZE. CONTRACTOR TO FIELD VERIFY SIZE, ROUTING AND INVERT ON SITE.
- CONTRACTOR TO FILED VERIFY AND CONNECT NEW 2" VENT TO EXISTING VENT IN EXISTING TOILET AREA.
- SANITARY PIPING RUNNING UNDERGROUND SHOWN FOR REFERENCE. CONTRACTOR TO COORDINATE WITH EXISTING STRUCTURAL AND REROUTE AS REQUIRED TO AVOID ANY CONFLICTS AS PER FILED CONDITIONS.

3 SANITARY ISOMETRIC RISER  
SCALE: N.T.S.




GAS PIPING NOTES:

- CONTRACTOR TO FIELD VERIFY AND CONNECT EXISTING GAS PIPING TO NEW ROOFTOP UNITS. VERIFY EXACT LOCATION OF BOTH THE RTU IN FIELD.
- VERIFY EXACT PRESSURE REQUIRED FOR THE NEW RTU.
- PROVIDE NEW SHUT-OFF VALVE, IF NOT EXISTING/DAMAGED/NOT IN GOOD CONDITION.
- CONTRACTOR TO FIELD VERIFY EXISTING AVAILABLE GAS PRESSURE AND MAKE SURE TO PROVIDE ADEQUATE INLET PRESSURE REQUIRED TO RTU-1 AND RTU-2. PROVIDE GAS BOOSTER PUMP IF INLET PRESSURE IS LESS THAN 7" W.C. BASE BID ACCORDINGLY.
- CONTRACTOR TO FIELD VERIFY EXISTING PIPE ROUTING AND ITS CONDITION, ACCORDINGLY PROVIDE NEW IF EXISTING IS DAMAGED OR NOT IN GOOD CONDITION.



4 GAS ISOMETRIC RISER  
SCALE: N.T.S.



PLUMBING SYMBOLS LIST

- SANITARY PIPING
- SAN SANITARY UNDERGROUND PIPING
- VENT PIPING
- COLD WATER PIPING
- HOT WATER PIPING
- HOT WATER RETURN PIPING
- G EXISTING GAS PIPING
- PIPE UP
- PIPE DROP
- SHUT-OFF VALVE
- EXIST. PLUG VALVE
- POINT OF NEW CONNECTION

FIXTURE CONNECTION SCHEDULE

MARK	FIXTURE	HW	CW	SAN	VENT
WC-1	ADA WATER CLOSET	--	3/4	4	2
LAV-1	ADA LAVATORY	1/2	1/2	1-1/2	1-1/2
MS-1	MOP SINK	1/2	1/2	3	1-1/2
DF-1	DRINKING FOUNTAIN	1/2	1-1/2	1-1/2	1-1/2
WH-1	WATER HEATER	3/4	3/4	--	--
FD-1	FLOOR DRAIN	--	--	3	--
CO-1	CLEANOUT	--	--	3	--
S-1	SINK	1/2	1/2	1-1/2	1-1/2
WB-1	WASHING MACHINE BOX	1/2	1/2	1-1/2	1-1/2
WD-1	WATER DISPENSER	--	1/2	--	--

GAS LOAD SUMMARY	
EQUIPMENT TAG	CFH LOAD
RTU-1	70
RTU-2	70
TOTAL GAS LOAD	140

EXPANSION TANK SCHEDULE

TAG	LOCATION	SERVICE	CAPACITY (GALLONS)	MANUFACTURER & MODEL	DIMENSION (DIA X HEIGHT)	WEIGHT (LBS)	NO. OF EXPANSION TANK
ET-1	REFER FLOOR PLANS	HW	2	THERM-X-TROL ST-5	8" X 13"	5	1

ELECTRIC STORAGE WATER HEATER SCHEDULE

HEATER TAG	NO. OF ELEMENTS	LOCATION	MAX. INPUT (kW)	STORAGE CAPACITY (GAL)	RECOVERY CAPACITY (GPH) @100° F RISE	TYPE	ELECTRICAL CHARACTERISTICS CONTROL	NO. OF HEATERS	EFFICIENCY (%)	MANUFACTURER & MODEL NO.	REMARKS
WH-1	1	ABOVE MOP SINK	5	30	20	ELECTRIC	208V/3Ø/60Hz	1	97	A.O.SMITH MODEL DEL-30	-DIMENSIONS: 22"DIA X 31"HIGH -PROVIDE ET-1 AS PER SCHEDULE -CEILING MOUNTED HEATER

NOTE: NSF RATED. PROVIDE CONDENSATE COLLECTOR, DRAIN TO MOP SINK. PROVIDE WITH VACUUM RELIEF VALVE. MOUNT ON CEILING & COORDINATE EXACT LOCATION WITH OWNER IN FIELD.  
PIPE INSULATION : PROVIDE HOT WATER PIPING WITH 1" INSULATION HAVING CONDUCTIVITY OF MINIMUM OF 0.27 BTU PER INCH.