


- MECHANICAL GENERAL NOTES**
- CONTRACTOR SHALL BALANCE EACH DEVICE WITH THE CFM SHOWN PLAN.
 - NEW PIPING AND DUCTWORK SHOWN ON PLAN ARE SCHEMATIC ONLY. CONTRACTOR SHALL COORDINATE WITH OTHER TRADES FOR PIPING AND DUCTWORK ROUTING. OFFSET AND RUN PIPING, DUCTWORK INSIDE THE STRUCTURE IF REQUIRED. PROVIDE ANY EXTRA PIPING, DUCTWORK, FITTINGS, INSULATIONS AND OTHER ACCESSORIES IN ORDER TO COMPLETE THE INSTALLATION.
 - COORDINATE LOCATIONS AND SIZES OF ROOF OPENINGS WITH OWNER AND STRUCTURE ENGINEERS.
 - EQUIPMENT SIZES, DIMENSIONS AND REQUIRED CONNECTIONS SHALL BE VERIFIED WITH THE ACTUAL EQUIPMENT SELECTED VENDOR DRAWINGS BEFORE FABRICATION OF DUCTWORK, PIPING ETC.
 - DUCT SIZES SHOWN ON PLANS ARE CLEAR INSIDE AIR STREAM DIMENSIONS.
 - CONTRACTOR SHALL COORDINATE ALL ELECTRICAL REQUIREMENTS FOR ALL HVAC BASED ON ACTUAL EQUIPMENT SELECTED PRIOR TO INSTALLATION.
 - CONTRACTOR SHALL COORDINATE EQUIPMENT WEIGHTS AND SUPPORTS BASED ON ACTUAL EQUIPMENT SELECTED.
 - ALL EXPOSED DUCTWORK SHALL BE AS SHOWN, DOUBLE WALL, INSULATED METAL, PRIMED FOR PAINTING. ALL CONCEALED DUCTWORK SHALL BE INSULATED METAL RECTANGULAR UNLESS OTHERWISE ALLOWED IN WRITING BY THE ENGINEER OF RECORD. COORDINATE FINAL FINISH WITH ARCHITECT.
 - COORDINATE WITH ALL TRADES FOR MATERIALS IN RATED AND PLENUM SPACES.
 - ALL EXHAUST FANS SCHEDULED TO BE AUTOMATICALLY CONTROLLED BY MECHANICAL AIR HANDLERS SHALL BE CONNECTED BY MEANS OF AN AUXILIARY RELAY. PROVIDE AUXILIARY RELAY AS NEEDED.
 - ALL SOURCE OF MECHANICAL INTAKE SHALL MAINTAIN 10 LINEAR FEET SEPARATION BETWEEN ANY SOURCE OF EXHAUST. CONTRACTOR IS RESPONSIBLE TO ADJUST DUCT LENGTH AS NEEDED.

- MECHANICAL PLAN KEY NOTES:**
- LOCATION OF DIGITAL THERMOSTAT CONTROL. INSTALL AND WIRE NEW 7-DAY PROGRAMMABLE THERMOSTAT. COORDINATE EXACT LOCATION WITH ARCHITECT AND OWNER PRIOR TO ROUGH-IN. PROVIDE LOCABLE COVER.
 - CEILING MOUNTED EXHAUST FAN. INTERCONNECT EXHAUST FAN WITH LIGHTS IN THIS ROOM. REFER TO ELECTRICAL LIGHTING PLAN. FAN SHALL BE SUSPENDED FROM STRUCTURE ABOVE. VERIFY EXACT LOCATION OF STRUCTURAL MEMBERS PRIOR TO INSTALLATION. PROVIDE WALL CAP EQUAL TO LOREN COOK WCR6-ALUM AND INSTALL BOTTOM OF WALL CAP AT SAME HEIGHT AS EXHAUST FAN.
 - CEILING MOUNTED EXHAUST FAN. INTERCONNECT EXHAUST FAN WITH T-STAT AND SET CUT-ON TEMP TO 80°F. FAN SHALL BE SUSPENDED FROM STRUCTURE ABOVE. VERIFY EXACT LOCATION OF STRUCTURAL MEMBERS PRIOR TO INSTALLATION. PROVIDE WALL CAP EQUAL TO LOREN COOK WCR6-ALUM AND INSTALL BOTTOM OF WALL CAP AT SAME HEIGHT AS EXHAUST FAN.
 - CONTRACTOR TO RUN CONDENSATE DRAIN FROM RTU 1 AND 2 TO SINK TAIL PIECE CONNECTION.
 - PROVIDE REMOTE TEMP SENSOR MOUNTED IN RETURN DUCT AND WIRE BACK TO T-STAT IN CHECK-IN ROOM.
 - EXTEND FULL SIZE SUPPLY & RETURN DUCTWORK FROM BOTH ROOFTOP UNITS TO SPACE. EXTEND AS SHOWN. ACOUSTICALLY LINE THE FIRST 10'-0" OF BOTH SUPPLY AND RETURN MAIN DUCTS.
 - SMOKE DETECTOR SHALL BE FURNISHED/INSTALLED BY MECHANICAL CONTRACTOR AND WIRED BY ELECTRICAL CONTRACTOR TO SHUT DOWN CORRESPONDING AIR CONDITIONING UNIT UNDER ALARM CONDITIONS. ALL WIRING SHALL BE IN CONDUIT PER N.E.C. SMOKE DETECTOR SHALL BE SYSTEM SENSOR MODEL DH100ACDCLP OR EQUAL.

1 MECHANICAL PLAN
1/4" = 1'-0"



- MECHANICAL ROOFTOP PLAN KEY NOTES:
- 1 PROVIDE AND INSTALL NEW ROOFTOP UNIT. PROVIDE FLEXIBLE CONNECTORS ON SUPPLY AND RETURN DUCT CONNECTIONS. SET OUTSIDE AIR AS INDICATED ON ROOFTOP UNIT SCHEDULES. MECHANICAL CONTRACTOR SHALL SCRIBE INTO UNIT POSITION OF OUTSIDE AIR DAMPER AND LABEL OUTSIDE AIR VOLUME AND PERCENT OF OUTSIDE AIR. TRANSITION AND CONNECT SUPPLY AND RETURN DUCTWORK FROM BELOW. COORDINATE ROUTING THROUGH STRUCTURAL TRUSSES AND OFFSET AS REQUIRED IN CURB SPACE.
 - 2 COORDINATE FINAL LOCATION OF EQUIPMENT WITH STRUCTURAL DRAWINGS. UNIT MUST BE AT LEAST 10' AWAY FROM EDGE OF ROOF.
 - 3 6"Ø EXHAUST DUCT UP THROUGH POOF WITH TALL CONE FLASHING, WEATHER SKIRT, AND VENT CAP. MAINTAIN A MINIMUM OF 10'-0" FROM ALL OUTSIDE AIR INTAKES AND TERMINATE 36" ABOVE ROOF.

1 MECHANICAL ROOFTOP PLAN
1/4" = 1'-0"