



1ST FLOOR WATER & GAS SUPPLY PLAN OVERALL 1/16" = 1'-0"

## **GENERAL NOTES**

- WATER HAMMER ARRESTORS SHALL BE PROVIDED AT ALL QUICK-CLOSING VALVES SUCH AS FLUSH VALVE, WASHING MACHINES, ICE MAKERS, REFRIGERATOR, DISHWASHERS, AND DRINKING FOUNTAINS. IT SHALL CONFORM TO ASSE1010.
- REFER TO THE UNIT PLANS FOR THE PIPING IN EACH UNIT. REFER TO THE ARCHITECTURAL DRAWING FOR PANTRY, FOOD PREP EQUIPMENT CALLOUTS.
- CONTRACTOR TO COORDINATE LOCATION OF PLUMBING RISER IN SHAFT WITH OTHER TRADES.
- REFER TO PLUMBING ISOMETRIC DRAWINGS FOR PIPE
- SIZES NOT LABELED IN PLANS. AS PER FLOW TEST REPORT IF STATIC PRESSURE IS LESS THEN 78 PSI BOOSTER PUMP IS REQUIRED, IF THESE
- PRESSURE CHANGES PLEASE CONTACT THE "EOR". PROVIDE INSULATION FOR ALL ICE MACHINE DRAIN TRAPS. ALL SHOWER AND SHOWER/TUBS SHALL HAVE PRESSURE
- BALANCING VALVES. BFP-2 TO BE PROVIDED FOR ALL ICE MACHINES NEAR COLD WATER SUPPLY.
- VIBRATION ISOLATOR TO BE GIVEN FOR BOOSTER PUMP & RECIRCULATION PUMPS
- CONTRACTOR TO SELECT ALL VALVES AND SUBMIT SPECS
- TO BASE4 FOR REVIEW.
- POOL CONTRACTOR TO SUBMIT POOL HEATER SPEC. TO BASE4 FOR REVIEW & GAS HEATING LOADS.
- POOL CONTRACTOR TO CONNECT POOL HEATING PIPES TO DHU BEFORE POOL HEATER".

IN PROGRESS





1 1ST FLOOR WATER & GAS SUPPLY PLAN - PART B 1/8" = 1'-0"

NOTE:

1. CONTRACTOR SHALL PROVIDE HOT BOX SPECIFICATIONS TO BASE4 FOR REVIEW. BASE4 SUGGESTS MAKE: "SAFETCOVER"

## WATER SUPPLY KEY NOTES Text PROVIDE AND INSTALL PRECISION PLUMBING PRODUCTS INC. #P1-500 TRAP PRIMER WITH 1/2" CW CONNECTION TO LINE INDICATED ON DRAWING. EXTEND OFF TOP OF LINE PER MANUFACTURER INSTRUCTIONS.(OR)

PROVIDE AND INSTALL THE PRO SET TRAP GUARD FLOOR DRAIN AS ALTERNATIVE.

- 1. WATER HAMMER ARRESTORS SHALL BE PROVIDED AT ALL QUICK-CLOSING VALVES SUCH AS FLUSH VALVE, WASHING MACHINES, ICE MAKERS, REFRIGERATOR, DISHWASHERS, AND DRINKING FOUNTAINS. IT SHALL CONFORM TO ASSE1010.
- REFER TO THE UNIT PLANS FOR THE PIPING IN EACH UNIT.
   REFER TO THE ARCHITECTURAL DRAWING FOR PANTRY,
- FOOD PREP EQUIPMENT CALLOUTS.
  4. CONTRACTOR TO COORDINATE LOCATION OF PLUMBING
- RISER IN SHAFT WITH OTHER TRADES.


  5. REFER TO PLUMBING ISOMETRIC DRAWINGS FOR PIPE
- SIZES NOT LABELED IN PLANS.

  6. AS PER FLOW TEST REPORT IF STATIC PRESSURE IS LESS THEN 78 PSI BOOSTER PUMP IS REQUIRED, IF THESE
- PRESSURE CHANGES PLEASE CONTACT THE "EOR".
  7. PROVIDE INSULATION FOR ALL ICE MACHINE DRAIN TRAPS.
- 8. ALL SHOWER AND SHOWER/TUBS SHALL HAVE PRESSURE BALANCING VALVES.
- 9. BFP-2 TO BE PROVIDED FOR ALL ICE MACHINES, COFFEE MAKERS, TEA BREAWERS AND SODA DISPENSORS NEAR
- COLD WATER SUPPLY.
- 10. VIBRATION ISOLATOR TO BE GIVEN FOR BOOSTER PUMP & RECIRCULATION PLIMPS
- RECIRCULATION PUMPS
  11. CONTRACTOR TO SELECT ALL VALVES AND SUBMIT SPECS
- TO BASE4 FOR REVIEW.


  12. POOL CONTRACTOR TO SUBMIT POOL HEATER SPEC. TO
- BASE4 FOR REVIEW & GAS HEATING LOADS.

  13. POOL CONTRACTOR TO CONNECT POOL HEATING PIPES TO
- DHU BEFORE POOL HEATER".

  14. ALL PUBLIC HAND WASHING SINKS THE HOT WATER
- TEMPERATUR SHALL NOT EXCEED 110°F TEMPERATURE,
  CONTRACTOR TO MAKES SURE THAT THE TEMPERATUR
  OR SINKS BE MAITIANED TO 110°F.



KEY PLAN - PART B



1 1ST FLOOR SANITARY & VENT PLAN OVERALL 1/16" = 1'-0"


## GENERAL NOTES


- I. REFER TO THE UNIT PLANS FOR THE PIPING IN EACH
- 2. REFER TO THE ARCHITECTURAL DRAWING FOR PANTRY EQUIPMENT CALLOUTS.
- 3. CONTRACTOR TO COORDINATE LOCATION OF PLUMBING RISER IN SHAFT WITH OTHER TRADES.


  4. REFER TO PLUMBING ISOMETRIC DRAWINGS FOR PIPE SIZES NOT LABELED IN PLANS.
- SIZES NOT LABELED IN PLANS.


  5. ALL STORM TO BE INSULATED VERTICALLY AND
- HORIZONTALLY.

  6. ALL SANITARY TO BE INSULATED ON ALL HORIZONTAL RUNS IN SLEEPING, PUBLIC AREAS, AND BACK-
- OFFICE AREAS.
  7. CONTRACTOR SHALL INSTALL PRESSURE RATED FITTINGS AND CLEANOUTSFOR ALL 8" SANITARY PIPE.












1 2ND FLOOR WATER & GAS SUPPLY PLAN 1/8" = 1'-0"

	WATER SUPPLY KEY NOTES	
Tag	Text	
1	PROVIDE AND INSTALL PRECISION PLUMBING PRODUCTS INC. #P1-500 TRAP PRIMER WITH 1/2" CW CONNECTION TO LINE INDICATED ON DRAWING. EXTEND OFF TOP OF LINE PER MANUFACTURER INSTRUCTIONS.(OR) PROVIDE AND INSTALL THE PRO SET TRAP GUARD FLOOR DRAIN AS ALTERNATIVE.	







SANITARY & VENT KEYNOTES (TYPICAL FLOOR)

Tag

Text

1 3/4" CONDENSATE RISER DOWN, SEE LOWER FLOOR PLANS FOR CONTINUATION.
ROUTE EACH CONDENSATE VERTICAL RISER TO CONNECT TO STORM LINE. GC
TO COORDINATE CONNECTION & ENSURE SLOPE OF 1/8"FT FOR THE HORIZONTAL
RUN OF PIPE. TYPICAL FOR ALL PTAC UNITS CONDENSATE DRAINAGE UNLESS
NOTED OTHERWISE.

